



ANNUAL SUMMARY OF MALAYSIAN

NOTICE TO MARINERS 2026





MALAYSIAN NOTICES TO MARINERS ANNUAL EDITION

2026

(Annual Edition 2025 is hereby cancelled)

CONTAINING

**Annual Notice No. 1 - 27
Temporary and Preliminary Notices pg No. 75**

Mariners are requested to inform The Hydrographer, National Hydrographic Centre, Bandar Armada Putra, Pulau Indah, 42009 PORT KLANG, Selangor Darul Ehsan, Malaysia. (Tel: 03-40160816), E-mail: nhc@navy.mil.my immediately upon the discovery of new dangers, changes or defects in aids to navigation and shortcoming in Malaysian charts or publications.

*DR. NAJHAN BIN MD SAID
Rear Admiral
The Hydrographer*

INDEX OF ANNUAL NOTICES

Serial	Subject	Page No
1.	General Information	1
2.	Availability of Notices to Mariners	1
3.	Malaysian Charts and Publications	2
4.	Cumulative List of Malaysian Notices to Mariners	9
5.	Notices to Mariners - Explanation of Terms	16
6.	Law and Regulations Pertaining to Navigations	16
7.	Confusion Between Bright Shore Light and Navigational Lights	16
8.	Prohibition of Anchoring in the Straits of Malacca and Singapore	17
9.	Straits of Malacca and Singapore - New and Amended Traffic Separation Schemes	17
10.	Straits of Malacca and Singapore - Rules for Vessels Navigation	24
11.	Straits of Malacca and Singapore - Description of The Mandatory Ship Reporting System (STRAITREP)	26
12.	Information About Radar Beacons	33
13.	Ship in Distress	35
14.	Maritime Rescue Coordinating Centre (MRCC) Malaysia	45
15.	Transit Corridors Within Area of Maritime Interest	46
16.	Piracy and Armed Robbery Reports	50
17.	Radio Navigational Warnings	54
18.	Firing Practice and Exercise Areas	55
19.	Information Concerning Submarine	57
20.	Caution With Regard to Ship Approaching Squadron Convoys and Other Warships at Sea	69
21.	Submarine Cables and Pipelines	70
22.	Development of Offshore Oil and Gas fields	71
23.	Caution with Regard to Reliability of Navigational Buoys	73
24.	Report of Shoal Obtained by Echo Sounding: Instructions Regarding Rendering Reports	73
25.	Temporary and Preliminary Notices	75
26.	Hydrographic Reports	93
27.	Hydrographic Note	94

1. GENERAL INFORMATION

- a. Notices to Mariners correcting MAL charts are issued by the National Hydrographic Centre (NHC) and should be inserted on the charts affected in water proof violet ink in case of Permanent Notice and in pencil in case of Temporary Notices.
- b. The capital (P) or (T) included in number of any notice denotes 'Preliminary' or 'Temporary' respectively.
- c. Geographical positions are referred to largest scale charts unless otherwise stated.
- d. Bearing is referred to the true compass and is reckoned clockwise from 000° (North) to 359°. Those relating to light are from seaward.
- e. Visibility of light is that of in clear weather.
- f. Depth is with reference to largest scale chart.
- g. Heights are above Mean High Water Spring.
- h. Nothing in these notices is to be taken as over ruling such general or local regulation as may be issued by Port Authority etc. to meet dangers or situation, which may arise, or to cover local conditions. While in the interest of the safety of shipping, the NHC takes every endeavor to include in the Hydrographic Publication correct and up to date details of all information pertaining to navigation in the coastal and of lying Malaysian Waters. It must be clearly understood that no liability whatsoever can be accepted by it for errors or failure to publish detail of such information.

2. AVAILABILITY OF NOTICES TO MARINERS

Malaysian Notices to Mariner are available at National Hydrographic Centre, Bandar Armada Putra, Pulau Indah, 42009 PORT KLANG, Selangor Darul Ehsan, Malaysia. (Tel: 03-40160816), E-mail: nhc@navy.mil.my or can be downloaded at NHC and RMN website. (<https://hydro.gov.my>)

Malaysian Notices to Mariners are also available at Marine Department of Malaysia, Marine Headquarters, PO Box 12, Shelter Road, 42007 Port Klang, Selangor. (Tel: +603-31629977), E-mail: inquiry@www.marine.gov.my/jlm or can be downloaded at <http://www.marine.gov.my>.

3. MALAYSIAN CHARTS AND PUBLICATIONS

The following charts and publications have been published and available as follows:

a. List of Malaysian Charts (MAL)

NO	CHART NO	TITLE	PUBLISHED	NEW EDITION	SCALE
(a)	(b)	(c)	(d)	(e)	(f)
1.	MAL 4508	LAUT CHINA SELATAN	31 Dec 1991	31 Dec 2009	1 : 3 500 000
2.	MAL 5	SEMENANJUNG MALAYSIA	31 Jan 1989	01 Oct 2008	1 : 1 250 000
3.	MAL 5123	SEKITAR PELABUHAN TANJUNG PELEPAS	31 Dec 1999	31 Dec 2019	1 : 30 000
4.	MAL 5128	SELAT JOHOR BARAT	31 Oct 1992	31 Dec 2019	1 : 27 500
5.	MAL 5129	PULAU PISANG - RAFFLES LIGHTHOUSE	01 Apr 2008	31 Dec 2019	1 : 75 000
6.	MAL 515	SELAT SINGAPURA	31 Mar 1993	31 Dec 2023	1 : 200 000
7.	MAL 5152	SEKITAR PELABUHAN BATU PAHAT	31 Dec 2017	-	1 : 50 000
8.	MAL 521	TANJUNG KELING - IYU KECIL	15 Dec 1989	31 Dec 2021	1 : 200 000
9.	MAL 5217	SEKITAR PELABUHAN SUNGAI UDANG - MELAKA	31 Aug 1994	31 Mar 2023	1 : 25 000
10.	MAL 5230	SEKITAR PERAIRAN KUALA LINGGI	01 Nov 2016	31 Mar 2023	1 : 50 000
11.	MAL 5239	SEKITAR PERAIRAN PORT DICKSON	31 Dec 2012	31 Dec 2020	1 : 30 000
12.	MAL 5255	SEKITAR PERAIRAN SELAT KLANG SELATAN	31 Dec 2019	-	1 : 25 000
13.	MAL 5257	TASIK PUTRAJAYA (PUTRAJAYA LAKE)	01 Dec 2016	-	1 : 7 500
14.	MAL 5259	PELABUHAN BARAT (WEST PORT)	31 Dec 2019	-	1 : 15 000
15.	MAL 5307	PELABUHAN UTARA (NORTH PORT)	15 Nov 1998	31 Dec 2019	1 : 15 000
16.	MAL 532	PERMATANG SEDEPA - TANJUNG KELING	30 Jun 1989	31 Dec 2012	1 : 200 000
17.	MAL 5321	SEKITAR PERAIRAN SELAT KLANG UTARA	31 Dec 2019	-	1 : 35 000
18.	MAL 54	PULAU JARAK - TANJUNG PIAI	01 Sep 2002	31 Oct 2006	1 : 500 000
19.	MAL 540	KEPULAUAN SEMBILAN - PELABUHAN KLANG	31 Dec 1993	15 Jul 2007	1 : 200 000
20.	MAL 5403	SUNGAI PERAK	30 Sep 1988	15 Dec 2024	1 : 25 000
21.	MAL 5410	SEKITAR PERAIRAN SUNGAI PERAK	15 Sep 1993	15 Dec 2024	1 : 35 000
22.	MAL 5416	TAMBATAN PANGKALAN LUMUT	01 Mar 1984	31 Dec 2015	1 : 10 000
23.	MAL 5417	PELABUHAN LUMUT	31 Dec 2023	-	1 : 10 000
24.	MAL 5419	SEKITAR PERAIRAN UTARA SELAT DINDING	01 Nov 1985	16 Sep 2016	1 : 12 500
25.	MAL 5425	SEKITAR PERAIRAN LUMUT	30 Dec 1991	31 Dec 2015	1 : 35 000
26.	MAL 5529	PELABUHAN PULAU PINANG	01 Mar 2006	31 Dec 2016	1 : 20 000
27.	MAL 553	PULAU PINANG - UJUNG TAMIANG	01 Sep 1992	15 Jul 2007	1 : 300 000

(a)	(b)	(c)	(d)	(e)	(f)
28.	MAL 5536	SEKITAR PERAIRAN PULAU PINANG	01 Dec 2016	-	1 : 60 000
29.	MAL 554	PULAU PINANG - KEPULAUAN SEMBILAN	15 Jun 1999	15 Aug 2005	1 : 200 000
30.	MAL 5622	SEKITAR PERAIRAN PELABUHAN LANGKAWI (KUAH)	30 Sep 1993	31 Dec 2010	1 : 40 000
31.	MAL 5625	SEKITAR PERAIRAN KUALA PERLIS	31 Oct 2015	-	1 : 10 000
32.	MAL 5630	SEKITAR PERAIRAN KUALA PERLIS - LANGKAWI	31 Dec 2010	-	1 : 50 000
33.	MAL 5631	SEKITAR PERAIRAN PELABUHAN LANGKAWI (TELUK EWA)	30 Sep 1991	31 Dec 2017	1 : 35 000
34.	MAL 565	KO TARUTAO - PULAU PINANG	31 Dec 1994	31 Dec 2018	1 : 300 000
35.	MAL 58	KO PHUKET - PULAU JARAK	31 Dec 1997	15 Jul 2004	1 : 500 000
36.	MAL 6	SABAH - SARAWAK	01 Oct 1991	30 Sep 2014	1 : 1 250 000
37.	MAL 6121	PENGERANG DEEPWATER TERMINALS	01 Oct 2024	-	1 : 10 000
38.	MAL 6124	SEKITAR PERAIRAN PENGERANG	30 Sep 2014	30 Sep 2020	1 : 30 000
39.	MAL 6125	SUNGAI SANTI - SUNGAI SEBINA	01 Sep 2002	15 Dec 2024	1 : 15 000
40.	MAL 6128	PELABUHAN JOHOR	01 Jun 1998	15 Jul 2016	1 : 10 000
41.	MAL 6130	SELAT JOHOR TIMUR	30 Nov 1992	01 Dec 2016	1 : 30 000
42.	MAL 6134	SEKITAR PERAIRAN TIMUR KUALA JOHOR	30 Nov 1992	01 Dec 2016	1 : 30 000
43.	MAL 6147	SEKITAR PERAIRAN TIMUR JOHOR	31 Dec 2017	31 Dec 2021	1 : 75 000
44.	MAL 6202	SEKITAR PERAIRAN SEDILI	01 Aug 2014	01 Oct 2024	1 : 50 000
45.	MAL 625	TELUK MAHKOTA - PULAU TIOMAN	01 Jun 1996	31 Dec 2010	1 : 200 000
46.	MAL 6257	SEKITAR PERAIRAN PULAU TIOMAN	31 Dec 1992	31 Dec 2021	1 : 50 000
47.	MAL 635	PULAU TIOMAN - KUANTAN	31 Dec 1996	15 Apr 2007	1 : 200 000
48.	MAL 6359	PELABUHAN KUANTAN	31 Dec 1991	31 Dec 2018	1 : 15 000
49.	MAL 6400	SEKITAR PERAIRAN KUANTAN	31 Dec 2018	-	1 : 35 000
50.	MAL 6416	SEKITAR PERAIRAN PELABUHAN KEMAMAN	30 Apr 1988	31 Jul 2017	1 : 25 000
51.	MAL 6436	PELABUHAN KERTIH	01 Oct 1999	15 Nov 2024	1 : 5 000
52.	MAL 6441	SEKITAR PERAIRAN PAKA - KERTIH	01 Jun 2000	15 Nov 2024	1 : 25 000
53.	MAL 645	KUANTAN – KUALA DUNGUN	30 Sep 2000	15 Apr 2007	1 : 200 000
54.	MAL 65	SELAT SINGAPURA - PULAU KAPAS	31 Dec 2008	-	1 : 500 000
55.	MAL 6522	KUALA TERENGGANU	01 Apr 2008	31 Dec 2025	1 : 10 000
56.	MAL 654	DUNGUN - PULAU REDANG	15 Dec 2001	31 Oct 2006	1 : 200 000
57.	MAL 655	KERTIH - KAWASAN GALIAN MINYAK TAPIS	31 Dec 1993	15 Apr 2007	1 : 250 000
58.	MAL 6554	PELABUHAN TOK BALI - SUNGAI SEMERAK	30 Nov 2020	-	1 : 5 000
59.	MAL 6558	TOK BALI	31 Mar 2023	-	1 : 20 000
60.	MAL 6603	SEKITAR PERAIRAN TOK BALI	31 Mar 2023		1 : 50 000

(a)	(b)	(c)	(d)	(e)	(f)
61.	MAL 664	PULAU REDANG - TUMPAT	15 Dec 2001	31 Dec 2010	1 : 200 000
62.	MAL 673	TUMPAT - SONGKHLA	15 Nov 1998	31 Dec 2009	1 : 240 000
63.	MAL 68	TERENGGANU - LAUT CHINA SELATAN	31 Dec 2008	-	1 : 500 000
64.	MAL 7139	TANJUNG BATU - PENDING	15 Nov 1998	31 Dec 2009	1 : 15 000
65.	MAL 7150	SEKITAR PERAIRAN TANJUNG PO	01 Dec 1989	31 Oct 2009	1 : 25 000
66.	MAL 7212	SARIKEI - BINTANGOR	30 Oct 1992	31 Dec 2009	1 : 20 000
67.	MAL 7213	TANJUNG MANIS - SARIKEI	30 Sep 1991	01 Oct 2008	1 : 20 000
68.	MAL 7215	KUALA RAJANG - TANJUNG MANIS	15 Apr 1989	01 Oct 2008	1 : 35 000
69.	MAL 723	TANJUNG BAYUNG - TANJUNG SIPANG	01 Dec 1996	31 Dec 2018	1 : 200 000
70.	MAL 7257	MUARA RAJANG	30 Oct 1989	03 Sep 2018	1 : 100 000
71.	MAL 731	TANJUNG SIPANG - TANJUNG SIRIK	15 Jul 1996	31 Dec 2007	1 : 200 000
72.	MAL 7317	PELABUHAN BINTULU	30 Sep 1988	31 Dec 2007	1 : 15 000
73.	MAL 7332	SEKITAR PERAIRAN PELABUHAN BINTULU	15 Aug 1989	01 Apr 2008	1 : 50 000
74.	MAL 740	KUALA RAJANG - KUALA MUKAH	15 Apr 1996	31 Dec 2008	1 : 200 000
75.	MAL 741	KUALA MUKAH - KUALA NIAH	01 Jun 1998	15 Nov 2002	1 : 200 000
76.	MAL 750	KUALA NIAH - MIRI	01 Oct 1998	31 Dec 2007	1 : 200 000
77.	MAL 751	KAWASAN GALIAN MINYAK BINTULU - GUGUSAN BETING PATINGGI ALI	31 Dec 1993	31 Oct 2009	1 : 250 000
78.	MAL 752	TG. BARAM - LABUAN	15 Dec 1997	31 Dec 2009	1 : 150 000
79.	MAL 754	KAWASAN GALIAN MINYAK TANJUNG BARAM - TANJUNG NOSONG	31 Dec 1993	15 Aug 2003	1 : 250 000
80.	MAL 761	TERUMBU SAJI – IBAN RIDGE	31 Dec 2025	-	1 : 250 000
81.	MAL 762	GUGUSAN BETING PATINGGI ALI	31 Oct 2009	31 Dec 2015	1 : 250 000
82.	MAL 765	SAPEH ESCARPMENT AND KAYAN HILL	31 Dec 2025	-	1 : 250 000
83.	MAL 7724	PULAU LAYANG - LAYANG	30 Apr 1996	31 Dec 2023	1 : 12 500
84.	MAL 773	IBAN RIDGE – BISAYA HILL	31 Dec 2025	-	1 : 250 000
85.	MAL 781	TERUMBU SEMARANG BARAT KECIL - TERUMBU PENINJAU	30 Oct 1988	31 Dec 2013	1 : 300 000
86.	MAL 8421	SEKITAR PERAIRAN SIPADAN - LIGITAN	01 Nov 1999	31 Dec 2009	1 : 50 000
87.	MAL 8425	SEKITAR PERAIRAN TAWAU	01 Nov 1999	30 Aug 2022	1 : 75 000
88.	MAL 8433	TERUSAN TANDO BULONG	01 Sep 2002	31 Dec 2007	1 : 25 000
89.	MAL 8434	TELUK SIBUKO UTARA	15 Dec 2001	31 Oct 2006	1 : 100 000
90.	MAL 8447	KUNAK	15 Dec 2024	-	1 : 20 000
91.	MAL 85	TG. LABIAN – PULAU TARAKAN	31 Dec 2025	-	1 : 500 000
92.	MAL 8502	PELABUHAN LAHAD DATU	31 Jul 1996	31 Dec 2017	1 : 20 000
93.	MAL 8503	TELUKAN LAHAD DATU (DARVEL BAY)	15 Sep 1998	15 Jul 2016	1 : 100 000
94.	MAL 8518	PELABUHAN LABUAN (VICTORIA HARBOUR)	31 Dec 1993	31 Dec 2021	1 : 15 000

(a)	(b)	(c)	(d)	(e)	(f)
95.	MAL 8523	SEKITAR PERAIRAN LABUAN	30 Sep 2014	-	1 : 20 000
96.	MAL 8553	PELABUHAN SANDAKAN	15 Jul 2016	-	1 : 20 000
97.	MAL 860	TERUMBU SEGAMA - PULAU LIGITAN	30 Sep 2014	-	1 : 200 000
98.	MAL 8608	KOTA KINABALU - TELUK SAPANGAR	15 Nov 1992	31 Dec 2007	1 : 25 000
99.	MAL 8617	SEKITAR PERAIRAN SANDAKAN - TELUKAN LABUK	01 Feb 2006	31 Jul 2017	1 : 100 000
100.	MAL 8621	PULAU TAGANAK - TERUMBU SEGAMA	31 Dec 2010	-	1 : 100 000
101.	MAL 864	LABUAN - KOTA KINABALU	31 Aug 1993	31 Dec 2007	1 : 225 000
102.	MAL 8645	PULAU JAMBONGAN - PULAU SILINGAN	01 Jun 1998	31 Dec 2008	1 : 100 000
103.	MAL 865	KOTA KINABALU - KEPULAUAN MANTANANI	31 Dec 2007	-	1 : 150 000
104.	MAL 8655	PELABUHAN KUDAT	31 Dec 2017	-	1 : 15 000
105.	MAL 871	KEPULAUAN MATANANI - PULAU BANGGI	01 Jun 1998	30 Sep 2014	1 : 150 000
106.	MAL 8715	PULAU BANGGI - PULAU JAMBONGAN	01 Aug 2014	31 Dec 2021	1 : 100 000
107.	MAL 872	KAWASAN GALIAN MINYAK KOTA KINABALU - KEPULAUAN MANTANANI	31 Dec 1993	31 Dec 2010	1 : 250 000
108.	MAL 88	KEPULAUAN MANTANANI – LAUT SULU	31 Dec 2025	-	1 : 500 000
109.	MAL 880	PULAU BALABAC - PULAU BANGGI	31 Aug 2011	31 Mar 2023	1 : 150 000
110.	MAL 884	TERUMBU UBI - TERUMBU LAKSAMANA	30 Sep 2014	-	1 : 250 000
111.	MAL 885	BETING MANTANANI - SELAT BALABAC	31 Dec 2013	-	1 : 250 000

b. List of Malaysian Nautical Publications

NO	PUBLICATIONS	TITLE	PUBLISHED & EDITION
1.	MAL 1	SYMBOLS AND ABBREVIATIONS USED ON MALAYSIAN CHARTS	Edition 2025
2.	MAL 2	MALAYSIAN CHARTS CATALOGUE	Edition 2026
3.	TIDE TABLE	MALAYSIA, SINGAPORE AND BRUNEI DARUSSALAM TIDE TABLES	Edition 2026

C. List of Malaysian Electronic Navigational Charts (MYENC)

NO	CELL NO	TITLE	EDITION
(a)	(b)	(c)	(d)
1.	MY2C0054	PULAU JARAK - TANJUNG PIAI	10
2.	MY2C0058	KO PHUKET - PULAU JARAK	8
3.	MY3C0540	KEPULAUAN SEMBILAN - PELABUHAN KLANG	7
4.	MY3C0553	PULAU PINANG - UJUNG TAMIANG	5
5.	MY3C0554	PULAU PINANG - KEPULAUAN SEMBILAN	7
6.	MY3C0565	KO TARUTAO - PULAU PINANG	8
7.	MY3C0625	TELUK MAHKOTA - PULAU TIOMAN	7
8.	MY3C0635	PULAU TIOMAN - KUANTAN	5
9.	MY3C0645	KUANTAN - DUNGUN	5
10.	MY3C0654	DUNGUN - PULAU REDANG	7
11.	MY3C0655	KERTIH - KAWASAN GALIAN MINYAK TAPIS	9
12.	MY3C0664	PULAU REDANG - TUMPAT	4
13.	MY3C0723	TANJUNG BAYUNG - TANJUNG SIPANG	2
14.	MY3C0731	TANJUNG SIPANG - TANJUNG SIRIK	4
15.	MY3C0740	KUALA RAJANG - KUALA MUKAH	4
16.	MY3C0741	KUALA MUKAH - KUALA NIAH	1
17.	MY3C0750	KUALA NIAH - MIRI	5
18.	MY3C0751	KAWASAN GALIAN MINYAK TANJUNG BARAM - GUGUSAN BETING PATINGGI ALI	9
19.	MY3C0754	KAWASAN GALIAN MINYAK TG. BARAM - TG. NOSONG	5
20.	MY3C0762	GUGUSAN BETING PATINGGI ALI	2
21.	MY3C7257	MUARA RAJANG	1
22.	MY3C0781	TERUMBU SEMARANG BARAT KECIL - TERUMBU PENINJAU	4
23.	MY3C0860	TERUMBU SEGAMA - PULAU LIGITAN	4
24.	MY3C0864	LABUAN - KOTA KINABALU	7
25.	MY3C0865	KOTA KINABALU - KEPULAUAN MANTANANI	4
26.	MY3C0871	KEPULAUAN MANTANANI - PULAU BANGGI	7
27.	MY3C0872	KAWASAN GALIAN MINYAK KOTA KINABALU - KEPULAUAN MANTANANI	2
28.	MY3C0880	PULAU BALABAC - PULAU BANGGI	7
29.	MY3C0884	TERUMBU UBI - TERUMBU LAKSAMANA	3
30.	MY3C0885	BETING MANTANAN I- SELAT BALABAC	1
31.	MY3C8434	TELUK SIBUKO UTARA	4
32.	MY3C8503	TELUKAN LAHAD DATU	3
33.	MY3C8617	SEKITAR PERAIRAN SANDAKAN - TELUKAN LABUK	5
34.	MY3C8621	PULAU TAGANAK - TERUMBU SEGAMA	4
35.	MY3C8645	PULAU JAMBONGAN - PULAU SILINGAAN	2
36.	MY3C8715	PULAU BANGI - PULAU JAMBUNGAN	3

(a)	(b)	(c)	(d)
37.	MY4A5403	SUNGAI PERAK	2
38.	MY4C5123	PELABUHAN TANJUNG PELEPAS	4
39.	MY4C5129	PULAU PISANG - RAFFLES HOUSE	1
40.	MY4C5152	PELABUHAN BATU PAHAT	1
41.	MY4C5217	SEKITAR PERAIRAN PELABUHAN SUNGAI UDANG – MELAKA	8
42.	MY4C5230	PERAIRAN KUALA LINGGI	5
43.	MY4C5239	SEKITAR PERAIRAN PORT DICKSON	7
44.	MY4C5255	SEKITAR PERAIRAN SELAT KLANG SELATAN	1
45.	MY4C5321	SEKITAR PERAIRAN SELAT KLANG UTARA	1
46.	MY4C5403	SUNGAI PERAK	4
47.	MY4C5410	SEKITAR PERAIRAN SUNGAI PERAK	3
48.	MY4C5425	SEKITAR PERAIRAN LUMUT	9
49.	MY4C5536	PERAIRAN PULAU PINANG	4
50.	MY4C5550	SEKITAR PERAIRAN TANJUNG DAWAI	2
51.	MY4C5622	SEKITAR PELABUHAN LANGKAWI (TELUK EWA)	2
52.	MY4C5630	KUAH - KUALA PERLIS	2
53.	MY4C5631	SEKITAR PERAIRAN PELABUHAN LANGKAWI (TELUK EWA)	6
54.	MY4C6130	SELAT JOHOR TIMUR	3
55.	MY4C6147	SEKITAR PERAIRAN TIMUR JOHOR	1
56.	MY4C6202	SEKITAR PERAIRAN SEDELI	1
57.	MY4C6257	SEKITAR PERAIRAN PULAU TIOMAN	3
58.	MY4C6400	SEKITAR PERAIRAN KUANTAN	3
59.	MY4C6416	SEKITAR PERAIRAN PELABUHAN KEMAMAN	5
60.	MY4C6441	SEKITAR PERAIRAN PAKA - KERTIH	3
61.	MY4C6603	SEKITAR PERAIRAN TOK BALI	2
62.	MY4C7146	TANJUNG PO KE PENDING	1
63.	MY4C7215	KUALA RAJANG - TANJUNG MANIS	1
64.	MY4C7332	SEKITAR PERAIRAN PELABUHAN BINTULU	5
65.	MY4C8421	SEKITAR PERAIRAN SIPADAN - LIGITAN	2
66.	MY4C8425	SEKITAR PERAIRAN TAWAU	5
67.	MY4C8504	PERLABUHAN SIPITANG	1
68.	MY4C8608	KOTA KINABALU - TELUK SEPANGGAR	8
69.	MY5A5123	PELABUHAN TANJUNG PELEPAS	5
70.	MY5A5217	PELABUHAN SUNGAI MELAKA	5
71.	MY5A5622	TANJUNG MALAI	2
72.	MY5A5631	PELABUHAN TELUK EWA	4
73.	MY5A6359	SUNGAI KUANTAN	5
74.	MY5A6416	PELABUHAN KEMAMAN	4

(a)	(b)	(c)	(d)
75.	MY5A7150	PULAU LAKEI	2
76.	MY5A8425	TAWAU	4
77.	MY5A8608	KOTA KINABALU	5
78.	MY5B5631	TELAGA HARBOUR MARINA	4
79.	MY5C5239	PERLABUHAN PORT DICKSON	1
80.	MY5C5259	PELABUHAN BARAT (WEST PORT)	2
81.	MY5C5307	PELABUHAN UTARA (NORTH PORT)	5
82.	MY5C5416	TAMBATAN PANGKALAN LUMUT	13
83.	MY5C5417	PELABUHAN LUMUT	2
84.	MY5C5419	SEKITAR PERAIRAN UTARA SELAT DINDING	6
85.	MY5C5529	PELABUHAN PULAU PINANG	8
86.	MY5C5617	PANGKALAN TLDM LANGKAWI	1
87.	MY5C5625	SEKITAR PERAIRAN KUALA PERLIS	1
88.	MY5C6202	TANJUNG SEDILI	1
89.	MY5C6359	PELABUHAN KUANTAN	4
90.	MY5C6436	PELABUHAN KERTIH	3
91.	MY5C6522	KUALA TERENGGANU	1
92.	MY5C6537	PELABUHAN TERENGGANU SILICA	1
93.	MY5C6558	TOK BALI	2
94.	MY5C7134	TANJUNG BAKO - KUCHING	2
95.	MY5C7139	TANJUNG BATU - PENDING	4
96.	MY5C7212	SARIKEI - BINTANGOR	2
97.	MY5C7339	PELABUHAN BINTULU (SAMALAJU PORT)	1
98.	MY5C7724	PULAU LAYANG – LAYANG	4
99.	MY5C8447	KUNAK	1
100.	MY5C8502	PELABUHAN LAHAD DATU	2
101.	MY5C8518	PELABUHAN LABUAN	4
102.	MY5C8523	SEKITAR PERAIRAN LABUAN	3
103.	MY5C8553	PELABUHAN SANDAKAN	2
104.	MY5C8608	PELABUHAN TELUK SEPANGGAR	1
105.	MY5C8655	PELABUHAN KUDAT	1
106.	MY6A6125	SEBANA COVE MARINA	4
107.	MY6A6554	SUNGAI SEMERAK	1
108.	MY6A7139	PENDING	2
109.	MY6A7212	BINTANGOR	2
110.	MY6A7724	TERUSAN TIMUR	3
111.	MY6A8655	DERMAGA PELABUHAN KUDAT	1
112.	MY6B5123	PELABUHAN TANJUNG PELEPAS	2
113.	MY6B5411	JETI VALE, PERAK	2
114.	MY6B5526	PELABUHAN PULAU PINANG	2

(a)	(b)	(c)	(d)
115.	MY6B6122	PELABUHAN TANJUNG PENGERANG	3
116.	MY6B6129	PELABUHAN TANJUNG LANGSAT	3
117.	MY6B6130	SELAT TEBRAU - JOHOR TIMUR	2
118.	MY6C6125	SUNGAI SANTI - SUNGAI SEBINA	4
119.	MY6C6522	KUALA TERENGGANU SUPPLY BASE	1
120.	MY6C6554	PELABUHAN TOK BALI	1
MALACCA AND SINGAPORE STRAIT MSS - ENC CELL			
1.	MS3IK2EB	IYU KECIL TO EAST BANK	9
2.	MS30F2TT	ONE FATHOM BANK TO TANJUNG TUAN	7
3.	MS3RS2FC	RALEIGH SHOAL TO FAIR CHANNEL	9
4.	MS4BR2JS	BUFFALO ROCK TO JOHOR SHOAL	11
5.	MS4IK2RL	IYU KECIL TO RAFFLES LIGHT HOUSE	10
6.	MS4NS2EB	NONGSA TO EAST BANK	10

4. CUMULATIVE LIST OF MALAYSIAN NOTICES TO MARINERS

List of charts published by National Hydrographic Centre and Permanent Correction to charts promulgated through Notices to Mariners up to date **31st Dec 2025 (NTM 12 of 2025)**.

BIL	NO CARTA	EDISI	PEMBETULAN	JUMLAH
(a)	(b)	(c)	(d)	(e)
1.	MAL 4508	31 Dec 2009	2010 -51-52-77-78-141-167-168- 2011 -51-75-88-89-90-92-104-105-106-143-144- 2012 -34-52- 2013 -78-97-116-126-149-175-176- 2014 -26-38-80-111-112-130-141- 2015 -26-39-54-106-107-108-167-207- 2016 -48(T)-87-123-175-206- 2017 -76-123- 2018 -44	50
2.	MAL 5	01 Oct 2008	2013 -43-79-98(T)-99(T)-107-158-177-178-179-191- 2014 -27-28(T)-39-40-52(T)-64-83-84-88-101-102-131-132-146- 2015 -40-41-70-90-109-151-198(T)-213(T)-214-215(T)- 2016 -27(T)-28(T)-48(T)-88-107(T)-108(T)-124-138-186-192-207-208(T)-209-226-227-228- 2017 -26(T)-124-149-182-201-202-215-216- 2018 -45-61(T)-76(T)-93(T)-96(T)-128-129-165(T)-182-196-204-206(T)-222-263(T)-264(T)-277- 2019 -28-38-66(T)-73-86-104(T)-116-117-118-128(T)-129(T)-144-145-146-153(T)-154(T)-156(T) 157(T)223-235-244(T)-255-265- 2020 -28-33(T)-35(T)-46-47-54-55-58(T)-67-68-69-77(T)-121-134(T)-135(T)-164-203- 2021 -34(T)-37-59-124-135-166-192-195- 2022 -47-91-144-145-180-181- 2023 -35-64-128-129(T)-143-155-157-161-179-182-183-202- 2024 -29-97-114-137(T)-151-152-163(T)-175-176-199-200-213-219(T)-227- 2025 -50-65-66-73(T)-82-83-115-133-140-186-209-286-288-291	167
3.	MAL 5123	31 Dec 2019	2020 -56(T)-64-72-97-106(T)-123-150-212(T)- 2021 -71-167-214-233- 2022 -29-35-48--108(T)-122-174(T)- 2023 -68-109(T)-180-201- 2024 -28-29-42-48(T)-114-201-202-212- 2025 -51-53-57(T)-58(T)-68-69-134-210-240-282	40
4.	MAL 5128	31 Dec 2019	2023 -68-109(T)- 2025 -67-211	4
5.	MAL 5129	31 Dec 2019	2020 -56(T)-97-106(T)-122-123-150-212(T)- 2021 -71-168-233- 2022 -35-108(T)-122-174(T)- 2023 -66-76-99-109(T)-180-201- 2024 -28-29-42-44-48(T)-114-116-153-201-212- 2025 -28-51-53-58(T)-68-84-133-134-147-178-240-282	42
6.	MAL 515	31 Dec 2023	2024 -29-43-44-84(T)-98-104-114-115-143(T)-151-155-175-185-199-201-228-254(T)-260- 2025 -28-29-30-42(T)-43-51-57(T)-69-85-107-108-133-147-178-257-283-284	35
7.	MAL 5152	31 Dec 2017	2017 - 2019 -54-157(T)- 2020 -47- 2021 -166- 2023 -46- 2024 -114-178- 2025 -109	8
8.	MAL 521	31 Dec 2021	2022 -29-36-108(T)-122-144-166- 2023 -46-77-117-118-123-142-201- 2024 -29-44-114-152-178-179-180-261- 2025 -28-57(T)-69-109-133	26
9.	MAL 5217	31 Mac 2023	2023 -117-118-181- 2024 -114	4

(a)	(b)	(c)	(d)	(e)
10.	MAL 5230	31 Mac 2023	2023 -100-118-156-181- 2024 -114- 2025 -140-148-149	8
11.	MAL 5239	31 Dec 2020	2015 -132-133- 2016 -72-223- 2018 -49-281- 2020 -29- 2021 -60-86-193- 2022 -37-50- 2024 -114-144(T)-243- 2025 -285	16
12.	MAL 5255	31 Dec 2019	2019 - 2021 -109-150(T)-170-177(T)- 2022 -97(T) 136(T)- 2023 -78-222- 2024 -117-165(T)- 2025 -31-32-37-142(T)-159-193(T)	16
13.	MAL 5257	01 Dec 2016		
14.	MAL 5259	31 Dec 2019	2019 - 2020 -204- 2021 -150(T)- 2022 -136(T)- 2023 -47-78- 2024 -165(T)- 2025 -31-32-37-93(T)-142(T)159-163(T)-193(T)	13
15.	MAL 5307	31 Dec 2019	2019 - 2020 -205- 2021 -171-194- 2022 -92- 2023 -28-47-184- 2024 -87(T)-211- 2025 -32-150-179	12
16.	MAL 532	31 Dec 2012	2015 -132-133-149-150(T)-152-198(T)-212-215(T)- 2016 -26(T)-72-88-108(T)-209-214-223-227- 2017 -138(T)-149-204- 2018 -37(T)-38(T)-49-50-62(T)-76(T)-106-119(T)-128-131-149-204-249-277-281- 2019 -66(T)-100-117-121-128(T)-129(T)-153(T)-154(T)-182(T)-196-244(T)-255- 2020 -44-58(T)-67-68-77(T)-83-99-121-134(T)-135(T)- 2021 -60-86-109-124-150(T)-151(T)-154(T)- 193 - 2022 -50-58(T)-67-81(T)-97(T)-107- 2023 -78-117-118-129(T)-156-161-222- 2024 -29-114-117-137(T)-144(T)-152-163(T)-165(T)-200-213-214-227-229-243-262- 2025 -37-140-148-149-193(T)-285	92
17.	MAL 54	31 Oct 2006	2013 -119-151-161-162-180-193(T)- 2014 -28(T)-41-67-90(T)-150(T)- 2015 -41-55-71-72-90-93-94(T)-95-111-112(T)-147-148-149-150(T)-152-198(T)-199(T)-215(T)- 2016 -27(T)-71-88-108(T)-125-209-214-215- 2017 -111-138(T)-182-202-217- 2018 -38(T)-50-62(T)-63-71-76(T)-93(T)-96(T)-204-249-263(T)-277- 2019 -30-66(T)-77-100-117-121-128(T)-129(T)-153(T)-154(T)-155(T)-156(T)-170-172-177-223-244(T)-255- 2020 -28-45-58(T)-67-68-69-77(T)-121-134(T)-135(T)-203- 2021 -37-38-39-40-62-63-64-109-124-154(T)-203(T)-234- 2022 -50--58(T)-91-107-144-166-182- 2023 -46-123-129(T)-161-222- 2024 -29-44-114-137(T)-152-164(T)-200-201-213-214-227-246(T)- 2025 -109-133-140-149-	122
18.	MAL 540	15 Jul 2007	2014 -28(T)- 2015 -41-90-198(T)-199(T)-215(T)- 2016 -27(T)-30-49-88-108(T)-209-215- 2017 -68-111-112-138(T)-185- 2018 -38(T)-62(T)-76(T)-119(T)-204-254-263(T)-277- 2019 -32-66(T)-100-121-129(T)-154(T)-155(T)-172-177-182(T)-196-197-244(T)-255- 2020 -28-45-58(T)-67-68-69-77(T)-99-121-148-203- 2021 -37-39-40-62-63-150(T)-234- 2022 -67-91-182- 2023 -78- 2024 -29-114-137(T)-164(T)-165(T)-177-200-213-227-229-230-246(T)-247(T)-262- 2025 -37	76
19.	MAL 5403	15 Dec 2024		
20.	MAL 5410	15 Dec 2024		
21.	MAL 5416	31 Dec 2015	2016 -141-178(T)-179(T)- 2017 -129-151- 2018 -163(T)- 2019 -33-127(T)- 2021 -179(T)-180(T)- 2023 -48-83-126- 2024 -61-67(T)- 2025 -52-135-292	18
22.	MAL 5417	31 Dec 2023		
23.	MAL 5419	16 Sep 2016	2016 -141-178(T)-179(T)- 2018 -163(T)-253- 2019 -33-127(T)- 2021 -179(T)-180(T)- 2023 -48-83-126- 2024 -231- 2025 -52-151-292	15
24.	MAL 5425	31 Dec 2015	2016 -141-178(T)-179(T)-180-231- 2017 -129-151- 2018 -51-163(T)-253- 2019 -127(T)-147-206(T)- 2021 -139(T)-179(T)-180(T)- 2022 -33(T)-56(T)-68- 2023 -48-79-82-83-101-126- 2024 -61-67(T)-71(T)-88(T)-186-232-263- 2025 -135-292	34
25.	MAL 5529	31 Dec 2016	2017 -61-87-152-205- 2018 -197- 2019 -34-79-148- 2020 -30- 2024 -80- 2025 -290	9
26.	MAL 553	15 Jul 2007	2015 -56-57-58-118-145-184- 2016 -27(T)-30-49-182- 2017 -35-111-185- 2018 -51-150-224-253-254-282- 2019 -79-104(T)- 2020 -33(T)-185- 2021 -39-62-152-234- 2022 -70(T)-172- 2024 -29-88(T)-114-186-203-246(T)- 2025 -152-185-186-290	39
27.	MAL 5536	01 Dec 2016	2017 -78-87-130-2018-28-150-197-224-264(T)- 2019 -34-38-79-86-103(T)-104(T)- 2020 -30-33(T)-185- 2021 -87-216-217-220(T)-223(T)- 2025 -54-110-152-186-209-275(T)-276(T)-286-290-298(T)-299(T)	34
28.	MAL 554	15 Aug 2005	2015 -56-96-184- 2016 -27(T)-30-49-178(T)-179(T)-183-231- 2017 -35-78-111-185- 2018 -150-224-264(T)- 2019 -38-79-80-86-103(T)-104(T)-206(T)- 2020 -30-33(T)- 2021 -39-62-87-139(T)-152-217-220(T)-223(T)- 2022 -33(T)-56(T)-68-70(T)-172- 2023 -82-101- 2024 -88(T)-114-186-203- 2025 -54-152-185-186-209-275(T)-276(T)-286-290-292-298(T)-299(T)	57

(a)	(b)	(c)	(d)	(e)
29.	MAL 5622	31 Dec 2010	2011-58-59-2013-33-153-182-2014-91-105-114(T)-2016-31-74-75-89-168-2018-225-2021-61-176-2022-146-154(T)-155(T)- 2023-88(T)-105-128-165(T)-187	24
30.	MAL 5625	31 Oct 2015	2016-184(T)-2017-153-2018-164(T)-2021-41- 2025 - 212	5
31.	MAL 5630	31 Dec 2010	2011-59-165-2013-153-2016-60-74-75-89-168-184(T)-2017-131-153-2018-164(T)-225-2021-41-2022-146-154(T)-155(T)- 2023-88(T)-105-128-165(T)-187-2025 - 212	23
32.	MAL 5631	31 Dec 2017	2018-151-2019-149-2024-163(T)-2025-70-136-291	6
33.	MAL 565	31 Dec 2018	2019-38-79-86-103(T)-104(T)- 2020-33(T)-55-185-2021-41-59-61-107-121-216-217-223(T)-2022-38-2023-29-128-165(T)-187-2024-29-114-219(T)-2025-66-152-186-194(T)- 209-286-287-290-291	33
34.	MAL 58	15 Jul 2004	2005-55-2006-64-150-2007-79-2008-69-175-176-209-2009-73-103-162-2010-54-2011-129(T)-163(T)-199-2012-40-54-59(T)-114-115-167-2013-98(T)-111-177-180-2014-92-114(T)-135(T)-2015-39-41-57-58-118-145-2016-27(T)-30-60-75-2017-30(T)-2018-51-254-282-2019-103(T)-104(T)-2020-33(T)-55-148-185-2021-39-62-107-121-234-2022-38-70(T)-167-172-2023-29-128-2024-29-114-203-219(T)-246(T)- 2025-66-186-287-291	68
35.	MAL 6	30 Sep 2014	2014-126-127-136-137-2015-28-74-75-76-77-78-119-137-138-157-202-203-214-216-219(T)-2016-34(T)-35-50-51-128-129-206-216-2017-44(T)-62-76-113-123-124-132-133-139(T)-189-206-218-219-2018-29-55-75-77(T)-87-89-97(T)-152-153-166(T) -182-183-226-227-228-256-257-283-2019-57-58-59-81-150-151-239-251-2020-73-165-166-172(T)-2021-50(T)-88-89-111-218-235-2022-30-125(T)-130-147-149-167-183-2023-31-49-143-158-212-2024-30-97-151-156-160-204-232-233-234-250(T)-2025-33-55-83-133-153-154 -214-263-265-293-295	104
36.	MAL 6121	01 Okt 2024		
37.	MAL 6124	30 Sep 2020	2015-91(T)- 113(T)-114(T)-210-2016-26(T)-32(T)-76-110-111-127-130-139-185-217-233-2017-31-35-43(T)-96(P)-118(T)-119(T)-134-137(T)- 140(P)-154-226(T)-2018-30-36(T)-47-63-72-139(T) -178 -179-198-250-262-289(T)-2019-64-82-173-217-218-2020-44-81-167-186-2021-90-122-169-195-215-2022-49-148-168-2023-55(T)-65-104-203-2024-44-62-85(T)-98-143(T)-151-154-155-185-187-199-205-206-228-254(T)-2025-42(T)-43-53-71(T)-133-217(T)-133 - 241- 260	83
38.	MAL 6125	15 Dec 2024		
39.	MAL 6128	15 Jul 2016	2017-135-2023-204-2024-207-2025-181-218(T)-242	6
40.	MAL 6130	01 Dec 2016	2017-88-126-135-167-169-170-186-220-221-2018-88-107-2019-60-2020-65-186-2022-184-2023-65-204-2024-99-151-2025-67-134-218(T)-242	23
41.	MAL 6134	01 Dec 2016	2017-63-88-140(P)-167-169-170-178(T)-186-221-2018-30-47-52-63-88-107-108-162(T)-179-198-250-2019-60-82-173-180(T)-217-218-252-2020-167-186-2021-136(T)-169-2022-148-185-2023-65-2024-62-81-98-99-151-175-181-206-235-2025-53-122-134-180-258-259-260-294	51
42.	MAL 6147	31 Dec 2021	2022-49-168-2023-55(T)-104-203-205-2024-44-84(T)-97-98-104-115-143(T)-151-154-155-175-185-199-205-228-236-254(T)-260-2025-29-30-42(T)-43-85-108-133-217(T)-241-257-283	35
43.	MAL 6202	01 Okt 2024		
44.	MAL 625	31 Dec 2010	2011-45(T)-70-2012-41(T)-96-118-125-2013-74-150-2014-131-142-2015-30(T)-73-98-120-121-134-186-200-2016-76-2017-124-2018-63-95(T)-180-234(T)-2019-41(T)-265-136(T)-2021-91-92-127(T)-175-195--2022-42(T)-69-187(T) -188(T)-2023-69(T)-124-143-164(T)-188(T)-202-2024-44-123-140-151-175-199-249(T)-264-2025-40(T)- 73(T)-94(T)115-133-187-288	57
45.	MAL 6257	31 Dec 2021	2022-42(T)-69-117-187(T) -2023-124-164(T)-188(T)2025-288	8
46.	MAL 635	15 Apr 2007	2007-91-129-2010-117(T)-2011-45(T)-70-2012-41(T)-73-96-118-125-128-2013-34-2015-73-120-134-135-200-201-214-2016-33-163-2017-222-2018-90-180-184(T)-229-288-2019-83-122-265-2020-171(T)-208-2021-93-127(T)-2022-42(T)-69-187(T) 2023-69(T)-89(T)-123-125-2024-232-271(T)-2025-82-88	46
47.	MAL 6359	31 Dec 2018	2019-101-198-221-2020-84-110(T)-129-149-196(T)-197(T)-206-209-210-2021-42-125(T)-126(T)-140(T)-155(T)-172-222(T)-2022-118-133(T)-186-2023-36-80-87(T)-185-2024-86(T)-125-129(T)-145(T)-161-162-2025-188	32

(a)	(b)	(c)	(d)	(e)
48.	MAL 6400	31 Dec 2018	2019 -84-101-198-221- 2020 -70(T)-76-110(T)-129-149-187-196(T)-206-207-209- 2021 -42-110-125(T)-140(T)-222(T)- 2022 -57(T)-93-133(T)-186- 2023 -36-80-185- 2024 -129(T)-130(T)-161	27
49.	MAL 6416	31 Jul 2017	2018 -53-54-237(T)-238(T)-284- 2019 -106(T)-240-267-270(T) 2020 -34(T)-75-88(T)-100-103-193(T)-194(T)-195(T)-213(T)-214(T)-215(T)- 2021 -32-33-43-80(T)-99-200(T)-221(T)-237(T)- 2022 -39-94(T)-96(T)-110(T)-119-121-135(T)-153- 2023 -127-147-162(T)-167(T)- 2024 -33(T)-50(T)-82-100-118-157-270(T)- 2025 -38-155	49
50.	MAL 6436	15 Nov 2024	2025 -122 - 246(T)- 269	3
51.	MAL 6441	15 Nov 2024	2024 -267- 2025 -41(T)-122-123 – 246(T)- 269	6
52.	MAL 645	15 Apr 2007	2007 -82-91-107-125- 2008 -40-197- 2010 -126- 2011 -184(T)-203(T)-209(T)- 2012 -42(T)-80-85-103- 2013 -26-49-50- 2014 -101-132- 2015 -213(T)-218- 2016 -28(T)-53-79- 2017 -95(T)-188-201- 2018 -54-61(T)-90-94(T)-129-155-182-230-236(T)-288- 2019 -35-107(T)-179- 2020 -70(T)-76(T)-100-107(T)-109(T)-110(T)-126-128-129-187-195(T)-196(T)-206-207-209-215(T)- 2021 -33-80(T)-93-99-140(T)-195-200(T)- 2022 -57(T)-93-94(T)-96(T)-135(T)-153- 2023 -37-50-148(T)-160-207-213(T)- 2024 -33(T)-63-100-127-130(T)-157-189(T)-190(T)-210-232-244-252(T)-267	88
53.	MAL 65	31 Dec 2008	2010 -72-78-79-105-117(T)-152-182- 2011 -34-91-130-184(T)- 2012 -37-73-80-96-124-125-128- 2013 -26-27-28-43-99(T)-118- 2014 -39-42-64-101-103-131-132-142- 2015 -30(T)-73-98-120-122-134-135-201-213(T)-214- 2016 -28(T)-33-124-212- 2017 -29-124-176(T)-188-201-203-215-222- 2018 -61(T)-129-182-222-234(T)-236(T)-288- 2019 -146-171-235-265- 2020 -54-100-187-207- 2021 -90-175-195- 2022 -47-169- 2023 -30-64- 69 (T)-143-164(T)-188(T)-202-207- 2024 -44-63-84(T)-97-104-123-124-151-175-199-232- 2025 -73(T)-82-83-115-133-288	99
54.	MAL 6522	31 Dec 2025	New Edition 2025	
55.	MAL 654	31 Oct 2006	2008 -98-182-200-226- 2009 -147- 2010 -75-126-127- 2011 -184(T)- 2012 -80-124-179- 2013 -27-36-104-120- 2017 -201- 2018 -73-156-206(T)-207(T)-222- 2019 -199-268- 2020 -31-54-192(T)- 2021 -30-70-94-100(T)-123- 2022 -51-109(T)-169- 2023 -38-67-213(T)-49(T)- 2024 -126-127-128-142(P)-190(T)-244- 2025 -83-137-184 -261	49
56.	MAL 655	15 Apr 2007	2007 -166- 2008 -67-211(T)- 2009 -183- 2010 -52-80-91- 2011 -184(T)- 2012 -42(T)-55-61(T)-71-80-124- 2013 -27-28-29-37-43- 2014 -27-39-52(T)-64-88-102-146- 2015 -123- 2016 -79-124- 2017 -201-215- 2018 -156-182-222- 2019 -107(T)-179-235- 2020 -54-107(T)-109(T)-126-128- 2020 -108- 2022 -47-169-180- 2023 -37-50-81-148(T)-155-160-182-183-208-213(T)- 2024 -63-127- 2025 -83 - 237	59
57.	MAL 6554	30 Nov 2020		*
58.	MAL 6558	31 Mac 2023	2024 -70(T)-83- 2025 -59(T)-117	4
59.	MAL 6603	31 Mac 2023	2023 -223-225(T) 2024 -70(T)-83-182- 2025 -59(T)-78(T)-116-117-300(T)	9
60.	MAL 664	31 Dec 2010	2011 -204(T)- 2012 -176-179- 2013 -27-36-104-121-158-179- 2014 -31-40- 2015 -70-154- 2016 -48(T)-207-208(T)-218-228- 2017 -26(T)-201- 2018 -73-165(T)-200-206(T)-265(T)-266(T)- 2019 -42(T)-63-105(T)-152-175-178-271(T)-272(T)- 2020 -35(T)-46-57-85-87(T)-168- 2021 -34-45-51(T)-72-94-123-137- 2022 -28-31-52-109(T)- 2023 -67-155-223-225(T)- 2024 -34(T)-49(T)-66-70(T)-83-103-128-182- 2025 -60(T)-72(T)-116-137-184-192(T)-243-300(T)	71
61.	MAL 673	31 Dec 2009	2011 -204(T)- 2013 -121- 2017 -201- 2018 -157- 2020 -85-101- 2021 -45-51(T)- 2022 -28-31-52- 2024 -34(T)-66-103- 2025 -60(T)-243	15
62.	MAL 68	31 Dec 2008	2009 -183-191- 2010 -52-75-80-91-127- 2012 -55-71-127-176-179- 2013 -28-29-36-43-104-107-121-158-178-179-191- 2014 -27-31-39-40-52(T)-64-84-88-102-146- 2015 -40-70-109-123- 2016 -48(T)-80(T)-164-186-193-207-208(T)-228- 2017 -26(T)-201-215-216- 2018 -45-73-156-165(T)-206(T)-222-285- 2019 -73-105(T)-123-144-145-178-235-271(T)- 2020 -35(T)-46-54-164- 2021 -29-34-72-108-137-192- 2022 -28-31-47-51-52-109(T)-145-169-180-181- 2023 -35-67-155-157-179-182-183-223-225(T)- 2024 -70(T)-83-142(P)-176-182- 2025 -50-65-72(T)-83-116-184- 237-261-300(T)	106
63.	MAL 7139	31 Dec 2009	2010 -64-189- 2011 -38-39-189- 2012 -74- 2016 -81- 2017 -89- 2018 -32- 2019 -37-61-102-200- 2020 -	13

(a)	(b)	(c)	(d)	(e)
64.	MAL 7150	31 Oct 2009	2009 -149(T)-166(T)- 2010 -44-189- 2011 -38-100(T)-169(T)- 2012 -63(T)-74-86-193- 2013 -38-39-105-114(T)- 2014 -49-57- 2015 -202- 2017 -90- 2018 -29-121(T)- 2019 -37-241- 2020 -137(T)-190(T)- 2022 -78-105- 2023 -39(T)-51-52(T)-56(T)-84- 2024 -35(T)-68-119-237-268-269- 2025 -39(T)-44-119-120-124(T)-161-244(T)-245(T)-296	47
65.	MAL 7212	31 Dec 2009	2010 -108	1
66.	MAL 7213	01 Oct 2008	2016 -54	1
67.	MAL 7215	01 Oct 2008	2009 -42(T)-57(T)-58-59(T)-80-94-134(T)- 2010 -157-159- 2013 -76(T)-154-167- 2014 -57-71- 2016 -54-82(T)-90-194(T)-220(T)- 2017 -45-46-91-92-114- 2018 -116(T)-136-158-201- 2019 -59-61- 2020 -151(T)-152(T)-153(T)-189- 2021 -138-196- 2023 -53(T)-224- 2024 -47(T)-138-253(T)- 2025 -89-90(T)-92(T)-111-118-121-160	48
68.	MAL 723	31 Dec 2018	2019 -39(T)-57-205(T)- 2020 -172(T)- 2021 -88- 2022 -130- 2023 -119-146-209- 2024 -97-102-234- 2025 -162(T)-183-295	15
69.	MAL 7257	03 Sep 2018	2018 - 2019 -58-59-126(T)-204- 2020 -74-86-105(T)-151(T)-152(T)-153(T)-189- 2021 -65-196- 2022 -41(T)- 2023 -53(T)-110(T)-146-224- 2024 -253(T)- 2025 -90(T)-91(T)-92(T)-111-118-121-141(T)-160-182-216-239-266	31
70.	MAL 731	31 Dec 2007	2008 -74-163-201- 2009 -42(T)-57(T)-58-60(T)-80-81(T)-92-93-107-149(T)-150-151-185(T)- 2010 -83-156-159-173(T)- 2011 -100(T)-116(T)-188-190(T)- 2012 -104- 2013 -53-75(T)-76-105-113(T)-124- 2014 -49-56(T)-57-71-139(T)- 2015 -47-61-74-187-202-219(T)- 2016 -34(T)-35-90-194(T)-196(T)- 2017 -46-47-92-114-124- 2018 -29-109-116(T)-117(T)-121(T)-134-136-138- 2019 -39(T)-205(T)- 2020 -172(T)- 2021 -65-196- 2022 -130-167- 2023 -110(T)-121-143-146-209- 2024 -47(T)-97-102-159-208-253(T)- 2025 -86-90(T)-92(T)-111-118-121-141(T)-162(T)-182-213-295	89
71.	MAL 7317	31 Dec 2007	2008 -75-88(T)-89-122-184-185- 2009 -43(T)-44(T)-61(T)-120(T)-121(T)-135-172(T)-173(T)-186(T)- 2010 -65-66-85-109-190- 2011 -40-47(T)-78(T)-82(T)-157-206- 2012 -44(T)-45(T)-106- 2013 -115-168-196(T)- 2014 -57-59-143- 2015 -31(T)-32(T)-79(T)-80-81-124(T)-155(T)-188- 2016 -36(T)-114(T)-115-165-187(T)-197- 2017 -48-94-155-159(T)-175-223- 2018 -159-231-235(T)- 2019 -62-181(T)-202-256(T)- 2020 -36(T)-48-49(T)-89(T)-104(T)-130-131-132-133-211(T)- 2021 -75(T)-178(T)-201- 2022 -80(T)-123-124-170-173(T)- 2023 -85(T)-108- 2024 -36(T)-37(T)-69(T)-183-188(T)-215-216-217-218-238- 2025 -112-190(T)-219(T) – 238- 247(T)-271-272-273	101
72.	MAL 7332	01 Apr 2008	2008 -88(T)-122-164-184-185- 2009 -43(T)-44(T)-61(T)-62-120(T)-121(T)-173(T)-186(T)- 2010 -65-66-85-109-190- 2011 -40-77-82(T)-157-206- 2012 -44(T)-45(T)-106- 2013 -115-168-196(T)- 2014 -57-59-143- 2015 -31(T)-79(T)-80-81-124(T)-155(T)-188-202- 2016 -36(T)-112-115-197-219- 2017 -48-155(T)-175-223- 2018 -29-33-55-159-235(T)- 2019 -62-181(T)-202-242-253-256(T)- 2020 -49(T) – 89(T)-104(T)-130-131-132-133-211(T)- 2021 - 75(T)-178(T)-200(T)-201- 2022 -32-124-170- 2023 -85(T)-108- 2024 -36(T)-37(T)-69(T)-184-215-216-238-239- 2025 -154-190(T)-219(T)-238 – 247(T)- 262-271-272-273	88
73.	MAL 740	31 Dec 2008	2009 -42(T)-57(T)-58-59(T)-60(T)-80-94-134(T)-165- 2011 -61-79-170(T)-171(T)- 2012 -169-170- 2013 -47-51-52-70-76(T)-128-129-186(T)- 2014 -32-57-58-69-71-72(T)-39(T)- 2015 -28-60-74-75-202-219(T)- 2016 -35-90-194(T)-196(T)- 2017 -32-46-92-93-114- 2018 -29-110-115(T)-116(T)-117(T)-134-136-137-138-232- 2019 -58-81-126(T)-204-251- 2020 -74-86-105(T)-165- 2021 -65-111-196- 2022 -41(T)- 2023 -110(T)-146-210-212- 2024 -47(T)-138-159- 2025 -86-91(T)-141(T)-153-154-160-182-213-214-216- 239-266	86
74.	MAL 741	15 Nov 2002	2003 -37-86-122-132-150- 2004 -82-97-178-179-180-181-182- 2005 -36-64-83-85-86-168-178-208- 2007 -44-46-47-48-49-50-58-193- 2009 -62-79-164-165- 2010 -160-188-190- 2011 -77-82(T)-96-171(T)-187-206- 2012 -44(T)-45(T)-106- 2013 -70-112-128-129-169-196(T)- 2014 -45-57-59-69- 2015 -48-75-202- 2016 -36(T)-115-116-197-198(T)- 2017 -33(T)-49-50-64-113-133-156- 2018 -33-55-56-111-134-232- 2019 -81-150-242-243-253-269- 2020 -36(T)-48-165- 2021 -95-111-197- 2022 -32-149-170-189(T)- 2023 -146-155-189(T)-210-212- 2024 -30-138-159-184-209-240- 2025 -56-83-112-113-154-156 – 248(T)-270	106
75.	MAL 750	31 Dec 2007	2013 -129-184-187(T)- 2014 -33-55-57-73-93- 2015 -33(T)-34-62-63-77-78-156(T)-202- 2016 -37-50-55(T)-188-199- 2017 -51(T)-189-218-224- 2018 -29-55-74-75-87-89-112-113-133-134-259-286- 2019 -81-124-125(T)-151-201-203- 2020 -166-191(T)- 2021 -49(T)- 50(T)-66-69-173-198-218-219(T)- 2022 -40(T)-53-54-55-120- 2023 -31-40(T)- 41(T)-54(T)-106-107-122-144-155-166(T)-186-212- 2024 -30-38(T)-156-158-160-204-240- 2025 -55-83-154-274-289-297(T)	81

(a)	(b)	(c)	(d)	(e)
76.	MAL 751	31 Oct 2009	2010 -38-110-160-188-190- 2011 -77-82(T)-156-187-206- 2012 -44(T)-45(T)-106- 2013 -70-101-112-128-129-169-184- 2014 -45-55-57-59-69-93-137- 2015 -48-75-77-202- 2016 -36(T)-115-116-188-197-198(T)- 2017 -33(T)-49-50-113-133-156-206-218- 2018 -29-33-55-56-74-87-89-111-112-134-228- 2019 -62-81-150-151-243- 2020 -166- 2021 -95-173-197-218- 2022 -32-149-189(T)- 2023 -31-144-146-155-186-189-212- 2024 -30-138-156-159-184-204-209-233-240- 2025 -55-56-83-112-113-154-156- 248(T)-270-289	94
77.	MAL 752	31 Dec 2009	2010 -67-76-78- 2011 -62-172-191-205-207- 2012 -64(T)-84-105-119-129-130-140-192- 2013 -122-123-129-165-187(T)-194- 2014 -33-57-60-73-116-117- 2015 -33(T)-62-63-78-125-156(T)-170-202-214- 2016 -37-38-55(T)-56-166-199- 2017 -52-81-123-173-174-189-224- 2018 -57-77(T)-113-114-133-135-181-226-233-259-260-286-287- 2019 -85-125(T)-201-203-222-254- 2020 -191(T)- 2021 -49(T)- 50(T)-66-69-96-97-198-218-219(T)- 2022 -40(T)- 54-55-120-131-132-147-150-171- 2023 -40(T)-41(T)-54(T)-106-107-122-155-166(T)-212- 2024 -30-38(T)-241- 2025 -34-114-138-274-297(T)	101
78.	MAL 754	15 Aug 2003	2004 -39-48-112-128-129-138-139-140-142-158-183-184-185-210- 2005 -38-87-111-112-139-179-180-196-197- 2006 -51-71-84-106-113-136- 2007 -37-85-133-161-175- 2008 -41-42-53-90(T)-123-125- 2009 -63-78-108-136(T)-174-187- 2010 -39-76-78-86(T)-110-111-158-161-191- 2011 -62-71-117-172-191-205-207- 2012 -64(T)-84-105-119-129-130-138-140-192- 2013 -122-123-129-165-184-187(T)-194- 2014 -33-57-60-73-116-117- 2015 -33(T)-34-49-62-63-64(T)-125-126-156(T)-170-202-214- 2016 -37-38-39-50-55(T)-56-58-112-166-199-235- 2017 -32-51(T)-52-81-123-173-174-189-24-225- 2018 -55-57-75-77(T)-113-114-132-134-135 -181-226-256-259-260-286- 2019 -85-125(T)-201-203-222-254- 2020 -32-191(T)- 2021 -49(T)- 50(T)-66-69-96-153-198-218-219(T)- 2022 -40(T)-53-54-55-120-131-132-147-150-171- 2023 -40(T)-41(T)-53(T)-106-107-155-166(T)-212- 2024 -30-38(T)-158-160-240-241- 2025 -34-55-83-138- 274 -297(T)	178
79.	MAL 761	31 Dec 2025		
80.	MAL 762	31 Dec 2015	2018 -55-74-87-89-112- 2019 -81-151-176- 2020 -166- 2021 -173-218- 2023 -31-103-143-144-155-186-212- 2024 -30-156-204-233- 2025 -55-154-263-264-289	27
81.	MAL 765	31 Dec 2025		
82.	MAL 7724	31 Dec 2023		
83.	MAL 773	31 Dec 2025		
84.	MAL 781	31 Dec 2013	2014 -106- 2015 -126- 2016 -51- 2017 -44(T)-219- 2018 -75-182-202-226-257- 2021 -235- 2023 -47-145-211- 2024 - 2025 -157	16
85.	MAL 8421	31 Dec 2009	2010 -128- 2011 -208- 2012 -131(T)- 2016 -221(T)- 2018 -97(T)-227- 2025 -267-293	8
86.	MAL 8425	30 Aug 2022	2022 -106	1
87.	MAL 8433	31 Dec 2007	2008 -199- 2016 -57(T)-92- 2018 -34- 2021 -67-73(T)- 74(T)- 76(T)- 77(T)- 78(T)-79(T)-236- 2022 -79- 2023 -86(T)- 2024 -242-266	16
88.	MAL 8434	31 Oct 2006	2016 -221(T)- 2018 -97(T)-227- 2021 -67-78(T)-79(T)-202- 2022 -106- 2023 -86(T)- 2024 -242-266- 2025 -267-293	13
89.	MAL 8447	15 Dec 2024		
90.	MAL 85	31 Dec 2025		
91.	MAL 8502	31 Dec 2017	2018 -203	1
92.	MAL 8503	15 Jul 2016	2016 -221(T)-157- 2018 -58-227- 2020 -102- 2021 -31-236- 2025 -35-87	9
93.	MAL 8518	31 Dec 2021	2022 - 2025 -36-268	2
94.	MAL 8523	30 Sep 2014	2015 -125- 2017 -173-174-225- 2018 -260- 2022 -147-150	7

(a)	(b)	(c)	(d)	(e)
95.	MAL 8553	15 Jul 2016	2016-236-2017-53-158-160(T)-2018-35-2021-199-204(T)-2024-45-120	9
96.	MAL 860	30 Sep 2014	2015-157-214-2016-40-59-221(T)-2018-227-2023-143-2024-250(T)-2025-191(T)-267	10
97.	MAL 8608	31 Dec 2007	2008-54-2009-82(T)-2010-87-2011-84(T)-208-2012-132-133-171-180-2013-54-125-2014-50-2018-75 -182-2020- 66-169-2022-125(T)-156(T)-2024-121-2025-139	20
98.	MAL 8617	31 Jul 2017	2017-158-160(T)-2018-35-59-92-153-166(T)-2021-199-204(T)-2024-45-120-248(T)	12
99.	MAL 8621	31 Dec 2010	2015-214-2016-223-2018-92-2025-189(T)	4
100.	MAL 864	31 Dec 2007	2015-49-64(T)-125-126-214-2016-38-39-52(T)-56-58-93-169-200-235-2017-32-52-62-66-81-173-174-225-2018-57-60-75-77(T)-114-135-181-182-226-233-256-260-287-2019-65(T)-85-222-254-2021-96-97-98-153-2022-125(T) -131-132-147-150-171-2023-155-2024-46(T)-241-245-2025-33-34-114-138-215	56
101.	MAL 8645	31 Dec 2008	2011-208-2015-214-2016-117-2017-80(T)-2021-46-	5
102.	MAL 865	31 Dec 2007	2010-68-2011-208-2012-46-2013-55-123-2014-127-2015-139-214-93-2017-62 – 2018 -182-256-2019-65(T) -2022-125(T) -2023-155-2024-122-139-2025-33-265	19
103.	MAL 8655	31 Dec 2017		
104.	MAL 871	30 Sep 2014	2014-152(T)- 2016-145-2017-190-2018-63-256-2020-2025-158	6
105.	MAL 8715	31 Dec 2021		
106.	MAL 872	31 Dec 2010	2011-71-208-2012-48-2013-54-55-83-2014-127-2015-125-139-214-2016-38-52(T)-56-93-200-235-2017-62-81-173-225-2018-60-75-135 -182-226-256-260-2019-65(T)-85 -2020-73-2021- 47-48(T)-153-2022-125(T)-2024-122-139-2025-33-158-265	39
107.	MAL 88	31 Dec 2025		
108.	MAL 880	31 Mac 2023		
109.	MAL 884	30 Sep 2014	2016-206-2023-49	3
110.	MAL 885	31 Dec 2013	2016-206-2017-219-2020-73-2021-47-2023-47-143-2024-	6

5. NOTICES TO MARINERS - EXPLANATION OF TERMS

a. An explanation of the various commands used within Section II of monthly Notices to Mariners is summarized below. The main text of the update starts with one of the following five commands, usually in the order shown:

(i) **INSERT** is used for the insertion of all new data or, together with the **DELETE** command (see v. below), when feature has moved position sufficiently that the **MOVE** command (see iv. below) is not appropriate. For example: Delete feature and insert in a different position.

(ii) **AMEND** is used when a feature remains in its existing charted position but has a change of characteristic, for example:

Amend light to, Fl.3s25m10M 02° 23'.49N 101° 58'.31E.

When only the range of a light changes:

Amend range of light to, 20M 02° 23'.49N 101° 58'.31E.

(iii) **REPLACE** is used when one feature replaces an existing, but different, feature and the position remains as charted. The old feature will always first in the sentence, e.g. Replace xx with yy (where yy is the **new** feature). Example:

Replace depth 34 with depth 29 01° 07'.30N 103° 34'.30E.

(iv) **MOVE** is used for feature whose characteristics or descriptions remain unchanged, but they are to be moved small Distance, for example:

Move starboard-hand conical
buoy from: 01° 07'.30N 103° 34'.30E.

to: 01° 06'.80N 103° 35'.00E.

(v) **DELETE** is used when features are to be removed from chart or, together with the **INSERT** command (see (i) above), when features are moved a significant Distance such that the **MOVE** command is inappropriate.

b. Full details of chart updating methods can be found in NP294, "How to Keep Your Admiralty Charts Up-To-Date".

6. LAW AND REGULATIONS PERTAINING TO NAVIGATIONS

a. Nothing in this notice is to be taken as over ruling local regulations as may be issued by Port Authority etc. to meet dangers or situations, which may arise or cover local conditions.

b. While in the interest of the safety of navigation, the National Hydrographic Centre makes every endeavor to include in its hydrographic publications a correct and up to date detail of all information pertaining to navigation in Malaysian waters. **It must be clearly understood that no liability whatsoever can be accepted by it for errors in, of failure to publish detail of such information.**

7. CONFUSION BETWEEN BRIGHT SHORE LIGHT AND NAVIGATIONAL LIGHTS

a. With the increasing use of brilliant shore lights for advertising etc, mariners are warned that these shore light may, at times, be mistaken for navigation light and that difficulty may be experienced in Distinguishing navigation light particularly in the vicinity of harbours in the approaches to harbour, these brilliant shore light may be raised before the navigational light come into view.

b. Mariners are, therefore requested to report such cases with necessary details of the lights their characteristics and approximate positions to the appropriate Harbour Authority and to the National Hydrographic Centre, Bandar Armada Putra, Pulau Indah, 42009 PORT KLANG, Selangor.

8. PROHIBITION OF ANCHORING IN THE STRAITS OF MALACCA AND SINGAPORE

a. It is been observed vessels have been anchoring off the Traffic Separation Schemes (TSS) and Precautionary Areas in the Straits of Malacca and Singapore. These vessels are not only obstructing port approaches and traffic flow but also pose a risk to safety of navigation and the marine environment. There have been reported cases of incidents involving vessels maneuvering to anchor off the TSS and precautionary areas.

b. In view of the above, vessels is advised to not to anchor in all areas in the Straits of Malacca and Singapore between the landward limits of the TSS or precautionary areas, and adjacent port limits. Vessels are to anchor at the appropriate areas designated by the three littoral states (Malaysia, Indonesia and Singapore).

9. STRAITS OF MALACCA AND SINGAPORE - NEW AND AMENDED TRAFFIC SEPARATION SCHEMES

a. The New and Amended Traffic Separation Schemes have been implemented at 0000 hours UTC on 1st Dec 1998.

b. The IMO Maritime Safety Committee, at its 69th session (11-20 May 1998), has adopted in accordance with the provisions of resolutions A. 858 (20), the following new and amended existing Traffic Separation Schemes and associated routing measures.

AT ONE FATHOM BANK

Description of the Traffic Separation Scheme.

(i) A separation zone is bounded by a line connecting the following geographical positions:

1)	03°01'.70N	100°47'.40E
2)	02°54'.70N	100°56'.80E
3)	02°49'.50N	100°59'.50E
4)	02°44'.90N	101°10'.30E
5)	02°43'.40N	101°10'.00E
6)	02°49'.00N	100°59'.50E
7)	02°53'.40N	100°55'.40E
8)	03°00'.30N	100°47'.10E

(ii) A traffic lane for northwest bound traffic is established between the separation zone and line connecting the following geographical positions:

9)	03°02'.70N	100°48'.80E
10)	02°52'.50N	101°00'.00E
11)	02°46'.30N	101°11'.50E

(iii) A traffic lane for southeast bound traffic is established between the separation zone and line connecting the following geographical positions:

12)	02°54'.70N	100°43'.10E
13)	02°41'.20N	101°08'.80E

OFF PORT KLANG

Description of precautionary area.

(i) A precautionary area established by a line connecting the following geographical positions:

14)	02°46'.30N	101°11'.50E
15)	02°44'.30N	101°15'.00E
16)	02°39'.40N	101°12'.40E
17)	02°41'.20N	101°08'.80E

e. **PORT KLANG TO PORT DICKSON**

Description of the Traffic Separation Scheme.

(i) A separation zone is bounded by a line connecting the following geographical positions:

18)	02°42'.00N	101°13'.80E
19)	02°35'.00N	101°27'.10E
20)	02°27'.10N	101°37'.30E
21)	02°26'.50N	101°36'.80E
22)	02°35'.20N	101°25'.80E
23)	02°41'.60N	101°13'.60E

(ii) A traffic lane for northwest bound traffic is established between the separation zone and a separation line connecting the following geographical positions:

24)	02°44'.30N	101°15'.00E
25)	02°37'.40N	101°28'.00E
26)	02°29'.00N	101°38'.80E

(iii) A traffic lane for southeast bound traffic is established between the separation zone and a separation line connecting the following geographical positions:

27)	02°39'.40N	101°12'.40E
28)	02°34'.00N	101°23'.30E
29)	02°24'.60N	101°35'.30E

f. **INSHORE TRAFFIC ZONE**

The area between the landward boundary of the Traffic Separation Scheme and the Malaysian coast between a line drawn from position (24) **02°44'.15N, 101°15'.00E** in a direction of **027°** to meet the coast and a line drawn from position (26) **02°29'.00N, 101°38'.80E** in a direction of **034°** to meet the Malaysian coast.

g. **OFF PORT DICKSON**

Description of the precautionary area.

(i) A precautionary area is established by a line connecting the following geographical positions:

30)	02°29'.00N	101°38'.80E
31)	02°25'.80N	101°42'.90E
32)	02°21'.40N	101°39'.40E
33)	02°26'.60N	101°35'.30E

h. **PORT DICKSON TO TANJUNG KELING**

Description of the Traffic Separation Scheme.

(i) A separation zone is bounded by a line connecting the following geographical positions:

34)	02°23'.90N	101°41'.40E
35)	02°09'.70N	101°59'.60E
36)	02°09'.00N	101°59'.00E
37)	02°23'.20N	101°40'.90E

(ii) A traffic lane for north - west bound traffic is established between the separation zone and a separation line connecting the following geographical positions:

38)	02°25'.80N	101°42'.90E
39)	02°11'.60N	101°01'.00E

(iii) A traffic lane for southeast bound traffic is established between the separation zone and a separation line connecting the following geographical positions:

40)	02°21'.40N	101°39'.40E
41)	02°07'.10N	101°57'.50E

(iv) A deep - water route for southeast bound traffic is established by connecting the following geographical positions:

42)	02°21'.40N	101°39'.40E
43)	02°13'.80N	101°39'.30E
44)	02°05'.10N	101°55'.90E
45)	02°03'.00N	101°54'.20E
46)	02°12'.30N	101°36'.80E
47)	02°22'.20N	101°36'.80E
48)	02°24'.00N	101°36'.10E

i. **INSHORE TRAFFIC ZONE**

The area between the landward boundary of the Traffic Separation Scheme and the Malaysian coast between a line drawn from position (38) **02°25'.80N, 101°42'.90E** in a direction of **059°** to meet the Malaysian coast and a line drawn from position (39) **02°11'.60N, 102°01'.00E** in a direction of **034°** to meet the Malaysian coast.

j. **OFF MALACCA/DUMAI**

Description of the precautionary area.

(i) A precautionary area is established by a line connecting the following geographical positions:

49)	02°11'.60N	102°01'.00E
50)	02°07'.20N	102°06'.20E
51)	02°00'.00N	102°59'.80E
52)	02°03'.00N	101°54'.20E

k. **MALACCA TO IYU KECIL**

(i) A separation zone is bounded by a line connecting the following geographical positions:

53)	02°05'.40N	102°04'.60E
54)	01°55'.70N	102°15'.40E
55)	01°40'.00N	102°48'.30E
56)	01°23'.20N	103°12'.40E
57)	01°13'.80N	103°24'.00E
58)	01°12'.20N	103°28'.50E
59)	01°10'.50N	103°27'.50E
60)	01°13'.20N	103°23'.40E
61)	01°23'.20N	103°12'.40E
62)	01°39'.10N	102°48'.00E
63)	01°54'.80N	102°14'.80E
64)	02°04'.60N	102°03'.80E

(ii) A traffic lane for northwest bound traffic is established between the separation zone and a separation line connecting the following geographical positions:

65)	02°07'.20N	102°06'.20E
66)	01°57'.90N	102°16'.60E
67)	01°38'.40N	103°00'.00E
68)	01°25'.50N	103°15'.00E
69)	01°15'.20N	103°25'.30E
70)	01°14'.30N	103°29'.70E

(iii) A traffic lane for southeast bound traffic is established between the separation zone and a line connecting the following geographical positions:

71)	02°02'.80N	102°02'.20E
72)	01°52'.60N	102°13'.30E
73)	01°36'.80N	102°46'.90E
74)	01°22'.00N	103°11'.10E
75)	01°11'.60N	103°22'.80E
76)	01°09'.20N	103°26'.80E

(iv) A deep-water route for southeast bound traffic established by connecting the following geographical positions:

77)	02°01'.90N	102°01'.50E
78)	01°59'.70N	102°05'.60E
79)	01°52'.60N	102°13'.30E
80)	02°00'.00N	101°59'.80E

I. INSHORE TRAFFIC ZONE

The area between the landward boundary of the Traffic Separation Scheme and the Malaysia coast between a line drawn from position (65) **02°07'.20N, 102°06'.20E**, to Pulau Undan Lighthouse (**Lat 02°02'.90N, Long 102°20'.20E**) then in direction of **040°** to meet the Malaysian coast and a line drawn from position (70) **01°14'.30N, 103°29'.70E** in a direction of **038°** to meet the Malaysian coast.

m. OFF SULTAN SHOAL LIGHTHOUSE

Description of the precautionary area.

(i) A precautionary area is established by a line connecting the following geographical positions:

81)	01°14'.28N	103°29'.73E
82)	01°12'.62N	103°36'.24E
83)	01°05'.94N	103°32'.30E
84)	01°09'.23N	103°26'.76E

n. IN THE SINGAPORE STRAITS (MAIN STRAIT)

Description of the traffic separation scheme area.

(i) A separation zone is bounded by a line connecting the following geographical positions:

85)	01°10'.35N	103°34'.90E
86)	01°10'.35N	103°39'.85E
87)	01°07'.50N	103°43'.72E
88)	01°08'.60N	103°45'.43E
89)	01°05'.90N	103°43'.38E
90)	01°03'.60N	103°38'.95E
91)	01°07'.06N	103°32'.96E

(ii) A separation line connects the following geographical positions:

92)	01°08'.60N	103°45'.43E
93)	01°10'.26N	103°47'.91E
94)	01°10'.81N	103°49'.30E

(iii) A traffic lane for westbound traffic is established between the separation zone/line and a line connecting the following geographical positions:

95)	01°12'.62N	103°36'.24E
96)	01°11'.50N	103°40'.55E
97)	01°08'.65N	103°44'.40E
98)	01°10'.45N	103°47'.50E
99)	01°11'.13N	103°49'.18E

(iv) A traffic lane for eastbound traffic is established between the separation zone/line and a line connecting the following geographical positions:

100)	01°05'.94N	103°32'.30E
101)	01°01'.60N	103°39'.65E
102)	01°05'.00N	103°43'.67E
103)	01°07'.80N	103°46'.25E
104)	01°09'.47N	103°48'.70E
105)	01°09'.92N	103°49'.65E

(v) A deep-water route is established within the eastbound lane described in paragraph (d). A line connecting the following geographical positions bound the deep-water route:

i)	01°03'.60N	103°38'.95E
ii)	01°05'.90N	103°43'.38E
iii)	01°08'.61N	103°45'.44E
iv)	01°10'.26N	103°47'.91E
v)	01°10'.81N	103°49'.30E
vi)	01°10'.45N	103°49'.45E
vii)	01°09'.95N	103°48'.28E
viii)	01°08'.90N	103°46'.82E
ix)	01°04'.95N	103°42'.87E
x)	01°02'.97N	103°39'.10E

o. **SINGAPORE STRAIT (OFF PULAU SEBAROK/PULAU BELAKANG PADANG)**

Description of the precautionary area.

(i) A precautionary area is established by a line connecting the following geographical positions:

106)	01°11'.13N	103°49'.18E
107)	01°11'.59N	103°50'.31E
108)	01°10'.45N	103°50'.75E
109)	01°09'.92N	103°49'.65E

p. **SINGAPORE STRAIT (OFF ST JOHN'S ISLAND)**

Description of the Traffic Separation Scheme.

(i) A separation line connects the following geographical positions:

110)	01°11'.27N	103°50'.43E
111)	01°12'.21N	103°52'.40E

(ii) A traffic lane for westbound traffic is established between the separation line and a line connecting the following geographical positions:

112)	01°11'.59N	103°50'.31E
113)	01°11'.96N	103°51'.21E
114)	01°12'.51N	103°52'.25E

(iii) A traffic lane for eastbound traffic is established between the separation line and a line connecting the following geographical positions:

115)	01°10'.45N	103°50'.75E
116)	01°11'.41N	103°52'.76E

(iv) A deep-water route is established within the eastbound lane described in paragraph (c). A line connecting the following geographical positions bound the deep-water route:

(xi)	01°11'.27N	103°50'.43E
(xii)	01°12'.21N	103°52'.40E
(xiii)	01°11'.78N	103°52'.58E
(xiv)	01°10'.92N	103°50'.57E

q. **SINGAPORE STRAIT (OFF ST. JOHN'S ISLAND/PULAU SAMBU)**

Description of the precautionary area.

(i) A precautionary area is established by a line connecting the following geographical positions:

117)	01°12'.51N	103°52'.25E
118)	01°13'.38N	103°53'.85E
119)	01°12'.11N	103°54'.40E
120)	01°11'.41N	103°52'.76E

(ii) The focal point of the precautionary area is located at the following geographical position:

121)	01°12'.60N	103°53'.20E
------	------------	-------------

Description of the area to be avoided.

A circular area to be avoided with a diameter of one cable is established around position 17.b (121).

r. **SINGAPORE STRAIT (OFF CHANGI/PULAU BATAM)**

Description of the Traffic Separation Scheme.

(i) A separation line connects the following geographical positions:

122)	01°12'.97N	103°54'.03E
123)	01°13'.57N	103°55'.40E
124)	01°14'.89N	103°59'.01E

(ii) A separation zone is bounded by a line connecting the following geographical positions:

125)	01°14'.89N	103°59'.01E
126)	01°15'.67N	104°03'.40E
127)	01°15'.42N	104°03'.45E

(iii) A traffic lane for westbound traffic is established between the separation zone/line and a line connecting the following geographical positions:

128)	01°13'.38N	103°53'.85E
129)	01°14'.07N	103°55'.18E
130)	01°16'.02N	104°00'.00E
131)	01°16'.60N	104°03'.32E

(iv) A traffic lane for eastbound traffic is established between the separation zone/line and a line connecting the following geographical positions:

132)	01°12'.11N	103°54'.40E
133)	01°13'.50N	103°57'.67E
134)	01°14'.05N	104°03'.58E

s. **SINGAPORE STRAIT (OFF TANJUNG STAPA/PULAU BINTAN)**

Description of the precautionary area.

(i) A precautionary area is established by a line connecting the following geographical positions:

135)	01°16'.60N	104°03'.32E
136)	01°18'.63N	104°15'.00E
137)	01°15'.40N	104°15'.00E
138)	01°14'.05N	104°03'.58E

t. **AT HORSBURGH LIGHT AREA**

Description of the Traffic Separation Scheme.

(i) A separation zone is bounded by line connecting the following geographical positions:

139)	01°17'.32N	104°15'.00E
140)	01°18'.00N	104°19'.70E
141)	01°24'.55N	104°27'.05E
142)	01°24'.30N	104°27'.25E
143)	01°17'.80N	104°19'.85E
144)	01°17'.10N	104°15'.00E

(ii) A traffic lane for southwest bound traffic is established between the separation zone and a line connecting the following geographical positions:

145)	01°18'.63N	103°15'.00E
146)	01°19'.40N	104°19'.50E
147)	01°25'.40N	104°26'.32E

(iii) A traffic lane for northeast bound traffic is established between the separation zone and a line connecting the following geographical positions:

148)	01°15'.40N	104°15'.00E
149)	01°16'.30N	104°19'.85E
150)	01°23'.40N	104°27'.95E

10. STRAITS OF MALACCA AND SINGAPORE - RULES FOR VESSELS NAVIGATION

I. Definitions

For the purpose of these rules the following definition shall apply:

- a. A vessel having a draught of 15 meters or more shall be deemed to be a deep draught vessel.
- b. A tanker of 150,000 DWT and above shall be deemed to be a very large crude carrier (VLCC).

Note: The above definitions do not prejudice the definitions of “vessels constrained by her draught described in Rule 3 (h) of the International Regulations for Preventing Collisions at Sea, 1972.

II. General Provisions

- a. Deep draught vessels and VLCCs shall allow for an under keel clearance of at least 3.5 meters at all times during the entire passage through the Strait of Malacca and Singapore and shall also take all necessary safety precaution, when navigating through the Traffic Separation Schemes.
- b. Master of deep draught vessels and VLCCs shall have particular regard to navigational constraints when planning their passage through the Straits.
- c. All deep draught vessels and VLCCs navigating within the Traffic Separation Schemes are recommended to use the pilotage service of the respective countries when they become available.
- d. Vessels shall take into account the precautionary areas where crossing traffic may be encountered and be in a maximum state of maneuvering readiness in these areas.

III. Rules

Rule 1. Eastbound deep draught vessels shall use the designated deep-water routes.

Rule 2. Eastbound deep draught vessels navigating in the deep - water routes in Philip Channel and Singapore Strait shall as far as practicable, avoid overtaking.

Rule 3. All vessels navigating within the Traffic Separation Scheme shall proceed in the appropriate traffic lane in the general direction of traffic flow for that lane and maintain as steady a course as possible, consistent with safe navigation.

Rule 4. All vessels having defects, affecting operational safety shall take appropriate measure to overcome these defects before entering the Strait of Malacca and Singapore.

Rule 5. In the event an emergency or breakdown of a vessel in the traffic lane, the vessel shall as far as practicable and safe, leave the lane by pulling out to the starboard side.

Rule 6. (a) Vessels proceeding in the westbound lane of the Traffic Separation Scheme “In the Singapore Strait” when approaching Raffles Lighthouse shall proceed with caution, taking note of the local warning system, and compliance with Rule 18(d) of the International Regulations for Preventing Collisions at Sea, 1972, avoid impeding the safe passage of a vessel constrained by her draught which is exhibiting the signals required by Rule 28 and which is obliged to cross the westbound lane of the scheme in order to approach the single point mooring facility (in approximate position **01°11’.42N, 103°47’. 50E**, from Phillip Channel).

(b) Vessel proceeding in the Traffic Separation Schemes when approaching any of precautionary areas shall proceed with caution, taking note of the local warning system, and in compliance with 18(d) of the International Regulations for Preventing Collisions at Sea, 1972, avoid impeding the safe passage of vessel constrained by her draught which is exhibiting the signals required by Rule 28 and which is obliged to cross that precautionary area.

- (c) Information relating to the movement of ships constrained by their draught as referred to in paragraphs (a) and (b) above will be given by radio broadcasts. The particulars of such broadcast are promulgated by Notices to Mariners. All vessels navigating in the Traffic Separation Scheme should monitor these radio broadcast and take the information received.

Rule 7. VLCCs and deep draught vessels navigating in the Straits of Malacca and Singapore shall, as far as it is safe and practicable, proceed at a speed of not more than 12 knots over the ground following areas:

- (a) At One Fathom Bank Traffic Separation Scheme.
- (b) Deep water routes in the Phillip Channel and Singapore Straits, and.
- (c) Westbound lanes between positions **01°12'.51N, 103°52'.25E** and **01°11'.59N, 103°50'.31E** and between position **01°11'.13N, 103°49'.18E** and **01°08'.65N, 103°44'.40E**.

Rule 8. All vessels navigating in the requiring system of the Strait of Malacca and Singapore shall maintain at all times a safe speed consistent with safe navigation, shall proceed with caution, and shall be in a maximum state of manoeuvring readiness.

Rule 9. (a) Vessels that are fitted with VHF radio communication are to participate in the ship reporting system adopted by the Organization.

- (i) Vessels of 300 GT and above.
- (ii) Vessels of 50 meters or more in length.
- (iii) Vessels engaged in towing or pushing with a combined GT of 300 and above, or with a combined length of 50 meters or more.
- (iv) Vessels of any tonnage carrying hazardous and or potentially polluting cargo in accordance with the definitions in paragraph 1.4 of Resolution MSC 43(64).
- (v) All passenger vessels that are fitted with VHF, regardless of length or GT and
- (vi) Any category of vessels less than 50 meters in length or less than 300 GT which is fitted with VHF and in an emergency uses the appropriate traffic lane or separation zone, in order to avoid immediate danger.

(b) VLCCs and deep draught vessels navigating in the Straits of Malacca and Singapore are advised to broadcast, eight hours before entering the Traffic Separation Scheme, navigational information giving name, deadweight tonnage, draught, speed and times of passing One Fathom Bank Lighthouse, Raffles Lighthouse and Horsburgh Lighthouse, difficult and unwieldy tows are also advised to broadcast similar information.

Rule 10. All vessels navigating in the Straits of Malacca and Singapore are requested to report by radio to the nearest shore authority any damage to or malfunction of the aids to navigation in the Straits, or any aids out of position in the Straits.

Rule 11. Flag States, owners and operators should ensure that their vessels are adequately equipped in accordance with the appropriate international conventions/recommendations.

IV. Warning

Mariners are warned that local traffic could be unaware of the internationally agreed regulations and practices of seafarers and may be encountered in or near the Traffic Separation Scheme, and should take any precautions, which may be required by the ordinary practice of seaman or by the special circumstances of the case.

11. STRAITS OF MALACCA AND SINGAPORE - DESCRIPTION OF THE MANDATORY SHIP REPORTING SYSTEM (STRAITREP)

1. Categories of ships required to participate in the system.

1.1 Ships of the following categories are required to participate in the system.

1.1.1 Vessels of 300 GT and above.

1.1.2 Vessels of 50 metres or more in length.

1.1.3 Vessels engaged in towing or pushing with a combined GT of 300 and above, or with a combined length of 50 meters or more.

1.1.4 Vessels of any tonnage carrying hazardous cargo, as defined in paragraph 1.4 of resolution MSC.43 (64).

1.1.5 All passenger vessels that are fitted with VHF, regardless of length or GT and

1.1.6 Any category of vessels less than 50 meters in length or less than 300 GT which are fitted with VHF and emergency, uses the appropriate traffic lane or separation zone, in order to avoid immediate danger.

2. Geographical coverage of the system and the number and edition of the reference chart used for the delineation of the system.

2.1 The operational area of STRAITREP covers the Straits of Malacca and Singapore between longitudes **100° 40'E** and **104° 23'E** as shown in the chart lets attached as Appendix 1 and Appendix 2. The area includes the routing system in the Straits of Malacca and Singapore. The area is divided into nine sectors; each has an assigned VHF channel as shown in Appendix 3.

2.2 The reference chart which include the operational area STRAITREP are the Malaysian Chart Series MAL 515, 521, 532 and 54 published by the National Hydrographic Centre or the equivalent chart published by the competent Hydrographic Authority.

3. Format, content of report, times and geographical positions for submitting reports, authority to which report should be sent, available services.

The ship report short title STRAITREP shall be made to the VTS authorities as follows: -

3.1 Format

The ship report shall be drafted in accordance with the format shown in Appendix 4. The information requested from ship is derived from the Standard Reporting Format given in paragraph 2 of the IMO resolution A.851 (20).

3.2 Content

The report required from a ship contains only information, which is essential to meet the objectives of the STRAITREP:

3.2.1 Information considered essential:

A - Name of ship, call sign, and IMO identification number (if available)

C or D - Position

P - Hazardous cargo, class if applicable and

Q or R - Breakdown, damage and or deficiencies affecting the structure, cargo or equipment of the ship or any circumstances affecting normal navigation in accordance with the provisions of the SOLAS and MARPOL Conventions.

3.2.2 Information considered necessary when requested by VTS authority

E and F- Course and speed of ship.

Note: On receive of position message, operators of the VTS establish the relation between the ship's position and information supplied by the facilities available to them. The information on heading and speed will facilitate the VTS operator's task of identifying a ship within a group.

3.3 Geographical position for submitting report:

3.3.1 Ships entering the operational area shall report when crossing the limits mentioned in paragraph 2 or when crossing a line joining Tanjung Piai **01°15'.50N, 103°30'.75E** and Pulau Karimun Kecil **01°09'.20N, 103°24'.35E** or when leaving port a anchorage in the area or before joining the traffic lane of the TSS.

3.3.2 Ships entering the operational area shall also report when approaching from the south via Selat Riau, abeam of Karang Galang Lt **01°09'.58N, 104°11'.47E** or via Selat Durian, report when Pulau Jangkat Beacon **00°57'.89N, 103°42'.72E** is abeam and when approaching from the East Johor Strait, abeam of the Eastern Buoy **01°17'.87N, 104°05'.99E**.

3.3.3 A ship approaching from any direction other than those specified above shall on reaching sector 7, sector 8, or sector 9 as appropriate report by giving the vessel's position in term of bearing and Dectance from one the following reference points:

i)	Pu Iyu Kechil Lt	(01°11'.24N, 103°21'.07E)
ii)	Sultan Shoal Lt	(01°14'.38N, 103°38'.98E)
iii)	Raffles Lt	(01°09'.60N, 103°44'.55E)
iv)	Sakijang Lt Bn	(01°13'.30N, 103°51'.37E)
v)	Bedok Lt	(01°18'.54N, 103°56'.06E)
vi)	Tg Stapa Lt	(01°20'.57N, 104°08'.24E)
vii)	Horsburgh Lt	(01°19'.81N, 104°24'.44E)

3.4 Authority

The VTS authorities for the STRAITREP are as follows:

i)	Sector 1 to Sector 5	-	Klang VTS
ii)	Sector 6	-	Johor VTS
iii)	Sector 7 to Sector 9	-	Singapore VTS

4. Information to be provided to ship and procedures to be followed:

4.1 STRAITREP also provides information to ships specific and critical situation that could cause conflicting traffic movement and other information concerning safety of navigation.

4.2 Depending on the sector that a ship is in, every ship shall also maintain a VHF radiotelephone listening watch on the appropriate VHF Channel. Information of general interest to ship will be broadcast on VHF channel 16 and any other channel, as may be the appropriate VTS authority. This broadcast will be preceded by an announcement on the appropriate VHF channel assigned to the sector.

5. Radio communications required for the system, frequencies on which reports should be transmitted and information to be reported. The radio communication required for the STRAITREP is as follows:

5.1 STRAITREP will be based on VHF voice radio communication and will be interactive. The call to the appropriate VTS authority shall be made on the VHF channel assigned to the particular sector in which the ship is located as indicated in appendix 3, and the report shall be transmitted on the channel or any other available channel as assigned by the appropriate VTS authorities.

5.2 The language used for communication shall, using the IMO "Standard Marine Communications Phrases" where necessary.

5.3 Information of commercial confidentiality may be transmitted by non-verbal means.

6. Rules and regulations in force in the area of the system.

6.1 The International Regulation for Preventing Collisions at Sea, 1972 are applicable throughout the operational area of STRAITREP.

6.2 The rules for vessel navigating through the Strait of Malacca and Singapore as approved by IMO are applicable throughout the area.

7. Shore based facilities to support operation of the system. The facilities of the STRAITREP are as follows:

7.1 Klang VTS

- Telephone, Facsimile and telex communication.
- 6 set of VHF radio communication equipment.
- 6 real time Decplay console for "X" and "S" bands radar signals from remote radar stations.

7.2 Johor VTS

- Telephone, Facsimile and telex communication.
- 4 set of VHF radio communication equipment.
- 4 real time Decplay console for "X" and "S" bands radar signals from remote radar stations.

7.3 Singapore VTS

- Telephone, Facsimile and telex communication
- 11 set of VHF radio communication equipment
- 4 real time Decplay console for "X" band radar signals from remote radar stations.
- 4 radar of radio direction finder in marine bands.

7.4 Remote Stations:

7.4.1 Pulau Angsa

- 1 "X" band radar facility.
- 1 "S" band radar facility.
- VHF transmitters and receivers.

7.4.2 Bukit Jugra

- 1 "X" band radar facility.
- 1 "S" band radar facility.
- VHF transmitters and receivers.

7.4.3 Cape Rachado

- 1 "X" band radar facility.
- 1 "S" band radar facility.
- VHF transmitters and receivers.

7.4.4 Pulau Undan

- 1 "X" band radar facility.
- 1 "S" band radar facility.
- VHF transmitters and receivers.

7.4.5 Bukit Segenting

- 1 “X” band radar facility.
- 1 “S” band radar facility.
- VHF transmitters and receivers.

7.4.6 Tanjung Piai

- 1 “X” band radar facility.
- 1 “S” band radar facility.
- VHF transmitters and receivers.

7.4.7 Bukit Pengerang

- 1 “X” band radar facility
- 1 “S” band radar facility
- VHF transmitters and receivers

7.4.8 Sultan Shoal Lighthouse

- 1 “X” band radar facility.
- VHF transmitters and receivers.

7.4.9 Raffles Lighthouse

- 1 “X” band radar facility.

7.4.10 St John’s Island

- 1 “X” band radar facility.

7.4.11 Bedok Lighthouse

- 2 sets of VHF/DF radio direction finder.

7.4.12 Bedok

- 1 “X” band radar facility.

7.4.13 Horsburgh Lighthouse

- 1 “X” band radar facility.
- VHF transmitters and receivers.

7.4.14 Jurong Control

- 2 sets of VHF/DF radio direction finder.


8. **Alternative communication if the communication facilities of the shore-based authority fail:**

8.1 STRAITREP is designed to avoid, as far as possible, any irretrievable breakdown of equipment that would hinder the functioning of the services normally provided by the respective VTS authorities.

8.2 The most important items of equipment and power sources are duplicated and the facilities are provided with emergency generating sets as well as with Uninterruptible Power Supply (UPS) units. A maintenance team is available 24 hours a day to attend to any breakdown.


8.3 STRAITREP is also designed in such a manner that if one station fails, the adjacent station can provide the necessary coverage.

STRAITREP OPERATIONAL AREA (SECTORS 1 TO 6)



STRAITREP OPERATIONAL AREA (SECTORS 7 TO 9)

Appendix 2



**ASSIGNED VHF CHANNELS FOR SECTORS IN THE MANDATORY REPORTING SYSTEM IN
THE STRAITS OF MALACCA AND SINGAPORE
(STRAITREP)**

SECTOR	VHF CHANNELS	VTS AUTHORITIES
Sector 1	VHF Channels 66	Klang VTS
Sector 2	VHF Channels 88	Klang VTS
Sector 3	VHF Channels 84	Klang VTS
Sector 4	VHF Channels 61	Klang VTS
Sector 5	VHF Channels 88	Klang VTS
Sector 6	VHF Channels 88	Johor VTS
Sector 7	VHF Channels 73	Singapore VTS
Sector 8	VHF Channels 14	Singapore VTS
Sector 9	VHF Channels 10	Singapore VTS

**DRAFTING OF RADIO REPORTS TO THE MANDATORY SHIP REPORTING SYSTEM IN THE
STRAITS OF MALACCA AND SINGAPORE (STRAITREP)**

Designator	Function	Information Required
A	Ship	Name and call sign
C	Position	A 4 digit group giving latitudes in degrees and minutes suffixed with N (north) or S (south) and a 5 digit group giving longitudes in degrees in minutes suffixed with E (east) or W (west)
D	Position	True bearing (first 3 digits) and Dectance given in nautical miles from a clearly identifiable point (state landmark)
E	True course	A 3 digit group
F	Speed in knots and tenths of knots	A 3 digit group
P	Hazardous cargo on board	Indicate "Yes" or "No" to whether vessel is carrying hazardous cargo. If "Yes" the class if applicable.
Q	Defect/damage/deficiencies/other limitations	Brief detail of defects, deficiencies or other limitations
R	Description of pollution or dangerous goods lost overboard	Brief detail of type of pollution (oil, chemicals, etc) or dangerous good lost overboard position expressed as in (C) or (D)

12. INFORMATION ABOUT RADAR BEACONS

a. Racon (radar beacons) is being installed on the Malaysian Coast. These Racon are located on conspicuous objects like light house and etc. They operate in the 'X' band marine radar (9300 MHz) and provide information on bearing as well as range by means of special codes signals Displayed on the ships radar screen. Range is measured from the centre of the PPI to the innermost point of the special coded signal received from the Racon after applying a standard negative correction of 75 meters (246 feet), in order to take care of the delay between reception and transmission.

b. Racons have been installed at the following places and their details are as follow:

PENINSULAR MALAYSIA

1. One Fathom Bank

(i)	Object	:	White round steel tower with red bands on concrete piles structure
(ii)	Position	:	2° 53'.30N 100° 59'.80E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code O (— — —)

2. One Fathom Bank

(i)	Object	:	Yellow buoyant beacon with North Cardinal top mark
(ii)	Position	:	2° 48'.70N 100° 56'.50E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code M (— —)

3. One Fathom Bank (N)

(i)	Object	:	White beacon
(ii)	Position	:	3° 00'.90N 100° 51'.90E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code T (—)

4. Sepat RLB

(i)	Object	:	Black yellow horizontal stripes buoyant beacon
(ii)	Position	:	2° 34'.10N 101° 23'.40E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code C (— · — ·)

5. Mudah Selatan

(i)	Object	:	White round GRP tower on piles platform
(ii)	Position	:	1° 25'.20N 103° 11'.20E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code O (— — —)

6. Sungai Udang

(i)	Object	:	SBM (Super Buoy Mooring)
(ii)	Position	:	2° 11'.73N 102° 06'.77E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code U (· —)

7. Tanjung Piai

(i)	Object	:	White round GRP tower on pile
(ii)	Position	:	1° 15'.50N 103° 30'.70E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code M (— —)

8. Horsburgh Lighthouse

(i)	Object	:	White round tower black bands
(ii)	Position	:	1° 19'.82N 104° 24'.40E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code O (— — —)

9. Pulau Mungging

(i)	Object	:	Metal framework tower
(ii)	Position	:	1° 21'. 70N 104° 17'. 80E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code N (— ·)

10. Belida Oilfield

(i)	Object	:	Moored Storage Tanker
(ii)	Position	:	4° 07'. 80N 105° 07'. 80E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code T (—)

11. Lawit A

(i)	Object	:	On oil platform
(ii)	Position	:	6° 33'. 00N 103° 21'. 00E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code X (— · · —)

12. Jerneh A

(i)	Object	:	On oil platform
(ii)	Position	:	6° 33'. 68N 103° 44'. 62E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code Y (— · — —)

13. Sungai Golok

(i)	Object	:	White round GRP tower on pile
(ii)	Position	:	6° 14'. 20N 102° 05'. 50E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code A (· —)

EAST MALAYSIA (SABAH AND SARAWAK)

14. Pulau Sipadan

(i)	Object	:	On light beacon tower
(ii)	Position	:	4° 06'. 60N 118° 37'. 90E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code S (· · ·)

15. Bintulu

(i)	Object	:	At Fairway buoy
(ii)	Position	:	3°16'. 42N 112° 57'. 10E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code B (— · · ·)

16. Central Luconia Gasfield

(i)	Object	:	On gas platform
(ii)	Position	:	4°20'. 06N 112°40'. 72E
(iii)	Sector	:	360°
(iv)	Service	:	Continuous
(v)	Identification signal	:	Morse Code L (· — · ·)

17. Terumbu Peninjau

(i)	Object	:	At buoy No. 2
-----	--------	---	---------------

(ii)	Position	:	8°07'. 25N	114°47'. 83E
(iii)	Sector	:	360°	
(iv)	Service	:	Continuous	
(v)	Identification signal	:	Morse Code C (— · — ·)	

18. **Permatang Ubi**

(i)	Object	:	At buoy No. 3	
(ii)	Position	:	7°56'. 70N	114°26'. 13E
(iii)	Sector	:	360°	
(iv)	Service	:	Continuous	
(v)	Identification signal	:	Morse Code K (— · — ·)	

13. SHIP IN DISTRESS

I. Statutory Distress Signals

1. Annex IV of the International Regulation for Preventing Collision at Sea 1972, lists the signal to be used or exhibited either together or separately to indicate Distress and need of assistance.

a. These are:-

- 1) A gun or other explosive signal fired at interval of about a minute.
- 2) A continuous sounding with any fog signaling apparatus.
- 3) Rockets or shell, throwing red stars fired one at a time short intervals.
- 4) A signal made by radiotelegraphy or by any other signaling method consisting of the group · · · — — — · · · (SOS) in the Morse Code.
- 5) A signal sent by radiotelegraphy consisting of the spoken word "Mayday".
- 6) The International Code Signal of Distress indicated by N.C.
- 7) A signal consisting of a square flag having above a below it a ball or anything resembling a ball.
- 8) Flames on the vessel (as from a burning tar barrel, oil barrel, etc)
- 9) A rocket parachute flare or a hand flares showing a red light.
- 10) A smoke signal giving off orange - colour smoke.
- 11) Slowly and repeatedly raising and lowering arms outstretched to each side.
- 12) The radiotelegraph alarm signal.
- 13) The radiotelephone alarm signal.
- 14) Signal transmitted by emergency position - indicating radio beacons.
- 15) Approved signal transmitted by radio communication system.
- 16) The digital selective calling Distress signal.

b. The use or exhibition of any of the foregoing signals except for the purpose of indicating Distress and need of assistance and the use of other signals that may be confused with any of the above signals are prohibited.

c. Attention is drawn to the relevant sections of the International Code of Signals, the Merchant Ship Search and Rescue Manual and the following signals:

- 1) A piece of orange - colour canvas white either a black square and circle or other appropriate symbol (for identification from the air).
- 2) A dye marker.

2. The requirement for the carriage of ship Distress signals for all classes of ship including their associated survival craft, are contained in either:-

a. Regulation 5 - 11 and schedule 1 and 4 to the Merchant Shipping (Live Saving Appliances) Regulation 1986.

b. Regulation 36 and 51 to the Merchant Shipping (Live Saving Appliances) Regulation 1980.

Not less than twelve rocket parachute flares shall be carry by Classes I, II (A), III, IV, VII, VII (T), VIII, VIII (A), VIII (T). VIII (A) (A), IX, XI.

Classes VI, IX (A), IX (A) (T) and XII are allowed to carry alternative Distress signals.

Survival craft generally required to carry, four rocket parachute flares, six hand flares and two buoyant smoke signals. Class V ships are not required to carry ships Distress signal.

II. Authority to use Distress signals

3. Rule 3-(1) of the Merchant Shipping (Signals of Distress) Rules, 1977, provides as follow:-

a. No signal of Distress shall be used by any vessel unless the master of the vessel so orders.

b. The master of the vessel shall not order any signal of Distress to be used by his vessel unless he is satisfied:

(1) That his vessel is in serious and imminent danger, or that another vessel or an aircraft is in serious and imminent danger and cannot of itself send that signal, and

(2) That the vessel in danger (whether his own vessel or another vessel) or the aircraft in danger, as the case maybe, requires immediate assistance in addition to any assistance than available to her.

c. The master of the vessel which has sent any signal of Distress by means of radio or other means, shall cause that signal to be revoked by all appropriate means as soon as he is satisfied that the vessel or aircraft to which the signal relates is no longer in need of assistance as foresaid.

4. Master and others in charge afloat are reminded of the importance of making a properly authorized signal of Distress whenever a ship is in grave and imminent danger, even when they believe that assistance has already been assured. Master are also reminded of the need to cancel a Distress call if the ship is no longer in danger. Failure to do this has on occasions resulted in serious loss of the time to other ships and has in some instances caused needless anxiety to relatives and friends of those on board, because failure to find or establish communication with the ship sending the signal has led to the belief the she has foundered.

Ships have also on occasion used red flares to warn off other vessels, the flares have been sighted from a Dectance and extensive SARS operations has been mounted. This is illegal and it is also unnecessary. The use of warning signals is permitted provided that they are quite Dectinct from Distress signals and for the purpose white flares are manufactured and are readily available through chandlers. A well-trained AIDec Lamp supplemented by the ship's whistle is also often effective.

III. Need for care in the use of certain Distress signals

5. Two of the statutory Distress signal, namely "a continuous sounding with any fog-signaling apparatus" and "flames on the vessel" could on occasions be misunderstood and is recommended that where more easily recognized Distress signals can be made the above mentioned signals not be used.

6. Distress signal should be as Dectinctive as possible, so that may be recognized at once and assistance Decpatched without delay. Thus, instead of making an indefinite succession of blasts on the fog-signaling apparatus when in Distress, mariners should make the "continuous sounding" by repeating the Morse Signal SOS (. . . — — — . . .) on the whistle or other sound signaling equipment. If this is done there can be no mistake as to the meaning of the signal. Similarly, by the night, if signaling for helps by means of a lamp or flashing light the same signal SOS should always be used.

7. In the case of the “flame on the vessel” signal, unless the flames making the signal are sufficiently large to attract immediate attention, their chances of being recognized as a Distress signal are very poor. The best signals are rocket parachute flares or hand flares showing red lights or rockets emitting red stars. Arrangements should be made to steady rockets to ensure their satisfactory flight when fired.

IV. Procedure when sending a radio Distress or urgency signal

8. All the calls detailed below should be sent on one or other of the Distress and calling frequencies, 500 kHz for radiotelegraph transmissions, 2182 kHz and VHF Ch 16 for radiotelephone transmissions. (Although ships in Distress should normally transmit their Distress calls on either 500 kHz, 2182 kHz or VHF Ch 16 any other frequency may also be used, AT ANY TIME, if it appears probable that assistance may thereby be obtained more quickly).

9. Descriptions of and the procedures for sending the Alarm Signal, Distress Signal and Distress Message by radiotelegraph or radiotelephone are contained in the “Manual for use by the Maritime Mobile and Maritime Mobile-Satellite Services” published by the ITU, Geneva. The information is also contained in the “Handbook for Marine Radio Communication”, published by Lloyds London Press.

10. The RADIOTELEGRAPH ALARM SIGNAL is intended to give preliminary warning to other ships and to Coast Radio Stations, either aurally or by activation of the auto-alarms of ship within range, of the impending transmission of the Distress call and message, or to announce (a) that an urgent cyclone warning is to be transmitted by a duly authorised coast station, (b) the loss of a person or persons overboard when the assistance of other ship is required and cannot be obtained satisfactorily by the use of urgency signal only. Since the timing accuracy of this signal of twelve dashes sent in one minute is important, all compulsorily fitted radiotelegraph ships are provided with an automatic keying device that should be used for the purpose (Appendix A draws attention to the use which can be made of the device in an emergency by unskilled person who receive suitable instruction beforehand). It should be immediately followed by the Radiotelegraph DISTRESS CALL which consists of: -

a. The DISTRESS SIGNAL SOS sent three times.

b. The word DE;

c. The call-sign of the mobile station in Distress sent three times followed, when circumstances permit, by an interval of two minutes to enable radio officers and operators to reach their apparatus and bring it into operation. The radiotelegraph Distress signal indicates that a ship is threatened by grave and imminent danger and request immediate assistance; it also gives absolute priority over all other transmissions and secures silence for the Distress message. The Distress call should be repeated with Decretion until the Distress message can be sent. Should radio officers on listening for a minute or two after being called by the auto alarm bell hear nothing further, they would be liable to tribute the alarm to false call. The DISTRESS MESSAGE comprises the Distress signal followed by the name of the ships in Distress and information concerning her for position, the nature of Distress and the kind of assistances desired. It is important that the position of vessel in Distress should be given as accurately as possible in latitude and longitude. If the vessel is started to be in Distress on a rock or shoal, or near a headland or the place, a precise geographical indication should be given of the position of the vessel, in order that the place may not be mistaken for another place with the same name on another part of the coast. In the case of a vessel in Distress and underway or drifting, the Master should, after indicating his position, give the vessel's course and speed or estimated direction and rate of drift, stating whether his vessel is in a “light” or “loaded” condition. The Distress message should be immediately followed by the transmission of two dashes, each of approximately 10 to 15 second's duration to permit direction-finding stations to determine position. In addition to the radio Distress call, the appropriate visual and/or sound signals of Distress should, of course, be made to indicate the position of the vessel during darkness, or when visibility is poor.

11. The RADIOTELEPHONE ALARM SIGNAL is also intended to give preliminary warning to other ships and to Coast Radio Stations, either aurally or by activation of radio telephone auto-alarms, of the impending transmission of a Distress call and message or in certain cases a message prefixed by the Urgency Signal as indicated in paragraph 10. The signal consists of two tones transmitted alternately over a period of at least 30 seconds, and will normally be generated by an automatic device which is now available for use with ship's radiotelephone transmitters. (See appendix B). When such a device is provided, the signal should be transmitted.

12. The RADIOTELEPHONE DISTRESS SIGNAL consists of the spoken word "MAYDAY". The RADIOTELEPHONE DISTRESS CALL consists of the Distress signal "MAYDAY". Spoken three times, the words "THIS IS" and the name of the ship Distress, repeated three times. All stations hearing it must cease all transmissions capable of interfering with the Distress call or messages and must listen on the frequency used for the Distress call. This call must not be addressed to a particular station. The composition of the DISTRESS MESSAGE is as described in paragraph 10.

13. THE RADIOTELEGRAPH URGENCY SIGNAL XXX (— · · — · · — · · — · · —) repeated three times, and the RADIOTELEPHONE URGENCY SIGNAL, which consists of the group of words, "PAN PAN" repeated three times, are provided for use in cases in which a ship making a call has a very urgent message to transmit concerning the safety of the ship or of some person on the board or within sight, but it does not necessarily imply that ship in imminent danger or requires immediate assistance. The call has priority over all other communications except Distress calls and it should be used in all cases in which the sending out of the SOS and MAYDAY signal is not fully justified. The urgency signal and message must, where practicable, be addressed to a specific station, i.e. to the nearest Coast Radio Station or to other ship known to be in the vicinity. The urgency signal may also be used when the Master of the ship desires to issue a warning that circumstances are such that it may become necessary for him to send out the Distress signal at a large stage, but in any such case the signal need not be addressed to a specific station. If precautionary action ceases to be necessary, the message should be cancelled at once.

V. Radio watch for, and reception of, Distress signal

14. In accordance with the Merchant Shipping (Radio Installations) Regulations 1980 (as amended) and the Merchant Shipping (Radio) (Fishing Vessels) Rules 1974 (as amended), all Malaysia passenger ships, cargo ships of 300 tons and upwards and fishing vessels of 12 metres or more in length must keep continuous radiotelephone watch on the frequency of 2182 kHz. Merchant ships are required to maintain this watch by mechanical means and this method of watch is also permitted on fishing vessels. Merchant ships and fishing vessels required by the Regulations and Rules to carry radiotelegraph equipment must also maintain a continuous watch on the frequency of 500 kHz. On Merchant ships the watch is to be maintained by human means during working hours. These hours are specified in the ITU Radio Regulation. Outside of these hours, and all times on fishing vessels, the 500 kHz watch may be maintained by mechanical means. Ships and fishing vessels should, where practicable, maintain watch on VHF Ch 16 when within the service area of a coast station providing international maritime mobile radiotelephone service in the band 156-174 MHz. Ships and fishing vessels fitted only with VHF radiotelephone equipment operating in the authorized bands between 156 and 174 MHz should maintain on Ch 16 when at sea.

15. Any ships which receive a Distress message from a mobile station which is beyond any possible doubt in its vicinity must immediately acknowledge receipt. If however the mobile station in Distress is beyond any possible doubt not in the immediate vicinity, a short interval of time must be allowed before acknowledging receipt, so that ships nearer to the station in Distress can answer and acknowledge receipt without interference. The radio officer or operator is at once to inform the Master of the ship that he has received the "Distress Message" and whether or not he has been able to acknowledge it; he is also to inform the Master whether he has heard other ships acknowledging the "Distress Message" and what their relative positions are, if they have given them. He will then receive the Master's instructions on the action (if any) which he has taken with regard to the repetition of the Distress Message on 500 kHz, 2182 kHz or VHF Ch 16 as the case may be. All Distress messages and Distress traffic must be entered in full in radiotelegraph log or any radiotelephone log. Any ship which is not in a position to render assistance and which has heard a Distress message which has not been immediately

acknowledged, must take all possible steps to attract the attention of the ships that are in position to render assistance. For this purpose, on the authority of the Master, the Distress call and message may be repeated on the Distress frequency and on any other frequencies, which are known to be in use the neighbourhood at the time. Radio Distress signals are, of course, also received by Coast Radio Station.

16. When it appears that a point has been reached at which no additional assistance is required by casualty in the Distress situation, the Coast Radio Station, having consulted the Coastguard may ask the ship in Distress if the SOS (Mayday) phase may be ended so that normal working could resumed with caution on the Distress frequency and the subsequent communications from the casualty should be prefixed by URGENCY SIGNAL. The decision to make such a change is entirely the responsibility of the Master in Charge of the vessel in Distress; his every urgent situation may persist. When complete radio silence is no longer necessary on frequency, which is being used for Distress traffic the station, which has controlled the traffic, shall transmit:

(1) in radiotelegraph,

CQ DE

Call sign of station sending the message.

The time of handing in of the message.

The name and call sign of the ship in Distress.

QUZ

(2) in radiotelephony,

MAYDAY

HELLO ALL STATIONS THIS IS name of station sending the message.

The time of handing in of the message.

The name and call sign of the ship Distress.

PRUDONCE

If Distress working continues on other frequencies these will be identified in the transmission. For example:

(3) in radiotelegraphy,

QUZ on 500 kHz but QRT, 2182 kHz and VHF Ch 16.

(4) in radiotelephony,

PRUDONCE on 500 kHz and 2182 kHz but SEELONCE on VHF Ch 16.

Restricted working confined to calls related to the exchange of essential radio communications may then be made Distress frequency concerned but great care must be exercised to avoid interference with a subsequent resumption of Distress signals. The Distress situation must not be considered to have ended until the signal for the resumption of normal working, i.e. QUM (radiotelegraphy) or SEELONCE FEENEE (radiotelephony), has been given.

17. Many Malaysian ships are provided with radio equipment, portable or otherwise for use in the ship's survival craft. This equipment is capable of transmitting signals on 500 kHz and 8364 kHz, and may also be capable of transmitting signals on 2182 kHz. It will be capable of receiving signals on 500 kHz, and may also be capable of receiving signals on 2182 kHz. The equipment includes an automatic keying device which can be set at will to key the radiotelegraph alarm signal on 500 kHz followed by the Distress signal, or the Distress on 8634 kHz without the radiotelegraph alarm signal. They may carry equipment capable of sending out the two-tone alarm signal on the radiotelephony frequency of 2128 kHz.

VI. Private Distress message

18. It is understanding for a vessel in Distress to send a private message, bearing a specific address, asking for assistance because, if not general Distress message is sent out, the public authorities concerned will be unable to render assistance to the vessel in question or to take steps to make the need generally known in order that ships or persons may render assistance.

VII. Visual signals used between shore stations in Malaysia and ships in Distress

19. In the event of a ship being in Distress off or stranded on the coast of Malaysia, the following signals should be used by life-saving stations when communicating with her, and by the ship when communicating with life-saving stations.

- a. Replies from life-saving stations or maritime rescue units to Distress signals made by a ship or person:-

<u>Signals</u>	<u>Signification</u>
By day - Orange smoke signal or combined light and sound signal (thunder light) consisting of three single signals which are fired at interval of approximately one minute	"You are seen - assistance will be given as soon as possible"
By night - White star rocket consisting of three single signals which are fired at interval of approximately one minute.	(Repetition of such signals shall have the same meaning)

If necessary the day signals may be given at night or the night signal by day

- b. Landing signals for the guidance of small boats with crew or person in Distress

<u>Signals</u>	<u>Signification</u>
By day - Vertical motion of a white flag or the arms or signalling the code letter "K" (— · —) give by light or sound signal apparatus	
By night - Vertical motion of a white light or flare or signalling the code letter "K" (— · —) given by light or sound signal apparatus. A range (indication of direction) may be given by placing a steady white light or flare at a lower level and in line with the observer.	"This is the best place to land"
By day - Horizontal motion of a white flag or arms extended horizontally or signalling the code letter "S" (· · ·) given by light or sound signal apparatus.	
By night - Horizontal motion of a white light or flare or signalling the code letter "S" (· · ·) given by light or sound-signal apparatus	"Landing here highly dangerous"
By day - Horizontal motion of a white flag, followed by the placing of the white flag in the ground and the carrying of another white flag in the direction to be indicated and or a white star signal in the direction towards the better landing place or signalling the code letter "S" (· · ·) followed by the code letter "R" (· — ·) if a better landing place for a craft in Distress is located more to right in the direction of approach or signalling the code letter "L" (· — · ·) if a better place for a craft in Distress is located more to the left in the direction of approach	"Landing here highly dangerous. A more favourable location for landing is in the direction indicated"
By night - Horizontal motion of a white light or flare, followed by the placing of the white light or flare on the ground and the carrying of another white light or flare in the direction to be indicated and or a white star-signal in the direction towards the better	"Landing here highly dangerous. A more favourable location for landing is in the direction indicated"

landing place or signalling the code "S" (· · ·) followed by code letter "R" (· — ·) if a better landing place for the craft in Distress is located more to the right in the direction of approach or signalling the code letter "L" (· — · ·) if a better landing place for the craft in Distress is located more to the left in the direction of approach

- c. Signals to be employed in connection with the use of shore life-saving apparatus:-

<u>Signals</u>	<u>Signification</u>
By day - Vertical motion of a white flag or the arm	In general "Affirmative" Specially - -
By night - Vertical motion of a white flag or flare	"Rocket line is held" "Tail block is made fast" "Man is in the breeches buoy" "Haul away"
By day - Horizontal motion of a white flag or arms extended horizontally	In general "Negative"
By night - Horizontal motion of a white light or flare	Specifically - - "Slack away" "Avast hauling"

- d. Signal to be used to warn a ship which is standing into danger:-

<u>Signals</u>	<u>Signification</u>
The international Code Signals U or NF The letter U (· · —) flashed by lamp or made by foghorn, or whistle, etc	"You are running into danger"

If it should prove necessary, the attention of the vessel is called to these signals by a white flare, a rocket showing white stars on bursting, or an explosive sound signal.

20. Should lives be in danger and your vessel is in position where rescue by the rocket rescue equipment is possible, a rocket with line attached will be fired from the shore across your vessel. Get hold of this line as soon as you can. When you have get hold of it, signal to the shore as indicated in paragraph 19(c).

21. Should your vessel carry a line-throwing appliance, it may be preferable to use this and fire a line ashore, but this should not be done without first consulting the rescue company on shore. If this method is used, the rocket line may not be of sufficient strength to haul out the whip and jackstay and those on shore will secure it to a stouter rocket line. When this is done, they will signal as indicated in paragraph 19(c). On seeing the signal, haul in the line that was fired from the vessel until the stouter line is on board.

22. Then, the rocket line is held, make the appropriate signal to the shore (paragraph 19(c)) and proceed as follows:-

- When you see the appropriate signal, i.e "haul away" made from the shore haul upon the rocket line until you get a tail block with an endless fall rove through it (called the "whip") and with a jackstay attached to the bracket of the tail block.
- Cut or cast off the rocket line and make the tail block fast, close up to the mast or other convenient position, bearing in mind that the fall should be kept clear from chafing any part of the vessel. Before cutting or casting off the rocket line, make sure that you have the tail attached to the block well in hand. When the block is made fast, signal to shore again (paragraph 19(c)).

c. As soon as the signal is seen, the shore party will then set the jackstay taut, and by means of the whip will haul the breeches buoy out to the ship. The person to be rescued should get in to the breeches buoy and sit well down. When he is secure the should signal again to the shore as indicated in paragraph 19(c) and the men on shore will haul the person in the breeches buoy to the shore. When he is landed the empty breeches buoy will be hauled back to the ship. The operation will be repeated until all persons are landed.

d. During the course of the operations should it be necessary to signal, either from your ship to the shore or from the shore to your ship, to "Slack away" or "Avast hauling" this should be done as indicated as paragraph 19(c).

23. It may sometimes happen that the state of the weather and/or the condition or position of the ship will require the aforementioned procedures to be modified. Where this is the case, the rescue company will always attempt to advise you of the procedure to be followed.

24. Normally, all women, children, passengers and helpless persons should be landed before the crew of the vessel but that may be occasions when, perhaps because of the communication difficulties between the casualty and the rescue company ashore, it would be sensible if the first person to be landed were a responsible member of the ship's crew.

VIII. Use of rocket line-throwing apparatus between ships

25. Where in assisting ship proposes to establish communication by means of the line throwing apparatus she should before making her final approach ascertain whether or not it is safe for her to fire the rocket, particularly if the other ship is a tanker. If it is safe she should manoeuvre to WINDWARD before firing over the other ship's deck. If not, she should go to LEEWARD and prepare to receive a line. EXTREME CAUTION must be exercise when firing line-throwing rockets between ships when helicopters are in the vicinity.

26. When a vessel in Distress is carrying petrol spirit or other highly inflammable liquid and is leaking, the following signals should be exhibited to show that is dangerous to fire a line-carrying rocket by reason of the risk of ignition:-

By day - Flag B of the International Code of hoisted at masthead.

By night - A red light hoisted at the masthead.

When visibility is bad the above signals should be supplemented by the use of the following International Code signal made by sound:-

GU (— — . . . —) "It is not safe to fire a rocket."

USE OF THE RADIOTELEGRAPH AUTOMATIC KEYING DEVICE BY UNSKILLED PERSON IN AN EMERGENCY

1. On many radiotelegraph ships only one radio officer is carried. If by chance he were to be incapacitated through an accident, illness or other serious mishap whilst his ship was at sea, it might well be that there would be no one else on board capable of operating the radio equipment to send a Distress call if one were necessary. It is clearly desirable that some provision should be made, to the extent that it is practicable, for one or more other officers on such ships to be capable of sending Distress call.

2. All ships which are fitted with radiotelegraph installations in compliance with the Merchant Shipping (Radio Installations) Regulation 1980, (as amended), and the Merchant Shipping (Radio) (Fishing Vessel) Rules, 1974, (as amended), are provided with an automatic keying device which, once it is set in operation, will first of all alert other ships by actuating their auto-alarms, and then transmit the Distress call and also signals, repeated at interval, which would be invaluable in enabling other ships to home on to the Distressed ship by means of their direction-finding apparatus.

3. Investigation has shown that it is possible to produce simple set of instruction which will enable the automatic keying device to be the emergency transmitter and set in operation by an intelligent person unskilled in radio operation, provided that he can easily identify the controls which he need to use. Moreover, the instructions need differ only slightly according to the types of equipment provided in the ship, the differences being in the description of the controls. A standard drill has been evolved, based on the operation of six controls on four pieces of equipment (the charging board, the aerial selector or switch unit, the emergency transmitter and the automatic keying device) and an outline of the instructions is given for information in the Appendix below. It is not intended for operational use.

4. A number of points arise from the use of the procedure outline. In particular, it is emphasized that:-

a. The marine radio companies have drawn up and can supply specific procedures for operational use with each of their various types of equipment, based on the outline in the Appendix, and supplementing the control numbers with the precise description which is given to each equipment.

b. It is an essential part of the procedure that the controls in question should be prominently identified on the equipment by means of coloured (preferably yellow) labels numbered (preferably in red) to correspond with the operation referred to in the instruction in the Appendix. In cases where any confusion between individual controls might still be possible (e.g.) in selecting the correct switch on an old-type charging board) the correct control knob or switch should be Distinctively painted;

c. To ensure the best possible response from the transmission of the Distress call it is important for the person operating the equipment to wait, two minutes after the completion of the transmission of the alarm signal, before sending the Distress call. This will give time for the radio officers on other ships, if off duty, to man their equipment after being alerted. Even one minute's delay is better than none at all.

d. To procedure will be of little value in an emergency unless the ships officers most likely to use it are practiced in it, and the instructions applicable to their particular ship are ready to hand in a known place.

5. It is strongly recommended to owners and masters that, in radiotelegraph ship which carry only one radio officer, arrangements should be made for:-

a. The detailed instructions referred to in paragraph 4(a) of this Appendix to be posted conspicuously in the radiotelegraph room, preferably where they can be read by the light of the emergency lamps as well as by that of the main lighting system;

b. Yellow labels with red numbers to be affixed to the equipments, and for the correct control to be suitably coloured wherever confusion might arise;

c. Deck officers subsequently to familiarize themselves with the procedure might well also necessitate the use the emergency lighting in the radiotelegraph room. Knowledge of the

position of the door switch for the emergency lamp would be an important factor under these conditions. The door switch should be clearly labelled to indicate its purpose and the fact that the emergency light should only be used when the main source of light has failed.

6. The emergency conditions which might involve the use of this procedure might well also necessitate the use of the emergency lighting in the radiotelegraph room. Knowledge of the position of the door switch for the emergency lamp would be an important factor under these conditions. The door switch should be clearly labelled to indicate its purpose and the fact that the emergency light should only be used when the main source of light has failed.

Outline of "INSTRUCTION TO ENABLE UNSKILLED PERSONS TO SEND A DISTRESS CALL IN AN EMERGENCY".

First ensure that the auto-alarm supply switch (AA) is in the "OFF" position. Then:-

- | | |
|--|--|
| a. On the charging board | Set battery switch to "DECCHARGE" position (by means of CONTROL No 1). |
| b. On the aerial selector or switch unit | Connect emergency aerial to the emergency transmitter (by means of CONTROL No 2). |
| c. On the emergency transmitter | Switch on the emergency transmitter (by means of CONTROL No.3). CHECK whether transmitter is set for transmission on the DISTRESS frequency (500 kHz), (and if not, adjust appropriate controls as indicated in the detailed instructions posted in the radiotelegraph room. |
| d. On the automatic keying device | Connect to the emergency transmitter (by means of CONTROL No.4). Set to "ALARM" (by means of CONTROL No.5). Start transmission (by means of CONTROL No.6). |

The ALARM SIGNAL, consisting of a series of 12 dashes, will now be sent out, the transmission taking one minute to complete. If circumstances permit, wait a further two-minute or as near two minutes as possible to allow the radio equipment of the ships which have been alerted through their auto-alarms to be manned, then:

A DISTRESS CALL, consisting of the international Distress signal (SOS repeated three times), the Morse characters for the word DE, the call sign of the ship repeated three times (if this facility has been provided in the automatic keying device), followed by a long dash or by two dashes each of 10 to 15 second's duration which will be used by other ships for direction-finding purposes, will now be sent out.

If the equipment is left, this Distress call will be repeated every twelve minutes until the battery is run down or the transmission is stopped (by setting CONTROL No. 4 at the "OFF" position) and the transmitter is switched off (by means of CONTROL No. 3). These repetitions will help searchers to fix the position of your ship and will provide radio beacon facilities for ships proceeding to your assistance.

Note: This is only an outline of the procedure to be followed. It is quoted for information and should not be used operationally. See paragraph 4(a) of Appendix A.

RADIO TELEPHONE ALARM SIGNAL GENERATING DEVICE

The radiotelephone alarm signal which consist of two tones transmitted alternately over a period of at least 30 seconds but not exceeding one minute, is intended primarily for used by ship in Distress to give preliminary warning to other ships carrying radiotelephone equipment capable of receiving on the international radiotelephone Distress frequency, 2128 kHz, and to coast radio station, of the impending transmission of a Distress call message by means of radiotelephony. Like the radiotelegraph alarm signal its use is permitted only for this purpose or to announce the loss of a person overboard in circumstances where the assistance of other ships is required and cannot be satisfactorily obtained by the use of the urgency signal only. The signal may be generated automatically by an electronic device, which is used in conjunction with a radiotelephone transmitter set to emit signals on 2128 kHz.

Malaysia coast stations have been transmitting the signal as s prelude to Distress broadcast on radiotelephony for several years, and so most radiotelephone operators will be aware of the alerting value of its Dectinctive warbling sound which can readily be recognized by ear through heavy interference.

The Merchant Shipping (Radio Installations) Regulation 1980, (as amended), and the Merchant Shipping (Radio) (Fishing Vessel) Rules, 1974 (as amended), require that ships which carry radiotelephone equipment in accordance with those Rules and Regulations shall carry the alarm signal generating device as part of the radio installation.

14. MARITIME RESCUE COORDINATING CENTRE (MRCC) MALAYSIA

- | | | | |
|----|-------------------------------------|---|--|
| a. | Coordinator | : | Bahagian Carilamat dan Bantuan Bencana
Agensi Penguatkuasaan Maritim Malaysia
Kementerian Dalam Negeri
Tingkat 8, One IOI Square
IOI Resort
62502 PUTRAJAYA
Malaysia |
| b. | Primary function | : | Co-ordinating maritime search and rescue
operations within the Malaysian area of
responsibility |
| c. | Operation time | : | 24 hours |
| d. | Telephone No | : | +6 03 8941 3140
+6 03 8995 7821 |
| e. | E-mail | : | mrccputrajaya@mmea.gov.my |
| f. | Web site | : | www@mmea.gov.my |
| g. | Fax No | : | +6 03 8941 4527 (24 hours) |
| h. | Radio Communication: (SSB)
(HF1) | : | 8124 kHz (24 hours) |
| i. | (SSB)
(HF2) | : | Used in SAR Operations
2182 kHz
5680 kHz
4077 kHz
3023 kHz |
| | VHS | : | Channel 16 (24 hours)
TX : 156-075 MHz
RX : 160-675 MHz |
| | CALLSIGN | : | MRCC |

j. Secondary Function.

- (1) Providing and co-ordinating medical evacuation of injured seaman from ship to shore.
- (2) Detection of overdue vessel.
- (3) Investigation of report regarding safety of navigation.
- (4) Co-ordinating and assisting in salvage operations.
- (5) Providing technical information on safety of navigation.
- (6) Co-ordinating of operation to combat oil spill.
- (7) Receiving/ promulgating navigational warning.
- (8) Receiving vessel's position report.
- (9) Promotion of safety at sea.

k. Maritime Rescue Sub-Centre.

- | | | | |
|-----|--------------------|---------------|--------------------------------|
| (1) | MRSC Langkawi | Telephone No. | 604-9662750 |
| | | Fax No. | 604-9662768 |
| | | Call sign. | MRSC LANGKAWI |
| | | E-mail. | mrsclangkawi@mmea.gov.my |
| | | Radio:(GEN) | Chanel 201 |
| | | (HF) | 6435 kHz |
| (2) | MRSC Johor Bahru | Telephone No. | <u>607-2219231</u> |
| | | Fax No. | <u>607-2224739/607-2279285</u> |
| | | Call sign. | MRSC JOHOR BAHRU |
| | | E-mail. | mrsbjohorbharu@mmea.gov.my |
| | | Radio:(HF) | 6435 kHz |
| (3) | MRSC Kuantan | Telephone No. | 609-5717368 |
| | | Fax No. | 609-5733569 |
| | | Call sign. | MRSC KUANTAN |
| | | E-mail. | mrsckuantan@mmea.gov.my |
| | | Radio:(GEN) | Chanel 401,404 |
| | | (HF) | 6435 kHz |
| (4) | MRSC Kuching | Telephone No. | 6082-432544 |
| | | Fax No. | 6082-364941/6082-432554 |
| | | Telex. | LAUT MA 70933 |
| | | Call sign. | MRSC KUCHING |
| | | E-mail. | mrsckuching@mmea.gov.my |
| | | Radio:(GEN) | Chanel 401,404 |
| | | (HF) | 6435 kHz |
| (5) | MRSC Kota Kinabalu | Telephone No. | 6088-387774 |
| | | Fax No. | 6088-387444 |
| | | Call sign. | MRSC KOTA KINABALU |
| | | E-mail. | mrsckotakinabalu@mmea.gov.my |
| | | Radio:(GEN) | Chanel 401,404 |
| | | (HF) | 6435 kHz |

15. TRANSIT CORRIDORS WITHIN AREA OF MARITIME INTEREST

a. The Trilateral Cooperative Arrangement among Malaysia, Indonesia and Philippines has agreed for Establishment of Transit Corridors within the Area of Maritime Interest (AMI) between the east coast of Sabah and the western part of Sulu Archipelago. The Transit Corridors are not a traffic separation scheme and are not marked by aids to navigation.

b. The Transit Corridors will serve as safety areas which will be Patrolled to allow safe passage of Commercial Traffic. The limit of the Areas bounded by the following coordinates:

Area of Maritime Interest (AMI) (see ANNEX 1)


POINT	LATITUDE	LONGITUDE
A	07° 11'.00N	118° 32'.00E
B	05° 48'.00N	120° 30'.00E
C	04° 48'.00N	120° 30'.00E
D	03° 11'.33N	119° 23'.52E
E	03° 56'.00N	118° 22'.50E
F	05° 21'.00N	119° 21'.50E
G	06° 21'.00N	117° 57'.00E

Transit Corridors for Commercial Shipping (see ANNEX 1)

POINT	LATITUDE	LONGITUDE
1	06° 09'.26N	119° 59'.77E
2	05° 59'.60N	119° 48'.98E
3	05° 59'.60N	118° 27'.14E
4	05° 21'.00N	119° 21'.50E
5	04° 44'.98N	118° 56'.50E
6	04° 03'.50N	118° 56'.50E
9	03° 56'.50N	118° 56'.50E
16	03° 59'.23N	119° 00'.50E
17	04° 39'.72N	119° 00'.50E
7	04° 03'.00N	118° 27'.36E
8	03° 56'.00N	118° 22'.50E
10	03° 44'.21N	118° 38'.78E
11	03° 39'.81N	118° 44'.85E
12	04° 52'.76N	120° 30'.00E
13	05° 01'.28N	120° 30'.00E
14	04° 28'.13N	119° 42'.00E
15	04° 23'.27N	119° 35'.00E
23	05° 04'.58N	119° 35'.03E
24	05° 04'.58N	119° 42'.00E
18	05° 19'.00N	119° 28'.62E
19	05° 25'.07N	119° 28'.62E
20	05° 52'.60N	118° 49'.86E
21	05° 52'.60N	119° 47'.10E
22	05° 07'.75N	119° 35'.03E
25	05° 56'.50N	119° 56'.00E
26	06° 05'.13N	120° 05'.64E

ANNEX 1

TRANSIT CORRIDORS WITHIN AREA OF MARITIME INTEREST



- c. All vessels are required to use the Transit Corridors render report to the following agencies as stated below at least 24 hours before arrival at the AMI.

AGENCY	EMAIL ADDRESS/CONTACT
National Coast Watch Center (NCWC)	ncwatchcenter@gmail.com +63(2)2413104
Naval Operation Center (NOC), Philippine Navy	noc@nav.ph hpn.noc@navy.mil.ph +63(917)8512708 +63 {215244981
Coast Guard Command Center (CGCC), Philippine Coast Guard	cgac@coastguard.gov.ph +63(966)2179610 +63(9669)6418964
Naval Forces Western Mindanao Operation Center	nfwm.nfoc@navy.mil.ph nfoc.wm@gmail.com +63(917)6860681
Maritime Research Information Center (MRIC)	mrhc@nav.ph +63 (917)7085248 +63(2)8431833
Maritime Command Center (MCC), Tawau Malaysia	mcctawau2@gmail.com +6089 775600 +6089 779777 +6089 982623 (5.00 pm-8.00am)
Eastern Sabah Security Command (ESSCOM) Malaysia	opsroomesscom@gmail.com +6089 863181
Marine Department Malaysia, Sabah Region	www.marine.gov.my +6088 401111
Maritime Command Center (MCC), Tarakan Indonesia	mcctarakan2@gmail.com mcc_tarakan@tnial.mid.id +625513806288 +625513806289

- d. The following reporting procedure shall be rendered upon entering the AMI upon establishment of voice radio contact with the monitoring station:

'SECURITY, SECURITY... THIS IS (NAME OF VESSEL).

I AM ENTERING (NAME OF SEA LANE, BG: SIBUTU PASSAGE, ALICE CHANNEL, ETC.)

WITH A SPEED OF— AND COURSE —

PRESENT POSITION: (LATITUDE I LONGITUDE) OR AT VICINITY (NEAREST POINT OF REFERENCE)"

STATUS: (I.E. UNDERWAY, ALL IS WELL, UNDER ATTACK OR IN DISTRESS)

**IF UNDER ATTACK, REQUEST IMMEDIATE ASSISTANCE/RESCUE.*

- e. All vessels are also required to render POSREP and SITREP as they enter the maritime areas of common concern, and every hour or as necessary.

- f. Charts affected - MAL 6 - MAL 8421 - MAL 8434 - MAL 8503 - MAL 860.

16. PIRACY AND ARMED ROBBERY REPORTS

I. Attacks when Underway

Attacks on ship when underway are most common in South Asian waters. A large proportion of attacks in this area have occurred in the Selat Philip (Phillip Channels) and other Channels used by vessels making passage via the Malacca Strait. Other attacks have taken place in the South China Sea and in waters adjacent to The Philippines. Attacks can take place in either international waters as piracy or, more commonly, as armed robbery in territorial waters of a coastal state. Hitherto attacks carried knives or swords but recent evidence indicates that it is not safe assume that they are not carrying firearms. In one recent incident firebombs were carried and oil tanker.

II. Reports on the increase in the frequency of attacks

The ICC International Maritime Bureau has recently noted an increase in the frequency of piracy attacks on shipping within Indonesian Waters. In all the reported attacks the vessels were boarded, left without navigation, the crew tied up and their personal effects stolen. It is urged that vessels report each and every attack, in the format given below, so that an accurate assessment of the situation can be obtained as quickly as possible.

III. Recommended Practices

The recommended practices outlined below are based on reports of incidents, advice published by commercial interests and organisations and measures developed to enhance ship security. The extents to the recommendations are followed or applied are matters solely for the owners or masters of vessels operating in areas where attacks may occur.

IV. The Anti Attack Plan

All ship operating in waters where attack occurs should have an anti attack plan. The anti attack plan should be prepared having regard to the risks that may be faced, the crew available, their capability and training. The ability to establish secure areas on board the ship and the surveillance and detection equipment that has been provided. The plan should, *Inter alia*, cover:

- (a) The need for enhanced surveillance and the use lighting and surveillance or report detection equipment;
- (b) Crew responses if a potential attack is underway;
- (c) The radio and alarm procedures to be followed, and
- (d) The reports that should be made after an attack, or an attempted attack.

V. Radio Procedures

- (a) A suitably qualified Radio Operator should be on duty at all times when ships are in, or approaching, areas where attacks occur. The master should not perform this duty though, on occasions, this may be unavoidable.
- (b) Prior to entering areas where attacks have occurred Radio Operators should practice and perfect all appropriate radio operational procedures and ensure all transmitters, including satellite ship earth station, are fully operational and available for immediate use on Distress and safety frequencies. Where a GMDSS installation is provided and "ship" position" data is not automatically updated from an associated electronic navigation aid. Radio Operator is strongly recommended to enter ship's position at regular interval into the appropriate communications equipment manually. Where an Inmarsat ship earth station is provided it may prove useful to draft and store "standard messages" (see paragraph 33) for ready use in an emergency in either the equipment's memory or on computer Deck. Master should ensure that all procedures to generate a Distress alert on communications equipment are clearly marked on, or near, the equipment and all appropriate crew members brief on their operation.

(c) Master should bear in mind the possibility that attackers are monitoring ship to shore communications and using intercepted information to select their targets. Caution should, therefore, be exercised when transmitting information on cargo or valuable on board by radio in areas where attacks occur.

VI. Radio Watch keeping and Responses

(a) A constant radio watch should be maintained with the appropriate shore or naval authorities when in areas where attacks have occurred. Continuous watch should also be maintained on all Distress and safety frequencies, particularly VHF Channel 16 and 2182 kHz. Ship should also ensure all maritime safety information broadcasts for the areas are monitored. As it is anticipated that Inmarsat's Enhanced Group Calling system (EGC) will normally be used for such broadcast using the safety NET (SM) services, owner should ensure a suitably configured EGC receiver is continuously available when in, or approaching, areas where there is a risk of attacks. Owners should also consider fitting a dedicated receiver for this purpose, if one that is not incorporated into a Ship earth station used for commercial purposes, to ensure no urgent broadcast are missed.

(b) The International Maritime Organisation (IMO) recommends in MSC Circular 597, issued August 1992 that report concerning attacks by pirates or armed robbers should be made to the relevant Rescue Co-Ordination (RCC) for the area. MSC Circular 597 also recommends that governments should arrange for the RCCs to be able to pass reports of attacks to the appropriate law enforcement agencies or naval authorities.

(c) If suspicious movements are identified which may result in an imminent attack, the ship is advised to contact the relevant RCC. Where the master believes these movements could constitute a direct danger to navigation consideration should be given to the broadcasting an "All Stations (CQ)" "danger message" as a warning to other ships in the vicinity as well as appropriate RCC. A danger message should be transmitted in plain language on VHF working frequencies following and announcement on VHF Channel 16 and or transmission of a DSC call on VHF Channel 70 using the "safety" priority. All such message shall be preceded by the safety signal (Security).

(d) When, in his opinion, there is conclusive evidence that the safety of his ship is threatened, the master should immediately contact the relevant RCC and, if considered appropriate, authorise broadcast of an "All Station" "Urgency Message" on VHF Channel 16, 2182 kHz, or any other radio communications service he considers appropriate; e.g. 500 kHz, Inmarsat, etc. All such message shall be preceded by the appropriate Urgency signal (PANPAN) and or a DSC call on VHF Channel 70 and or 2187.5 kHz using the "all ships urgency" category. If the Urgency signal has been used and an attack does not, in fact, develop the ship should cancel the message as soon as it knows that action is no longer necessary. This message of cancellation should likewise be addressed to "all station".

(e) Should an attack occur and in the opinion of the master, the ship or crew are in grave and imminent danger requiring immediate assistance, he should immediately authorise the broadcasting of a Distress message, preceded by the appropriate Distress alert (MAYDAY, SOS, DSC, etc), using all available radio communication systems. The appropriate RCC should acknowledge receipt and attempt to establish communications. To minimise delay, if using a ship earth station, ships should ensure the coast earth station with the RCC is used.

(f) Master should bear in mind that the Distress signal is provided for use only in case of imminent danger and its use for less urgent purpose might result in insufficient attention being paid to calls from ship really in need of immediate. Care and Decretion must be employed in its use, to prevent its devaluation in the future. Where the transmission of the Distress signal is not fully justified use should be made of the Urgency signal. The Urgency signal has priority over all communication other than Distress.

V. Standard Message Format

The standard formats for:

- (a) Initial message piracy attack alert, and
- (b) Piracy attack/sighting/suspicious act report, which was agreed by the IMO Sub Committee on Radio Communications in January 1993, is set out in ANNEX 1.

VI. Secreted VHF Transceiver

If communications equipment has been damaged by attackers to prevent an early alarm being raised, particularly when attacks have taken place off port owners and masters are recommended to secrete a VHF transceiver on the ship to allow contact to be established with the shore authorities if the main communications equipment is put of action.

VII. Action after an Attack and Reporting Incidents

(a) An immediate post attack report should be made to the relevant RCC and through them to the law enforcement agencies or naval authorities of the coastal State. As well as information on the identity and location of the ship, any injuries to crew members or damage to the ship should be reported as should the direction in which the attackers departed together with brief details of their numbers and, if possible a description of their craft. If the crew have apprehended an attacker, it should also be reported in this signal.

(b) If an attack has resulted in the death of or serious injury to any person on board the ship or serious damage to the ship itself, an immediate signal should also be sent to the ship's maritime administration. There are in any event, statutory requirements covering the duty to report deaths, serious injuries or serious damage to a ship to the maritime administration. In any event a report of an attack is vital if follow up action is to be taken by the ship's maritime administration. The text of this Merchant Shipping Notice may be amended to reflect experience based on the reports submitted to maritime administrations and also on reports submitted to the IMO by other flag States or by coastal States.

ANNEX 1

INITIAL MESSAGE - PIRACY ATTACK ALERT

1. Vessel's name and call sign/ Inmarsat ID (Plus ocean region code).

MAYDAY (See Note)
PIRACY ATTACK
2. Vessel's position (and time of position UTC)
3. Nature of event.

NOTE: It is expected that this message will be a Distress Message because the vessel or person will be in grave or imminent danger when under attack. Where this is not the case, the word MAYDAY is to be omitted.

Use of Distress priority (3) in the Inmarsat system will not require MAYDAY to be included.

PIRACY ATTACK / SIGHTING / SUSPICIOUS ACT REPORT

1. Vessel's name and call sign.
2. Reference initial PIRACY ALERT.
3. Position of incident.
4. Date / time of incident (UTC).
5. Detail of incident, e.g.
 - Method of attack
 - Description of suspect craft
 - Number and brief description of pirates
 - Injuries to crew
 - Damage to ship
 - Brief details of stolen property/cargo.
6. Last observed movements of pirate / suspect vessel, e.g.
Date/time/course position/cargo.
7. Assistance required.
8. Preferred communications with reporting vessel'
Appropriate Coast Radio Station.
HF/MF/VHF. Inmarsat ID (plus ocean region code).
9. Date / time of report (UTC).

SOUTH EAST ASIA, REGIONAL PIRACY COUNTERMEASURES CENTRE (RPCC) - KUALA LUMPUR

The International Maritime Bureau (IMB) of the International Chamber of Commerce has established a Piracy Countermeasures Centre at Kuala Lumpur, Malaysia. This centre operates for the South East Asia Region and is able to receive reports from vessels about piracy attacks within this region and advise of danger areas where attacks have recently taken places. The services provided by the centre are free of charge to all vessels irrespective of their flag.

Piracy warning originated by the centre will be transmitted daily to NAVAREA XI, VIII and X through Enhanced Group Calling (EGC) using the International safety NET System (see GLOBAL MARITIME DISTRESS AND SAFETY SYSTEM (GMDSS) section for details of the Safety NET System). At future date, messages will also be broadcast through the NAVTEX service.

The Centre operates 24/7, 365 days a year, and can be contacted as follows:

The Regional Piracy Countermeasures Centre
ICC International Maritime Bureau
Jalan Sultan Ismail, P.O. Box 12559, WP Kuala Lumpur, 52050 KUALA LUMPUR
Malaysia

Anti-Piracy HELPLINE Numbers :
Telephone : + 60 3 2031 0014
Fax : + 60 3 2078 5769
E-Mail : ccs@icc-ccs.org

17. RADIO NAVIGATIONAL WARNINGS

NAVAREA XI Warning

a. In the World Wide Navigational Service (WWNWS) network, Malaysian Waters are AREA XI and the Area Coordinator is Japan.

b. Details of NAVAREA XI Navigational Warning are as follows:

1. Matters of broadcast: Those concerning the waters where ocean going vessels navigational within the NAVAREA XI.

2. Broadcast Schedules:

NAVAREA	COAST STATION	CALLSIGN	FREQUENCIES	EMISSION TIME (GMT)
NAVAREA XI	TOKYO (Maritime Safety Agency)	JNA	4676 8492 12942 17052.5 22398	AI 0005* 0805* 1205* 0405#

* Main Broadcast

Repeat

Detail of Transmission

(1) Power: 5 km

(2) Broadcast will be made on the first three main schedules after receipt of information and thereafter at the requested time of 0405 GMT on days 2, 5, 8, 11, 14, 17, 20 and 23 counting day of the third main broadcast as day 1.

(3) A NAVAREA Warning Bulletin listing the numbers of in force warnings issued during the last 6 weeks will also be broadcast at 0005 GMT every Sunday.

(4) Simultaneous transmissions on all frequencies.

Coastal Navigation Warnings

c. Mariners engaging in coastal navigational warnings by the Malaysian National Coordinator:

Marine Department Peninsular Malaysia
PT 664
Jalan Limbungan
Port Klang, Malaysia
(Telex: MA 39748)
(Telegraph Address: Marine, Port Klang)

d. Details of transmission are as follow:

Nation	Radio Station	Call sign	Emission & frequency (kHz)		Times (UTC)
Malaysia	Penang	9MGS	A1A	522.5	□
Malaysia	Klang	VHF 16 Ch.	-	-	#
Malaysia	Kuantan	VHF 16 Ch.	-	-	#

- Transmit at 0148, 0548, 0948, 1348, 1748 & 2148 hours.

e. Coastal navigation warning contain information relating to the principal aids to navigation and other important hydrographic matter in around Malaysian Waters, such as:

1. Casualties to major lights, light vessels and the more important buoys.

2. Drifting mines and derelicts in congested water when the information is recent and sufficiently accurate.
 3. Large and unwieldy tows in congested waters.
 4. Dangerous wrecks and new or amended shoal depths.
 5. Establishment of salvage buoys in congested waters.
 6. Areas where Search and Rescue (SAR) and anti-pollution operation are being carried out (for avoidance of such areas).
 7. Radio beacons, VHS radio Lighthouse - significant casualties.
 8. New position of mobile drilling rig (RIG MOVES).
- f. Those warning are repeated at routine times as message so long as they remain in force. No serial numbers are given to the message and a cessation of broadcasting indicates that they are either cancelled for sufficiently promulgated in the Malaysia Notices to Mariners.
- g. Coastal navigation warning can only be expected to give information to assist the mariner about immediate dangers and major alterations to important navigation aids. The purpose is to assist mariners in coastal navigation up to the subject of a Notices to Mariners or local warning, may not be broadcast. Attention is drawn to *Admiralty List of Radio Signal Volume 1* for details of radio broadcasts.
- h. Masters are recommended to arrange, whenever possible, for a radio operator or an office to listen at scheduled times prior to sailing at which this information is broadcast, in the case any dangers affecting their routes are notified. Attention is however drawn to be caution on buoys in "General remarks relating to practical navigation in the *Mariners Hand Book* (NP 100). This caution especially applies to light buoys and buoys in expose positions which are liable to be operating in correctly or to break adrift without warning.

18. FIRING PRACTICE AND EXERCISE AREAS

- a. Firing and bombing practices and military exercises usually take place in number of areas off the Malaysian Coast.
- b. In view of the responsibility of range authorities to avoid accidents, limit of firing & bombing practice area will not as rule be shown on charts and description of such areas will not appear in Sailing Directions. Range beacons, lights and marking buoys as may be of assistance to the mariners or targets which might be a danger to navigation, will however be shown on charts and appropriate mention in Sailing Directions.
- c. The principal types of practices carried out are:
1. **Bombing practice from aircraft.** Warning signals usually shown. This carried out by aircraft at a large white or red sleeve, banner, a winged target, or flag towed by another aircraft moving on a steady course.
 2. **Air to air and air to sea ground firing.** This is carried out from aircraft at towed or stationary targets on sea or land, the firing normally takes place to seaward in the case of those on land. As a general rule, warning signals are shown when the targets are stationary, but not when towed target are used. All mariner crafts operating as range safety craft or target-towing vessels will Decplay for identification purposes, while in vicinity of the danger area, a large red flag at the masthead.
 3. **Anti aircraft firing.** This may be from Anti Aircraft (AA) guns or Marhine guns at a target towed by aircrafts as in Para b. above at Pilot less Target Aircraft (PTA). Practice may takes place from shore batteries or ships. Warning signal as rule is shown from shore batteries. Ships fly a red flag.

4. **Firing from shore batteries or ships at sea fixed or floating targets.**

Warning signal usually shown as in above.

d. Warning signals when given usually consist of red flag by day and red fixed, or red flashing lights at night. The absence of any such signal cannot, however, be accepted as evidence that a practice area does not exist. Warning signals are shown from shortly before practice commences until it ceases. Ships and aircraft carrying out night exercise may illuminate with bright colour flares. To avoid confusion with international Distress signals, red or orange flares will be used in emergency only.

e. **CAUTION.** A vessel may be aware of the existence of a practice area from Local Notices to Mariners or similar method of promulgation and by observing the warning signals or the

practice. The Range Authorities are responsible for ensuring that there should be no risk of damage from falling shell-splinters, bullets, etc. to any vessel, which may be in practice area.

f. If however a vessel finds, herself in an area where practice is in progress, she should maintain her course and speed but, if she is prevented from doing this by the exigencies of navigation, it would assist the Range Authority if she would endeavour to clear the area at the earliest possible moment. Furthermore if projectiles or splinters are observed to be falling near the vessel, all person on board should take cover.

g. Fisherman operating in the vicinity of firing practice and exercise areas may occasionally bring unexploded missiles or portions of them to the surface in their nets or trawls. These objects may be dangerous and should be treated with great circumspection and jettisoned immediately, no attempt being made to tamper with them or bring them back for inspection by Naval Authorities.

h. Areas are only force intermittently or over limited periods and local promulgation of warning by radio, visual signals or Notices should be such that they will come to the attention of those whose cooperation or instruction is intended.

i. The fore going provision do not apply to Submarine Exercise Areas.

19. INFORMATION CONCERNING SUBMARINE

NUMERICAL INDEX

No	Subject	Page
1.	Numerical Index	57
2.	Abbreviation	58
Malaysian Submarine Exercise Area		
3.	Malaysian Submarine Exercise Area	58
4.	Activities Affecting Submarine Operations	59
5.	Coordinating Agency	60
6.	Disclaimer	60
7.	Notification	60
8.	Point of Contact	60
Information Concerning Submarines		
9.	Warning Signal	61
10.	Submarines Operating in Areas Outside the Promulgated MSEA	61
11.	Navigation Lights	61
12.	Sunken Submarine	62
13.	Submarine Emergency Radio Beacon	63
14.	Submarine Launched One-Way Transmission Buoy	63
Submarines and Fishing Vessel		
15.	Periscope Depth	64
16.	Recommended Action for Fishing Vessel when Operating within MSEA	64

ABBREVIATION

ABBREVIATION	MEANING
CATAS	Critical Angle Towed Array Sonar
DTAS	Depressed Towed Array Sonar
MCM	Mine Counter Measure
MDV	Mine Disposal Vehicle
MMEA	Malaysian Maritime Enforcement Agency
MSEA	Malaysian Submarine Exercise Area
RMN	Royal Malaysian Navy
RMN SUBOPAETH	RMN Submarine Operating Authority
RMN SC HQ	RMN Submarine Command Headquarters
ROV	Remotely Operated Vehicle
SARSAT	Search and Rescue Satellite
SCC	Submarine Control Centre
SERB	Submarine Emergency Radio Beacon
SLOT BUOY	Submarine Launched One-Way Transmission Buoy

Malaysian Submarine Exercise Area

1. The Malaysian Government has established a Permanent Submarine Exercise Area known as the **MSEA** within Malaysian waters. MSEA is aimed to provide a safe area for Malaysian submarines to conduct its operations.

2. The MSEA is established in three (3) areas as follows:

a. **MSEA 1** is bounded by the following coordinates (see **Annex 1**):

- (1) 08° 20.00'N 113°35.00'E.
- (2) 08° 20.00'N 115°45.00'E.
- (3) 06° 52.26'N 115°45.00'E.
- (4) 06° 22.97'N 116°19.76'E.
- (5) 06° 14.52'N 116°11.40'E.
- (6) 06° 02.79'N 116°06.72'E.
- (7) 05° 51.00'N 116°02.00'E.
- (8) 06° 01.36'N 115°50.00'E.
- (9) 06° 00.00'N 115°36.00'E.
- (10) 06° 00.00'N 114°10.00'E.
- (11) 06° 40.00'N 113°35.00'E.

b. **MSEA 2** is bounded by the following coordinates (see **Annex 2**):

- (1) 06° 20.00'N 110° 30.00'E.
- (2) 04° 40.00'N 110° 30.00'E.
- (3) 04° 40.00'N 113° 45.00'E.
- (4) 05° 00.00'N 113° 45.00'E.
- (5) 05° 00.00'N 113° 30.00'E.
- (6) 06° 20.00'N 112° 30.00'E.

c. **MSEA 3** is bounded by the following coordinates (see **Annex 3**):

- (1) 05° 20.80'N 104° 00.03'E.
- (2) 05° 20.80'N 105° 36.03'E.
- (3) 05° 05.50'N 105° 28.83'E.
- (4) 04° 03.80'N 104° 51.93'E.
- (5) 03° 50.90'N 104° 46.53'E.
- (6) 02° 56.00'N 104° 51.33'E.
- (7) 02° 23.30'N 105° 01.23'E.
- (8) 01° 55.20'N 105° 05.23'E.
- (9) 01° 38.80'N 104° 53.03'E.
- (10) 01° 23.89'N 104° 29.08'E.
- (11) 01° 17.75'N 104° 29.36'E.
- (12) 01° 16.35'N 104° 28.48'E.
- (13) 01° 16.85'N 104° 19.11'E.
- (14) 01° 16.82'N 104° 16.18'E.
- (15) 01° 14.45'N 104° 12.70'E.
- (16) 01° 16.45'N 104° 09.50'E.
- (17) 01° 16.82'N 104° 07.04'E.
- (18) 01° 17.83'N 104° 04.09'E.
- (19) 01° 18.22'N 104° 02.12'E.
- (20) 01° 18.43'N 104° 07.53'E.
- (21) 01° 22.85'N 104° 17.53'E.
- (22) 01° 28.80'N 104° 20.03'E.
- (23) 01° 40.80'N 104° 15.03'E.
- (24) 02° 00.80'N 104° 15.03'E.
- (25) 02° 20.80'N 104° 00.03'E.

Activities Affecting Submarine Operations

3. To facilitate the safety of Malaysian submarine operations, the conduct of any of the following activities in the MSEA shall be notified to the Coordinating Agency (see paragraph 4) and RMN SUBOPAETH as stated in paragraph 5:

- a. Weapon firing serials (including serials where ordnance is released from aircraft);
- b. Towed bodies and arrays operations i.e. Variable Depth Sonar (VDS), DTAS and CATAS;
- c. Mine Counter Measure (MCM) and Mine Warfare Operations including Mine Disposal Vehicle (MDV) activities;
- d. Dived submersible operations i.e. Submarine Rescue Vehicle (SRV);
- e. ROV operations;
- f. Diving operations;
- g. Deep-sea coring and drilling activities;
- h. Hydrocarbon exploration and exploitation activities;

- i. Any type of survey at sea; or
- j. Any other activities that may jeopardize the safety of the submarines.

Coordinating Agency

4. The Coordinating Agency for MSEA is the Malaysian National Security Council. The coordinating agency is responsible for supervision and coordination of the MSEA with the support of the RMN SUBOPAUTH based in the RMN SC HQ in Kota Kinabalu, Sabah, Malaysia.

5. A Submarine Control Centre (SCC) has been established in the RMN SC HQ to assist RMN SUBOPAUTH in the management of the MSEA.

Disclaimer

6. The Malaysian Government shall not be responsible for any damage to or loss of ships, equipment, and life, caused by the failure to inform the usage of MSEA in advance to the Coordinating Agency and RMN SUBOPAUTH.

Notification

7. Notification for the use of MSEA shall be made 7 days prior to the commencement of any activity to the Coordinating Agency in the form as per **Annex 4**.

Point of Contact

8. Any enquiries concerning MSEA may be directed to either of the following agencies:

- a. National Security Council (Coordinating Agency):

Level 2, West Block
Perdana Putra Building
Federal Government Administrative Centre
62502 PUTRAJAYA
Malaysia

Phone : +603-88726846
Email : bkkm@mkn.gov.my

- b. RMN SUBOPAUTH/RMN SCC:

RMN Submarine Command Headquarters
Kota Kinabalu Naval Base
Sepangar Bay
88846 KOTA KINABALU
Sabah, Malaysia

Phone : +6088-350591
Email : pkkstldm@navy.mil.my

INFORMATION CONCERNING SUBMARINES

Warning Signals

1. Mariners are warned that considerable hazard to life may result from the disregard of the following signals which denote the presence of submarines:

a. **Visual Signals.** Warships fly the International Code Group 'NE2" to denote that submarines which may be submerged are in the vicinity. Vessels are cautioned to steer so as to give a wide berth to any vessel flying this signal. If from any cause it is necessary to approach her, a good look-out must be kept for submarines whose presence may be indicated only by their periscopes or snort masts showing above the water.

b. **Pyrotechnics and Smoke Candles.** The following signals are used by submerged submarines:

Signal	Signification
White smoke candle (with flame)..... Yellow smoke candles Yellow and green pyrotechnic flares	Indicates position in response to request from ship or aircraft or as required.
Red pyrotechnic flares..... (may be accompanied by smoke candles repeated as often as possible)	Keep clear I am carrying out emergency surfacing procedure. Do not stop propellers. Clear the immediate area, but stand by to render assistance

Note: If the red pyrotechnic flare signal is sighted and the submarine does not surface within 5 minutes it should be assumed that the submarine is in Distress and has sunk. An immediate attempt should be made to fix the position in which the signal was sighted, after which action in accordance with should be taken.

2. It must not be inferred from the above that submarines exercise only when in company with escorting vessels.

Submarines Operating in Areas other than Promulgated MSEA

3. The note Submarine Exercise Area on certain charts should not be read to mean that submarines do not exercise outside such areas. Under normal circumstances, the majority of submarine exercise activity will be limited to MSEA. However, this does not preclude exercises or operations in other areas, in such cases participating units will make or display appropriate warning signals. Under certain circumstances, warnings that submarines are exercising in specified areas may be broadcast by a coast radio station or promulgated in printed navigational warnings. These areas are known as Submarine Operating Area.

Navigation Lights

4. Malaysian submarines have their masthead and side lights placed well forward and very low over the water in proportion to the length and tonnage of these vessels. In particular:

- a. Some submarines can only show a forward masthead light in calm confined waters;
- b. The main masthead light may be well forward of the mid-point of the submarine's length.

5. Emergency Stern lights are placed at the end of the bridge fin, and may at times be partially obscured by spray and wash. In some cases the emergency stern lights will be well near to the masthead light of the submarine, and thus will not give a true indication of the submarine's length. They are invariably lower than the side lights.

6. The after light (used as stern light at sea) of submarines at anchor is mounted on the upper rudder, which is some distance astern of the hull's surface waterline. Care must be taken to avoid confusion with two separate vessels of less than 50 meters in length.

7. The overall arrangement of submarine lights is therefore unusual and may well give the impression of markedly smaller and shorter vessels than they are. Their vulnerability to collision when proceeding on the surface dictates particular caution when approaching them.

8. Nearly all submarines are fitted with an amber quick-flashing light situated above or abaft the main steaming light. This additional light is for use as an aid to identification in narrow waters and areas of dense traffic as well as in unfavourable weather conditions such as heavy rain and fog. Malaysian SCORPENE class submarines exhibit a very quick flashing yellow (VQ.Y) identification light of 120 flashes per minute. This identification light should not be confused with an air cushion vessel operating in a non-displacement mode which displays the same light.

Sunken Submarine

9. A bottomed submarine which is unable to surface will try to indicate Distress by launching a red grenade and shall mark her position upon located by assisting vessel by firing candles giving off red smoke of any colour available either on the approach of the surface vessel or at a regular basis.

Note: It should be remembered that it may be impossible for a submarine to fire her smoke candles. Correspondingly a partially flooded submarine may have only a certain number of her smoke candles available and searching ships should not therefore expect many to appear.

10. Since oil slicks or debris may be the only indication of the presence or whereabouts of the sunken submarine, it is vitally important that surface ships refrain from discharging anything which might appear to have come from a submarine while they are in the submarine probability area. Searching ships and aircraft can waste many valuable hours investigating these false contacts.

11. Some submarine pyrotechnics can be fitted with message carriers. If a message has been attached, the pyrotechnic will be fitted with a dye marker, giving off a yellowish-green dye on the surface. Such a pyrotechnic should be recovered as soon as it has finished burning.

12. The sighting of any beacon answering the attached description should at once be reported by the quickest available means to the RMN SF HQ. However, if vessels are unable to establish communications without leaving the vicinity of the submarine, it should be borne in mind that the primary consideration should be for vessels to remain standing by to rescue survivors and not leave the scene of the accident. Every effort should be made to include in the report the serial number of the beacon; this number is affixed on top of the Submarine Emergency Radio Beacon (SERB).

13. At any time after a submarine accident, survivors may start attempting to escape. Current policy dictates that survivors will wait before escaping until:

- a. Rescue vessels are known to be standing by; or
- b. Conditions inside the submarine deteriorate to such an extent that an attempt to escape must be made.

14. It should be noted that in certain circumstances the situation paragraph 13(b) might not arise through lack of air supply until a time after the accident of several days. However, if the submarine is badly damaged, survivors may have to make an escape attempt immediately. Any ship finding a SERB should not therefore leave the position but stand by well clear ready to pick up survivors. The latter will ascent nearly vertically, and it is plainly important plenty of sea room is given to enable them to do so in safety. On arrival on the surface men may be exhausted or ill, and if circumstances are favourable therefore the presence of a boat already lowered is very desirable. Some men may require a recompression chamber, and it will therefore be the aim of the RMN authorities to get such a chamber to the scene as soon as possible.

15. In order that those trapped in the submarine shall be made aware that help is at hand, RMN vessels drop small charges into the sea, which can be heard from inside the submarine. There is no objection to the use of small charges for this purpose, but it is vital that they are not dropped too close since men in the process of making ascents are particularly vulnerable to underwater explosions and may easily receive fatal injuries. A distance of a quarter of a mile is considered to be safe. If no small charges are available, the running of an echo sounder or the banging of the outer skin of the ship's hull with a hammer from a position below the water-line is likely to be heard in the submarine, and such banging and/or sounding should therefore be carried out at frequent intervals.

16. Submarines may at any time release pyrotechnic floats, which on reaching the surface burn with flame and/or smoke thus serving to mark the position of the wreck. They are likely to acknowledge sound signals by this means.

17. To sum up, the aims of a submarine rescue operation are:

- a. To fix the exact position of the submarine.
- b. To get a ship standing by to pick up survivors if practicable with boats already lowered.
- c. To get medical assistance to survivors picked up.
- d. To get a diver's decompression chamber to the scene in case this is required by those seriously ill after being exposed to great pressure.
- e. To inform the trapped men that help is at hand.
- f. To notify appropriate authorities.

18. There is a RMN organisation designed to fulfil these aims which are always kept at instant readiness for action. It is clear, however, that any ship may at any time find evidence of a submarine disaster, and if she takes prompt and correct action as described above she may be in a position to play a vital part.

Submarine Emergency Radio Beacon (SERB)

19. This beacon is made of aluminium, coloured orange and is cylindrical in shape, with two whip aerials. The beacon is fitted with an automatic transmitting unit, battery life of 48 hours operating on the following frequencies:

- a. 406.025 MHz COSPAS/SARSAT.
- b. 243 MHz Military Air Guard.
- c. 121.5 MHz Civil Air Guard.

Submarine Launched One-Way Transmission Buoy

20. This buoy is used for tactical communications between submarines and warships/aircraft. It can, however, be fired in an emergency default mode in which case it will transmit a SABRE tone on 243 MHz Military Air Guard.

21. A general description of Submarine Launched One-Way Transmission (SLOT) Buoy, smoke candles fired from submarines and aircraft float, smoke and flame markers is as follows:

- a. **White Smoke Candles.** These are fired from submarines to indicate their position. They burn for up to 15 minutes emitting white smoke and flame and can thus be seen day or night; they can easily be confused with aircraft marine markers and floats smoke and flame.
- b. **Green Smoke Candles.** These are fired from submarines to indicate their position. They burn for about five minutes emitting green smoke. They can be seen more easily than the white smoke candles in rough weather but cannot be seen at night.

22. The above may frequently be encountered in areas where warships and aircraft exercise, whether or not submarines are present, and should not be confused with submarine emergency buoys and beacons. In case of doubt, the object should be approached to confirm, visually, whether or not it is a submarine emergency buoy or beacon before reporting it.

SUBMARINES AND FISHING VESSEL


Periscope Depth

1. Submarine dived below Periscope Depth (PD) must remain at least 2 nautical miles clear of any fishing vessel engage in fishing. The submarine would return to PD when it is necessary. To assist submarines in identifying fishing vessels and maintaining the separation distances, ships are to inform submarine whenever a fishing vessel approaches within 6,000 yards of the ship.
2. To minimize the risk to fishing vessels operating in areas of submarine activity. It also explains how to obtain information about submarine activity and what action fishing vessel skippers need to take when operating in areas of submarine activity, particularly in the event of motive power being lost.


Recommended Action for Fishing Vessel when Operating within MSEA

3. Before carrying out, and during, fishing operations in a known submarine exercise area, skippers are strongly urged to make use of the NAVTEX and NTM broadcasts or the other services. Unless the skipper consents to a request by RMN personnel to do otherwise, or unless there is any doubt that sufficient radiated noise is being generated, normal fishing operations need not be affected by a submarine exercise and skippers need only ensure that proper navigational and radio watch on VHF Channel 16 is maintained.
4. In the event of a total power failure, there would be no radiated noise from the fishing vessel for a submarine to detect. If this were to occur in a known submarine exercise area, which had been declared active, the skipper should contact the RMN SCC for immediately advising them of his situation, and for the best interest of safe navigation, the skipper should consider marking and releasing the fishing gear for later recovery.
5. If the fishing vessel has stopped in the water but power to work the nets and any other machinery is available, then provided the nets or other machinery are being operated, the radiated noise should be sufficient to alert the submarine. Skippers should also ensure that all electronic equipment which generates impulses in the water (e.g. SONAR/echo sounder) is operating. If motive power cannot be restored in a short time scale, or there are any doubts about the vessel's capacity to generate sufficient radiated noise, the skipper should contact RMN SCC to advise them of his situation.
6. Submarines at PD make a careful visual assessment of the surface situation. A number of incidents have occurred because surface crafts have been showing incorrect navigation lights or no lights at all. It is therefore essential that at all times vessels display correct lights and signals in accordance with the International Regulations for Preventing Collisions at Sea.


MSEA 1



MSEA 2



MSEA 3



MALAYSIAN SUBMARINE EXERCISE AREA USAGE FORM

To:
National Security Council (Coordinating Agency)
 Level 2, West Wing
 Perdana Putra Building
 Federal Government Administrative Center
 62502 PUTRAJAYA Malaysia

Phone : +603-88726846
 Email : bkkm@mkn.gov.my

Copy to:
RMN Submarine Command Headquarters
 Kota Kinabalu Naval Base, Sepangar Bay
 88846 KOTA KINABALU
 Sabah
 Malaysia

Phone : +6088-350591
 Email : pkkstldm@navy.mil.my

Part I - Ship Data			
Vessel's Name		Type	
IMO Registration No		Flag State	
Max Breadth (m)		Draught (m)	
Displacement (Tonnes)		Height of Mast (M)	
Length (m)			
Part II - Operations			
Commencing Date & Time		Ending Date & Time	
Nature of Works		Latitude (WGS 84)	Longitude (WGS 84)
Depth of Water Engaged (m)		North	East
MSEA's Area Concerned	1/ 2/ 3		
Part III- Ship's Complement			
Name of Master			
Number of Crew			
Part IV - Communications / Radio Transmission			
Ship's Call Sign		Satellite Phone No	
Type of Emission		E-mail	
Frequency			
Part V - Other Relevant Information			
Applicant's Signature		Designation	
Applicant's Name		Date (dd/mm/yy)	

Part VI - Remarks (Official Use Only)			
<u>Coordinating Agency</u>		<u>RMN Submarine Commander</u>	
Signature		Signature	
Name		Name	
Appointment	(Official Stamp)	Rank	(Official Stamp)
Date (dd/mm/yy)		Date (dd/mm/yy)	

20. CAUTION WITH REGARD TO SHIP APPROACHING SQUADRON CONVOYS AND OTHER WARSHIPS AT SEA

Formation and Convoys

- a. The attention of ship owners and mariners is called to danger to all concerned which is caused by single vessels approaching a formation of warships, or merchant vessels in convoy, so closely as to involve risk of collision, attempting to pass ahead of, or through such a formation or convoy.
- b. Mariners are therefore warned that single vessels should adopt early measures to keep out of the way of a formation or convoy.
- c. Although a single is advised to keep out of the way of a formation or convoy.

Ships Operating Aircraft

- d. Attention is called to the uncertainty of movements of warships when aircraft or helicopters are operating to or from their decks. Such ships are required usually to steer a course, which is determined by the wind direction. While operating aircraft or helicopters from their decks, warship will show the light and shapes prescribed by *Rule 27 9b) of the Regulation for Preventing Collisions at Sea, 1972*. Aircraft carriers may display red or white deck lighting during night flying operations, and ships operating helicopters at night use red or white flood lighting.
- e. Furthermore, mariners are warned that by night aircraft carriers have:
 - 1. Their masthead lights placed permanently off the centre line of the ship, and at considerably reduced horizontal separation.
 - 2. Alternative positions for their side lights:
 - (a) On either side of the hull.
 - (b) On either side of the island structure, in which case the port side light may be as much as 30 meters from the port side of the ship.
- f. Certain aircraft carriers when at anchor exhibit four white lights as follows:
 - 1. In the forward of the vessel at the distance of not more than 1.5 meters below the light deck, two lights in the same horizontal plane, one on the starboard side.
 - 2. In the after part of the vessel at a height of not less than 5 meters lower than the forward lights, two lights in same horizontal plane one on the starboard side.
 - 3. Each light visible over an arc at least 180°. The forward lights visible over a minimum arc from one point on the opposite bow to one point from right astern on their own side, and the after lights from one point on the opposite quarter to one point from light ahead on their own side.

Replenishment at Sea

- g. Warships in conjunction with auxiliaries frequently exercise *Replenishment at Sea*. While doing so, the two or more ships taking part are connected by jackstays and hoses. They display the signal prescribed by *Rule 27(b)* of the above Regulations.
- h. Mariners are warned that while carrying out replenishment with auxiliaries frequently exercise; the ships are severely restricted, both in manoeuvrability and speed. Other vessels are therefore advised to keep well clear in accordance with *Rule 18(a)* of the above Regulations.

Certain Warships - Position of Steaming Lights

- i. Certain warship, which, in accordance with *Rule 23 Annex and Annex 1* of the above Regulations, cannot comply fully with the requirements as to the positioning of lights, comply as closely as possible.
- j. The principal departures from the Regulations are as follows:-
 - 1. The height above the hull of the lower main masthead light is either less than the breadth of the vessel, or less than 12 metres and not always in the forwards quarter of the vessel.
 - 2. The horizontal distances between masthead lights is less than half the length of the vessel.

Survey Vessels

- k. Survey vessels while carrying out hydrographic or oceanographic surveys will display the signals prescribed in *Rule 27(b)* of the above Regulations. The ship may also show an international two-letter group stating - ***I am engaged in submarine survey work. You should keep clear of me.***
- l. Mariners are warned that while carrying out this work, which may often be run across the normal shipping lanes, survey ships may be towing instrument up to 300 metres astern. These will restrict their manoeuvrability and ability to change speed or stop quickly. Other vessels are therefore are advised to keep well clear in accordance with *Rule 18 (a)* of the above Regulations, giving a clearance of at least 0.5 miles if passing astern.

21. SUBMARINE CABLES AND PIPELINES

Caution against Anchoring and Trawling in Vicinity

- a. Mariners are warned that every care should be taken to avoid anchoring or trawling in the vicinity of pipelines or submarine cables on account of the serious consequences which would result from fouling them.

Symbols

- b. Cables, cable areas, pipelines and pipeline areas will eventually be shown on all charts in magenta; but some symbols still appear on older charts in black.
- c. Submarine cables are shown as wavy lines, which may have accompanying legend "power". Submarine cable areas may be shown bounded by pecked lines with the legend "Cable Areas" (older charts) or by dashed T-shape lines interspersed with short section of the wavy cable symbol. Disused cable is shown by an interrupted wavy cable symbol.
- d. Submarine pipelines have been shown by a pecked line carrying the legend "Pipe, or Pipeline", or in respect of those transporting natural gas, "Gas Pipeline" with an additional cautionary note. Pipeline areas are shown by pecked line, with the legend Pipeline Area (see publication MAL).

Danger Involved in Cutting to Clear Anchors or Fishing Gear

- e. In the event of any vessel fouling a submarine cable, every effort should be made to clear the anchor or gear by normal method; should these efforts fail, the anchor or gear should be slipped and abandoned without attempting to cut the cable. High voltages are fed into certain submarine cables other than power transmission cables; serious risk exists of loss of life due to electric shock, or at least severe burns, if any attempt to cut the cable is made. No claim in respect of injury or damage sustained through such interference with a submarine cable will be entertained.
- f. In the event of any vessel fouling a pipeline the anchor or gear should be slipped and abandoned without attempting to get it clear. Any excessive force applied could result in a

rupture; in the case of a gas pipeline the consequential sudden release of gas at high pressure - somewhat like an explosion - could cause serious damage or loss of the vessel, and there would be an accompanying severe and immediate fire hazard.

Damage to International Cables

g. The International Cable Protection Committee (ICPC) wishes to give wide Dissemination to the notice, reprinted below, regarding prevention of damage to International Cables.

1. Modern high capacity repeater type submarine cables now cross the oceans and seas of the world. Cables of increasing capacity are being designed and will continue to be laid for many years to come. Activity on the sea bed could very easily damage cable, put it out of service and cause considerable disruption and interruption and world communications. Disruption of world telecommunications could be prolonged if repair is delayed due to disposition of cable ships at the time and weather hazards.

2. One of the main objectives of the ICPC and on eon, which they are continually working, is to make known the existence of and the location of submarine cables. Charts showing cable positions are available from many Hydrographic Offices and universal charting of cables has been endorsed by the International Hydrographic Organisation.

3. The ICPC has been asked to remain those interests are on or below the seabed to be sure that they are aware of submarine cable positions in their area of operation. Most of the leading companies and administrations in the telecommunication world are members ICPC and are ready and willing to furnish details of cable positions on request. If there is any difficulty in obtaining cable information, requests are to address to the Secretary ICPC, Mercury House, Theobalds Road, London WC1X 8 RX.

22. DEVELOPMENT OF OFFSHORE OIL AND GAS FIELDS

Seismic Surveys

a. Seismic surveys for offshore oil and mineral resource explorations are conducted in and around Malaysian Waters. Details of these surveys are generally broadcast to marines as a Radio Navigational Warning or by Notice to Mariners. It is seldom practicable to publish details of the areas of operation except in general terms and vessels carrying out seismic surveys may, therefore, be encountered without prior notice.

b. Two types of survey are practiced:

1. Seismic reflection surveys

This is by far the most common form of operation. The surveys vessel tows a multi-channel receiver cable of up to 3kms in length, at a depth of a few metres, with the end marked by a tail buoy and radar reflector. The seismic energy source usually an array of air guns mounted below large marker buoys and towed immediately behind the vessel. The arrays may have lateral extent of a hundred metres or more.

2. Seismic refraction surveys

(i) Single vessel operation

The seismic vessel tows a conventional source array (e.g. air guns) away from a stationary sonar buoy. The buoy contains an amplifier and radio transmitter, which transmit the received signals to a shipboard recorder. In the rare case of long range (40 - 50 Km) experiments, explosive charges are used.

(ii) Two vessels operation

One vessel tows a conventional reflection acquisition system (24000m.cable) away from another vessel at a fixed location firing a source array. Survey vessels generally carry the signals described in Rules 23 (a), 24 (a) and 27 (b) and (c). They may also show the signals PO and IR (International Code). The shooting vessel may display signal B (International Code) or at night a single red light addition.

c. Survey vessels are unable to manoeuvre freely and masters should therefore give them a wide berth (approximately 4 to 5 KM).

d. Refraction survey vessel occasionally keeps radio silence if charges are fired by radio so as to avoid any uncontrolled firings. Vessel being called by light by a survey vessel should therefore answer by the same means and not by a radio or radiotelephone.

Oil Rigs and Production Platforms

e. There are two principal types of drilling rigs in use at present in Malaysian offshore fields:-

1. Jack-up Rigs: - These are propelled or towed in position where their steel legs are lowered to the seabed; the drilling platform is then jacked-up clear of the water. They are generally used in depths up to 100 metres.

2. Dynamic Positioning Drill Ship: - These are built with a tall drilling rig amidships and usually with a helicopter deck near the stern. A typical drill ship has a displacement of 14,000 tons, a length of 135m and maximum speed of 14 knots. For drilling in depth of less than 200 metres, 8 point anchoring system is used. When drilling in deep water, their position is maintained by dynamic positioning equipment which enables these drill ship to keep on station above the borehole. A feature of the drill ship with automated station keeping facilities is their ability to manoeuvre accurately, with the aid of thrusters fitted with controlled pitch propeller. These are used in depth above 2000 metres.

Wellheads

f. In the course of exploratory work, numerous wells are drilled to find extent of the field. Wells, which will not be required, again are sealed with cement below the seabed and abandoned.

g. Other wells, known as suspend wells, which may be required at a later date, have their wellheads capped and left with a pipe and other equipment projecting from the seabed. Such wellheads are sometimes marked by buoys to assist recovery and to warn the mariners that they are a hazard to navigation or fishing.

Production Platforms

h. These are massive structures carrying drilling and production equipment, oil and gas separation and treating plants, pump line stations, electricity generators, cranes and helicopter landing deck. They are marked by lights, fog signals, and on some platforms flares burn at time. Production Platform is charted. Platforms stand singly or in groups, linked to each other by pipelines. A trunk pipeline connects them to the shore, storage tanker, tanker loading buoy or a floating terminal.

Safety Zones (Legal Sanctions) - Other Areas

i. **Safety Zones : Under International Law** a coastal state may construct and maintain on the continental shelf, installations and other devices necessary for the exploration of its natural resources, established safety zones around such installations, and take within these zones measures for their protection. Safety zones may extend to a distance of 5000 metres around installations, measured from their outer edges. Ships of all nationalities are required to respect these safety zones.

j. **Safety Zones: In their National Law** many coastal states have made entry by unauthorized vessels into declared zones varies from states, mariners are advised always to assume the existence of a safety zones unless they have information to the contrary.

Installations around which safety zone may have been established include fixed platform, mobile rigs (While on station), tanker loading moorings, and seabed installations such as submerged wellheads.

k. **Safety zones: Installations in the Malaysian Waters** are covered under the Exclusive Economic Zones (EEZ) Act 1984. Entry into safety zones by an unauthorized vessel makes the owner, master, and others who may have contributed to the offence, liable to a fine or imprisonment or both.

l. **Areas extending beyond 500 metres from installations:**

1. Certain fields which are being development, or are currently producing oil or gas, are designated Development Areas. Within these areas, the limits of which are charted, there are likely to be construction and maintenance vessels including submarine craft, divers and obstructions, possibly marked by buoys. Supply vessels, and in some cases tankers, frequently manoeuvre in these fields. Mariners are strongly advised to keep outside such areas.

2. Some coastal states have declared prohibitions on entry into, or on fishing and anchoring within, areas extending beyond 500 metres from installations.

23. CAUTION WITH REGARD TO RELIABILITY OF NAVIGATIONAL BUOYS

a. Navigational buoys operated by the Marine Department are intended to provide a general, rather than a precise means of marking hazards of turning points.

b. Most of these buoys are situated in exposed locations well away from port areas.

c. The actual buoy position may differ from the charted position for one or more reasons.

d. Mariners are therefore cautioned against using buoys as the sole means of establishing their position.

24. REPORT OF SHOAL OBTAINED BY ECHO SOUNDING: INSTRUCTIONS REGARDING RENDERING REPORTS

Depths Obtained by Echo Sounder

a. A several reports of depths obtained by echo sounder (E/S) are received in the National Hydrographic Centre, Royal Malaysian Navy, Port Klang and the Hydrographer RMN is appreciative of the time and effort spent in rendering them.

b. To assist in verifying the report the following details should be given where applicable:

1) Ship's name

2) Date

3) Courses, speeds and positional information to allow the ship's track to be plotted, or a tracing of portion of a chart showing the ship's track and times.

4) Make, model and stylus speed/sound velocity setting of echo sounder.

5) Whether E/S set to read depth below the keel or below the sea surface.

6) Ship's draught.

c. The E/S trace (which should always accompany the report) should be annotated to assist in reduction of the sounding, as follows:

1) Drawing a line across it (or making it by pressing the fix push, if fitted) each time a fix is taken and at a number of intermediate points at set time intervals. With a

set having a rotating stylus, a fix line can be obtained by drawing a line across the curved edge of the scale, taking care not to foul the stylus.

- 2) Inserting the times of each fix and each line.
- 3) Inserting the recorded depth of all shoal (peak) soundings.
- 4) Marking the limits of the phase or scale range in which the set running noting particularly when a change is made, In cases where the E/S paper is not pre-printed with the scale of depths, a scale should be drawn in a convenient part of the E/S trace.
- 5) Marking if with the name of the ship, date and scale reading on the left hand edge of the transmission line.

d. It may not be generally realized that false sounding may be obtained from correctly adjust E/S set due to one the following causes.

- 1) The retuning echo being received after the transmission interval has been completed once or perhaps twice, e.g. with rotary type E/S set having a maximum scale reading of 1097.28 mts, a reading on the trace of 91.44 mts might in facts be a sounding of 92628.72 or even 2286.0 metres. (In the case of E/S sets fitted with transmitter ON/OFF switches such doubt can be resolved by breaking the transmission circuit, with the set still running and then re-making it, it is only necessary to note the number of the subsequent stylus revolutions occurring before the echo re-appears).
- 2) Dense shoals of fish or layers of plankton, which sometimes give an echo completely masking that from the bottom. Such a layer is usually known as a "deep scattering layer" and is often found to rise towards the surface at dusk and after remaining during the night close to the surface, descends again at dawn. The deep scattering layer is frequently encountered at or near the edge of the continental shelf and is frequently mistaken for shoal water.
- 3) Layer of water of different temperature density from that of the surrounding water can sometimes give false echoes.
- 4) Strong tidal stream or eddies with solid particles in suspension, which may give a feathery echo.
- 5) It is possible in the more powerful types of E/S sets now being developed that, double echoes may be obtained even in depths of several hundred metres. The second echo caused by the rebounding ultrasonic waves will appear at twice the depth of the true echo. Care should be taken when phasing and using the on/off switch, as described above that in fact the echo is being recorded. The second echo is invariably weaker than the first and can be faded by turning down the sensitivity of the receiver.

e. When unexpected shoal sounding are obtained in waters where the charted depth gives no indication, even though Deccoloured water may be seen, the only certain method of confirmation of their existence is by taking a coast with the lead.

f. Where, however the charted depth is nowhere more than scale reading of the set and the shoal is seen to rise from the bottom on the trace, provide the speed and setting of the set are correct, the shoal sounding may be accepted unconditionally.

g. When report of shoal sounding not confirmed by a cast of the lead are received in the National Hydrographic Centre, unless there is other confirmatory evidence of their existence, the National Hydrographic Centre has no choice but to enter them on the charts affected with notation that the depth has not been verified and to take the first opportunity to investigate the area to verify or Deprove them. Vessels passing the vicinity of such unverified shoals should when practicable take sounding to confirm their existence.

25. TEMPORARY AND PRELIMINARY NOTICES

NUMERICAL INDEX OF NOTICE IN FORCE AS 31ST DECEMBER 2025

Notice No	Page	Notice No	Page	Notice No	Page
34(T)*/2021	76	69(T)*/2023	83	245(T)*/2025	90
48(T)*/2021	76	109(T)*/2023	83	275(T)*/2025	91
49(T)*/2021	76	110(T)*/2023	83	276(T)*/2025	91
50(T)*/2021	76	162(T)*/2023	84	297(T)*/2025	91
73(T)*/2021	76	163(T)*/2023	84	298(T)*/2025	91
74(T)*/2021	77	166(T)*/2023	84	299(T)*/2025	91
75(T)*/2021	77	167(T)*/2023	84	300(T)*/2025	92
76(T)*/2021	77	226(T)*/2023	84		
77(T)*/2021	77	33(T)*/2024	85		
79(T)*/2021	77	36(T)*/2024	85		
125(T)*/2021	78	38(T)*/2024	85		
126(T)*/2021	78	47(T)*/2024	85		
127(T)*/2021	78	48(T)*/2024	85		
140(T)*/2021	78	67(T)*/2024	86		
177(T)*/2021	78	71(T)*/2024	86		
180 (T)*/2021	79	130(T)*/2024	86		
204(T)*/2021	79	218(T)*/2024	86		
220(T)*/2021	79	219(T)*/2024	86		
222(T)*/2021	79	246(T)*/2024	87		
223(T)*/2021	79	247(T)*/2024	87		
41(T)*/2022	80	248(T)*/2024	87		
57(T)*/2022	80	249(T)*/2024	87		
81(T)*/2022	80	250(T)*/2024	87		
96(T)*/2022	80	254(T)*/2024	88		
97(T)*/2022	80	40(T)*/2025	88		
109(T)*/2022	81	42(T)*/2025	88		
110(T)*/2022	81	43*/2025	88		
125(T)*/2022	81	71(T)*/2025	88		
133(T)*/2022	81	93(T)*/2025	89		
136(T)*/2022	81	141(T)*/2025	89		
154(T)*/2022	82	162(T)*/2025	89		
155(T)*/2022	82	163(T)*/2025	89		
156(T)*/2022	82	189(T)*/2025	89		
173(T)*/2022	82	191(T)*/2025	90		
187(T)*/2022	82	192(T)*/2025	90		
188(T)*/2022	83	193(T)*/2025	90		
41(T)*/2023	83	194(T)*/2025	90		

34(T)*/2021 MALAYSIA - Terengganu - South China Sea - Light Beacons.

Source: Marine Department of Malaysia No. 304/2020(T).

1. Bintang-A light beacon, in position 06°33'.75N, 103°17'.52E and Bintang-B light beacon, in position 06°33'.61N, 103°15'.08E is temporarily unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 5 - MAL 664 - MAL 68.
-

48(T)*/2021 MALAYSIA - Sabah - Beting Mengalum - Buoy.

Source: National Hydrographic Centre.

1. Current Meter Buoy, in position 06°20'.00N, 115°27'.50E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 872.
-

49(T)*/2021 MALAYSIA - Sarawak - Kuala Baram - Buoy.

Source: Sarawak Marine Department No. 16/2021(T).

1. Wreck Marking Buoy, *Al.Oc.BuY.3s*, in position 04°40'.38N, 113°58'.61E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 750 - MAL 752 - MAL 754.
-

50(T)*/2021 MALAYSIA - Sarawak - Kuala Baram - Buoy.

Source: Sarawak Marine Department No. 18/2021(T).

1. Special Mark Buoy (A), *Fl.Y.5s*, in position 04°36'.28N, 113°54'.67E is temporarily unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 6 - MAL 750 - MAL 752 - MAL 754.
-

73(T)*/2021 MALAYSIA - Sabah - Terusan Tando Bulong - Beacons.

Source: Royal Malaysian Navy.

1. Beacon P4 and Beacon No.9 *Fl.5s5m5M*, in position 04°24'.24N, 118°35'.98E and 04°24'.22N, 118°36'.50E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 8433.
-

74(T)*/2021 MALAYSIA - Sabah - Terusan Tando Bulong - Buoy.

Source: Royal Malaysian Navy.

1. Buoy *Fl 5s*, in position 04°24'.58N, 118°35'.88E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 8433.
-

75(T)*/2021 MALAYSIA - Sarawak - Pelabuhan Bintulu - Buoy.

Source: Sarawak Marine Department No. 25/2021(T).

1. Buoy *K Fl.G.5s*, in position 03°15'.14N, 113°02'.55E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 7317 - MAL 7332 .
-

76(T)*/2021 MALAYSIA - Sabah - Terusan Tando Bulong - Beacons.

Source: Royal Malaysian Navy.

1. Beacon P6 and Beacon S5, in position 04°24'.76N, 118°35'.68E and 04°24'.59N, 118°36'.01E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 8433.
-

77(T)*/2021 MALAYSIA - Sabah - Terusan Tando Bulong - Beacon.

Source: Royal Malaysian Navy.

1. Beacon S9, in position 04°25'.54N, 118°34'.65E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 8433.
-

79(T)*/2021 MALAYSIA - Sabah - Terusan Tando Bulong - Buoy.

Source: Royal Malaysian Navy.

1. Buoy *Fl.10s*, in position 04°23'.48N, 118°36'.27E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 8433 - MAL 8434.
-

125(T)*/2021 MALAYSIA - Pahang - Kuantan - Light Beacon.

Source: Marine Department of Malaysia No. 98/2021(T).

1. Light Beacon KP.5 Q.G.15m18M, in position 03°56'.81N, 103°28'.44E is temporarily unlit.
 3. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 4. Charts affected - MAL 6359 - MAL 6400.
-

126(T)*/2021 MALAYSIA - Pahang - Sungai Kuantan - Buoy.

Source: Marine Department of Malaysia No. 65/2021(T).

1. Wreck Buoy *Fl. Y. 5s*, in position 03°47'.45N, 103°21'.16E is temporarily unlit.
 3. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 4. Charts affected - MAL 6359.
-

127(T)*/2021 MALAYSIA - Pahang - Pulau Tioman - Light Beacon.

Source: Marine Department of Malaysia No. 112/2021(T).

1. Light Beacon Q.G.3.5m5M, in position 02°49'.13N, 104°09'.38E is temporarily unlit.
 3. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 4. Charts affected - MAL 625 - MAL 6257 - MAL 635.
-

140(T)*/2021 MALAYSIA - Pahang - Pelabuhan Kuantan - Light Buoy.

Source: Marine Department of Malaysia No. 130/2021(T).

1. Inner Light Buoy *LFl. 10s*, in position 03°55'.52N, 103°29'.15E is temporarily unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 6359 - MAL 6400 - MAL 645.
-

177(T)*/2021 MALAYSIA - Selangor - Kuala Langat - Light Buoy.

Source: Marine Department of Malaysia No. 142/2021(T).

1. Kuala Langat 1G Light Bouy *FL(3)G10s*, in position 02°48'.00N, 101°21'.03E is off station.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 5255.
-

180(T)*/2021 MALAYSIA - Perak - Selat Manjung (Dinding) - Light Beacon.

Source: Marine Department of Malaysia No. 158,159/2021(T).

1. Muroh Light Beacon Fl.R.11m5M, 04°13'.33N, 100°35'.10E and Llyod Q.R.10m8M, 04°15'.43N, 100°35'.09E are temporarily unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 5416 - MAL 5419 - MAL 5425.
-

204(T)*/2021 MALAYSIA - Sabah - Sandakan - Beacon.

Source: National Hydrographic Centre.

1. Batuan Sim sim Beacon FL(2)5s, in position 05°50'.13N, 118°07'.34E is temporarily unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 8553 - MAL 8617.
-

220(T)*/2021 MALAYSIA - Pulau Pinang - N Tg. Tokong - Light Buoy.

Source: Marine Department of Malaysia No. 172/2021(T).

1. Penang No.4 Light Buoy Fl.G.2s, in position 05°31'.26N, 100°18'.45E is off station.
 2. Mariners are advised to navigate with caution in the area.
(WGS 84)
 3. Charts affected - MAL 5536 - MAL 554.
-

222(T)*/2021 MALAYSIA - Pahang - Pelabuhan Kuantan - Beacon.

Source: Marine Department of Malaysia No. 195/2021(T).

1. NDWT Breakwater 3G Beacon Fl.G.3s11m10M, in position 03°58'.49N, 103°26'.76E is temporarily unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS 84)
 3. Charts affected - MAL 6359 - MAL 6400.
-

223(T)*/2021 MALAYSIA - Kedah - Kuala Muda - Light Beacon.

Source: Marine Department of Malaysia No. 196/2021(T).

1. Kuala Muda Light Beacon Fl.3s10m8M, in position 05°34'.73N, 100°19'.84E is temporarily unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS 84)
 3. Charts affected - MAL 5536 - MAL 554 - MAL 565.
-

41(T)*/2022 MALAYSIA - Sarawak - Pasir Dua Belas - Buoy.

Source: Sarawak Marine Department No. 29/2022(T).

1. Outer Bouy Muara Lassa *Fl.G.3s*, in position 02°52'.43N, 111°24'.51E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 7257 - MAL 740.
-

57(T)*/2022 MALAYSIA - Pahang - Tg. Gelang - Light Buoy.

Source: Marine Department of Malaysia No. 29R/2022.

1. Outer Light Buoy *Is.6s6M*, in position 03°55'.73N, 103°33'.05E is destroyed and move to 03°54'.75N, 103°33'.19E.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 6400 - MAL 645
-

81(T)*/2022 MALAYSIA - Melaka - Tg. Tuan - Light Bouy.

Source: Marine Department of Malaysia No. 70/2022(T).

1. Tg. Tuan Light Bouy *Fl.Y.5s*, in position 02°24'.40N, 101°50'.75E is off station.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 5230 - MAL 532.
-

96(T)*/2022 MALAYSIA - Terengganu - Pelabuhan Kemaman - Light Beacon.

Source: Marine Department of Malaysia No. 83(T)/2022.

1. Light beacon No.8 Q.R.21m12M, in position 04°15'.02N, 103°27'.57E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 6416 - MAL 645.
-

97(T)*/2022 MALAYSIA - Selangor - Kuala Selat Lumut – Light Bouy.

Source: Marine Department of Malaysia No. 87(T)/2022.

1. Terusan Lightbouy *Fl.R.10s*, in position 02°51'.48N, 101°15'.35E is off station.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 5255 - MAL 532.
-

109(T)*/2022 MALAYSIA - Terengganu - P. Redang - Light Beacon.

Source: Marine Department of Malaysia No. 91/2022(T).

1. Light Beacon Fl.10s132m10M, in position 05°44'.60N, 103°00'.20E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 654 - MAL 664 - MAL 68 .
-

110(T)*/2022 MALAYSIA - Terengganu - Tg. Berhala - Light Beacon.

Source: Marine Department of Malaysia No. 105/2022(T).

1. Tg. Berhala Light Beacon Q.G.21m12M, in position 04°15'.40N, 103°27'.73E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected - MAL 6416.
-

125(T)*/2022 MALAYSIA - Sabah - Pulau gaya - Lighthouse.

Source: Sabah Marine Department No. 16/2022(T).

1. Lighthouse Pulau Gaya, Fl.10s169m15M, in position 06°02'.36N, 116°00'.75E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 6 - MAL 8608 - MAL 864 - MAL 865 - MAL 872.
-

133(T)*/2022 MALAYSIA - Pahang - Pelabuhan Kuantan - Light Beacon.

Source: Marine Department of Malaysia No. 81(T)/2022.

1. Kuantan Port Rear Light Beacon, Oc.G.5s34m15M, in position 03°58'.94N, 103°25'.49E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 6359 - MAL 6400.
-

136(T)*/2022 MALAYSIA - Selangor - Pulau Indah - Buoy.

Source: Marine Department of Malaysia No. 145(R)/2022.

1. Mahang 1 buoy, Fl.G.2s, in position 02°54'.36N, 101°16'.47E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 5255 - MAL 5259.
-

154(T)*/2022 MALAYSIA - Pulau Langkawi - P.Enggang - Buoys.

Source: KD PERANTAU.

1. Bouy Enggang 1Y *Fl. Y10s* and Enggang 2Y *Fl(4)Y. 10s*, in position 06°14'.20N, 099°53'.40E and 06°15'.00N, 099°53'.50E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 5622 - MAL 5630.
-

155(T)*/2022 MALAYSIA - Pulau Langkawi - Pelabuhan Kuah, Teluk Sambar - Beacon and Buoy.

Source: KD PERANTAU.

1. Beacon *Fl.G.5s5m5M* and bouy *Fl. Y.5s*, in position 06°17'.60N, 099°51'.05E and 06°18'.18N, 099°50'.88E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 5622 - MAL 5630.
-

156(T)*/2022 MALAYSIA - Sabah - Teluk Sepanggar - Buoy.

Source: Royal Malaysian Navy.

1. Buoy *Fl. Y*, in position 06°04'.53N, 116°06'.36E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected - MAL 8608.
-

173(T)*/2022 MALAYSIA - Sarawak - Pelabuhan Bintulu - Light Beacon.

Source: Sarawak Marine Department No. 145(T)/2022.

1. Beacon No.24B, *Iso.Or.4s5M*, in position 03°16'.10N, 113°03'.25E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected - MAL 7317
-

187(T)*/2022 MALAYSIA - Pahang - Pulau Tioman - Light Beacon.

Source: Marine Department of Malaysia No. 199(T)/2022.

1. Light beacon *Q.R.3.5m5M*, in position 02°49'.16N, 104°09'.39E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 625 - MAL 6257 - MAL 635.
-

188(T)*/2022 MALAYSIA - Pahang - Kuala Endau - Light Buoy.

Source: Marine Department of Malaysia No. 200(T)/2022.

1. Kuala Endau Light buoy *Fl.G*, in position 02°40'.06N, 103°38'.45E is off station.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 625.
-

41(T)*/2023 MALAYSIA - Sarawak - Tanjung Baram - Buoy.

Source: Sarawak Marine Department No. 13(T)/2023.

1. Starboard Hand Buoy No. 2, *Fl.R.4s*, in position 04°37'.27N, 113°56'.18E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 750 - MAL 752 - MAL 754.
-

69(T)*/2023 MALAYSIA - Pahang - Pontian - Light Beacon.

Source: Marine Department of Malaysia No. 45(T)/2023.

1. Batuan Pontian Light Beacon, *Fl.5s8m8M*, in position 02°45'.38N, 103°36'.69E is off unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 625 - MAL 635 - MAL 65.
-

109(T)*/2023 MALAYSIA - Johor - Tg. Bin - Light Beacon.

Source: Marine Department of Malaysia No. 111(T)/2023.

1. Light Beacon *Iso.WRG.10s18m24M-21M*, in position 01°19'.97N, 103°33'.70E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 5123 - MAL 5128 - MAL 5129 - MAL 515.
-

110(T)*/2023 MALAYSIA - Sarawak - Tg. sirik - Lighthouse.

Source: Sarawak Marine Department No. 82(T)/2023.

1. Lighthouse *Fl.10s38m23M*, in position 02°46'.76N, 111°19'.31E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 7257 - MAL 731 - MAL 740.
-

162(T)*/2023 MALAYSIA - Terengganu - Pelabuhan Kemaman - Light Beacon.

Source: Marine Department of Malaysia No. 204/2023(T).

1. Chukai No.2 Light Beacon, *Fl.R.5s*, in position 04°14'.04N, 103°25'.76E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected - MAL 6416.
-

163(T)*/2023 MALAYSIA - Terengganu - Pelabuhan Kertih - Light Buoy.

Source: Marine Department of Malaysia No. 206/2023(T).

1. Kertih Port No.2R Light Buoy, *Q.R.5M*, in position 04°35'.92N, 103°27'.67E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 6436 - MAL 6441.
-

166(T)*/2023 MALAYSIA - Sarawak - Kuala Baram - Light Buoy.

Source: Sarawak Marine Department No. 128/2023(T).

1. Special Mark Buoy B, *Fl.Y.5s*, in position 04°33'.70N, 113°54'.82E is off station and move 04°34'.07N, 113°57'.50E.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 750 - MAL 752- MAL 754.
-

167(T)*/2023 MALAYSIA - Terengganu - Tg. Berhala - Light Beacon.

Source: Marine Department of Malaysia No. 230(T)/2023.

1. Tg. Berhala No.7 Light Beacon *Q.G.21m12M*, in position 04°15'.40N, 103°27'.73E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected - MAL 6416
-

226(T)*/2023 MALAYSIA - Terengganu - Pelabuhan Kerteh - Light Bouy.

Source: Marine Department of Malaysia No. 276(T), 284(T)/2023

1. Kerteh Port No. 6, *Fl(2).R.4s5M*, in position 04°35'.05N, 103°27'.59E and Kerteh Port No. 3, *Fl.G.5s5M*, 04°35'.60N, 103°27'.45E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected - MAL 6436 - MAL 6441.
-

33(T)*/2024 MALAYSIA – Terengganu – Pelabuhan Kemaman – Light Bouy.

Source: Marine Department of Malaysia No. 19(T)/2024.

1. Tanjung Berhala No.1, *Fl.G.5s*, in position 04°13'.70N, 103°29'.31E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 6416 – MAL 645.
-

36(T)*/2024 MALAYSIA – Sarawak – Pelabuhan Bintulu – Buoy.

Source: Sarawak Marine Department No. 6(T)/2024.

1. Starboard - Hand Buoy, *Fl.G.4s*, in position 03°11'.10N, 113°01'.66E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 7317 – MAL 7332.
-

38(T)*/2024 MALAYSIA – Sarawak – Tanjung Baram – Buoy.

Source: Sarawak Marine Department No. 13(T)/2024.

1. Starboard Hand Buoy No. 1, *Fl.G.4s*, in position 04°36'.35N, 113°55'.87E is missing
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 750 – MAL 752 – MAL 754.
-

47(T)*/2024 MALAYSIA – Sarawak – Kuala Rajang – Buoy.

Source: Sarawak Marine Department No. 27(T)/2024.

1. Wk Buoy, *Fl(2)10s*, in position 02°09'.48N, 111°04'.01E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 7215 – MAL 731 – MAL 740.
-

48(T)*/2024 MALAYSIA – Johor – Tanjung Pelepas – Light Buoy.

Source: : Marine Department of Malaysia No. 29(T)/2024.

1. PTP No.6 *Fl(3)R.15s*, in position 01°18'.27N, 103°33'.16E is off station.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 5123 – MAL 5129.
-

67(T)*/2024 MALAYSIA – Perak – Sungai Dinding – Beacon.

Source: KD PERANTAU

1. Batu Beacon, in position 04°14'.60N, 100°36'.93E is destroyed.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 5416 – MAL 5425.
-

71(T)*/2024 MALAYSIA – Perak – Selat Dinding – Light Beacon.

Source: KD PERANTAU.

1. Light Beacon, Fl.G.5s, in position 04°11'.87N, 100°35'.33E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 5425.
-

130(T)*/2024 MALAYSIA – Pahang – Pelabuhan Kuantan – Light Beacon.

Source: Marine Department of Malaysia No. 115(T)/2024.

1. Kuantan Port KP.2, Fl.R.5s15m8M, in position 03°55'.59N, 103°30'.90E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 6400 – MAL 645.
-

218(T)*/2024 MALAYSIA – Sarawak – Pelabuhan Bintulu – Buoy.

Source: Sarawak Marine Department No. 171(T)/2024.

1. Y2 Bouy, Fl.Y.5s, in position 03°16'.02N, 113°03'.54E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 7317.
-

219(T)*/2024 MALAYSIA – Perak – P. Perak – Light Beacon.

Source: Marine Department of Malaysia No. 203(T)/2024.

1. Pulau Perak Light Beacon, Fl(2)10s128m16M, in position 05°41'.59N, 098°56'.23E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 5 – MAL 565 – MAL 58.
-

246(T)*/2024 MALAYSIA – Perak – P. Jarak – Bouy.

Source: RMN STN JARAK.

1. P. Jarak Light Bouy, *Fl.Y.5s*, in position 03°57'.95N, 100°05'.44E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 54 – MAL 540 – MAL 553 – MAL 58.
-

247(T)*/2024 MALAYSIA – Selangor – Batuan Penyu – Buoy.

Source: KD PERANTAU.

1. Penyu Light Bouy, *Fl.G.5s*, in position 03°14'.97N, 101°09'.90E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 5321 – MAL 540.
-

248(T)*/2024 MALAYSIA – Sabah – P. Berhala – Bouy.

Source: KD JERONG.

1. Bouy, *LFl.10s*, in position 05°58'.54N, 118°14'.62E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 8617.
-

249(T)*/2024 MALAYSIA – Pahang – Kuala Endau – Beacon.

Source: Marine Department of Malaysia No. 222(T)/2024.

1. Kuala Endau Beacon, *Fl(2)R.10s10m5M*, in position 02°39'.99N, 103°39'.12E is destroyed.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 625.
-

250(T)*/2024 MALAYSIA – Sabah – P. Tambisan – Light Beacon.

Source: KD JERONG.

1. P. Tambisan Light Beacon, *Fl.Y.5s9m5M*, in position 05°27'.81N, 119°05'.78E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 6 – MAL 860.
-

254(T)*/2024 MALAYSIA – Johor – Pulau Mungging – Racon.

Source: Marine Department of Malaysia No. 214(T)/2024.

1. Pulau Mungging Racon (N), in position 01°21'.72N, 104°17'.88E is off station.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 515 – MAL 6124 – MAL 6147.
-

40(T)*/2025 MALAYSIA – Johor – Tenggaraoh – Light Beacon.

Source: Marine Department of Malaysia No. 15(T)/2025.

1. Tanjung Leman Light Beacon, Fl.G.3s5m5M, in position 02°09'.29N, 104°00'.39E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 625.
-

42(T)*/2025 MALAYSIA – Johor – Pengerang – Light Buoy.

Source: Marine Department of Malaysia No. 271(T)/2024.

1. Isolated danger mark, *Fl(2)10s*, in position 01°17'.68N, 104°11'.09E is off station.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 515 – MAL 6124 – MAL 6147.
-

43*/2025 MALAYSIA – Johor – Teluk Ramunia – Buoy.

Source: Marine Department of Malaysia No. 9(T)/2025 and 21/2025.

1. Lima buoy, *Fl(2)10s*, in position 01°20'.60N, 104°16'.89E is off station and move to 01°20'.58N, 104°16'.87E
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 515 – MAL 6124 – MAL 6147.
-

71(T)*/2025 MALAYSIA – Johor – Tg. Penyusop – Buoy.

Source: Marine Department of Malaysia No. 62(T)/2025.

1. JBB97 Light Buoy, *Fl(2)10s*, in position 01°20'.86N, 104°18'.93E is off station.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 6124.
-

93(T)*/2025 MALAYSIA – Selangor – Tanjung Mahang – Light Beacon.

Source: Marine Department of Malaysia No. 80(T)/2025.

1. Tanjung Mahang light beacon, Iso.R.4s25m8M, in position 02°55'.02N, 101°16'.04E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 5259.
-

141(T)*/2025 MALAYSIA – Sarawak – Kuala Paloh – Buoy.

Source: Sarawak Marine Department No. 78/2025(T).

1. Buoy, Kuala Paloh, *Fl.G.4s*, in position 02°28'.67N, 111°11'.43E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 7257 – MAL 731 – MAL 740.
-

162(T)*/2025 MALAYSIA – Sarawak – Kuala Santubong – Buoy.

Source: Sarawak Marine Department No. 88(T)/2025.

1. Kuala Santubong Buoy, *Fl(2)10s*, in position 01°45'.07N, 110°16'.34E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 723, MAL 731.
-

163(T)*/2025 MALAYSIA – Selangor – Pelabuhan Barat – Beacon.

Source: Marine Department of Malaysia No. 153(T)/2025.

1. Pelabuhan Barat Light Beacon No.25, *Fl(2).R.15s7m8M*, in position 02°58'.52N, 101°18'.48E is destroyed.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 5259.
-

189(T)*/2025 MALAYSIA – Sabah – Terumbu Segama – Buoy.

Source: Marine Department of Malaysia No. 44(T)/2025.

1. Buoy, *Fl(2)8s5M*, in position 05°46'.54N, 118°49'.36E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 8621.
-

191(T)*/2025 MALAYSIA – Sabah – Terumbu Permata – Buoy.

Source: Marine Department of Malaysia No. 45(T)/2025.

1. Buoy *Fl(2)10s*, in position 05°35'.50N, 119°08'.68E is missing.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 860.
-

192(T)*/2025 MALAYSIA – Terengganu – Kuala Besut – Light Buoy.

Source: Marine Department of Malaysia No. 161(T)/2025.

1. Light Buoy *Fl.10s*, in position 05°51'.44N, 102°33'.55E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 664.
-

193(T)*/2025 MALAYSIA – Selangor– Kuala Selat Lumut – Light Buoy.

Source: Marine Department of Malaysia No. 169(T)/2025.

1. Light Buoy *Fl(2)R.10s*, in position 02°52'.40N, 101°15'.36E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 5255 – MAL 5259 – MAL 532.
-

194(T)*/2025 MALAYSIA – Kedah – Kuala Kedah – Beacon.

Source: Marine Department of Malaysia No. 174(T)/2025.

1. Beacon Q.G.5m5M, in position 06°05'.77N, 100°16'.10E is destroyed.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 565.
-

245(T)*/2025 MALAYSIA – Sarawak – Tanjung Po – Buoy.

Source: Sarawak Marine Department No. 154(T)/2025.

1. NO.5 Buoy, *Fl.G.5s*, in position 01°42'.33N, 110°33'.04E is off station, unlit and Move to 01°42'.32N, 110°33'.21E.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 7150.
-

275(T)*/2025 MALAYSIA – Pulau Pinang – Alur Utara – Light Buoy.

Source: Marine Department of Malaysia No. 242(T)/2025.

1. No 2G Buoy, *Fl.G.2s*, in position 05°33'.71N, 100°15'.13E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 5536 – MAL 554.
-

276(T)*/2025 MALAYSIA – Pulau Pinang – Alur Utara – Light Buoy.

Source: Marine Department of Malaysia No. 243(T)/2025.

1. No 3R Buoy, *Fl.R.2s*, in position 05°32'.59N, 100°16'.81E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Chart affected – MAL 5536 – MAL 554.
-

297(T)*/2025 MALAYSIA – Sarawak – Tanjung Baram – Buoy.

Source: Sarawak Marine Department No. 191(T)/2025.

1. Buoy, *Fl.Y.5s*, in position 04°36'.28N, 113°54'.67E is off station and Move to 04°37'.10N, 113°54'.93E.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 750 – MAL 752 – MAL 754.
-

298(T)*/2025 MALAYSIA – Kedah – Alur Utara – Light Buoy.

Source: Marine Department of Malaysia No. 258(T)/2025.

1. Buoy No.3R, *Fl.R.2s*, in position 05°32'.59N, 100°16'.80E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 5536 – MAL 554.
-

299(T)*/2025 MALAYSIA – Kedah – Alur Utara – Light Buoy.

Source: Marine Department of Malaysia No. 259(T)/2025.

1. Buoy No.5R, *Fl.R.2s*, in position 05°30'.66N, 100°19'.36E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 5536 – MAL 554.
-

300(T)*/2025 MALAYSIA – Terengganu – Pulau Perhentian Besar – Light Beacon.

Source: Marine Department of Malaysia No. 267(T)/2025.

1. Light Beacon, Fl.R.4s, in position 05°54'.25N, 102°44'.24E is unlit.
 2. Mariners are advised to navigate with caution in the area.
(WGS84 DATUM)
 3. Charts affected – MAL 6603 – MAL 664 – MAL 68.
-

26. HYDROGRAPHIC REPORTS

- a. Report conveying that could be useful to mariners generally, are always welcome in the National Hydrographic Centre. Such information will be used to improve existing charts, sailing directions and navigational publication, not only in the area Malaysian Charting Responsibility but worldwide.
- b. The type of information most needed concerns safe routes through poorly surveyed waters (with courses and depth where available), anchorages, harbour facilities, conspicuous, navigation aids, obstructions and other dangers that are not correctly or fully charted or described on the chart or in the Sailing Directions.
- c. When reports are received in National Hydrographic Centre, copies are sent to other affected maritime authorities, including the British Admiralty for correctly British charts and Sailing Directions.
- d. Report is accepted in any style or from that best suits the writer. Rough but legible handwritten report are quite accepted able and can be sent. If desired as a Hydrographic Note of which a blank copy, as a printed form, can be found attached to each monthly edition of Malaysian Notice to Mariners. Sketches, maps, diagrams, photographic view, newspaper cutting etc. When attached to reports can be very useful.
- e. Without making the task too arduous, report should include copies of the original observation on which a report is founded, with times courses and speed, bearing, radar distances or measured depths, rather than merely the derived latitudes and longitude or reduced depth.
- f. Most reports records what someone as seen or done. The report should include the name and address of that person, together with mariner's comments on its known or assumed reliability, so that the enquiries can be made when check against other sources.
- g. Mariners who send charts with their reports should ask for replacement to be sent to them, if required.

HYDROGRAPHIC NOTE
(for instructions, see overleaf)

Date : _____
Ref No : _____

Name of ship or address of sender.

General locality _____
Subject _____
Approx position Lat _____ Long _____
Chart Affected _____
Latest Notice to Mariners held _____
Publication affected (Edition No date of latest supplement, page and Light List No etc) _____

Details :-

A replacement copy of Chart No. _____ is required, but see 4 overleaf
Signature of observer/reporter _____

HYDROGRAPHIC NOTE

Forwarding Information for Malaysian Charts and Hydrographic Publications

INSTRUCTION: -

1. Mariners are requested to notify the National Hydrographic Centre, Bandar Armada Putra, Pulau Indah, 42009 PORT KLANG, Selangor, Malaysia, when new or suspected dangers to navigation are discovered, change observed in aids to navigation, or corrections to publications seems to be necessary.

2. This form and its instructions have been designed to help both the sender and the recipient. It should be used, or followed closely, whenever appropriate. Copies of this Form may be obtained gratis from the Hydrographic Directorate at the above address.

3. When **position** is defined by sextant angles or bearings (true or magnetic being specified) more than two should be used in order to provide and check. Distance's observed by radar and the reading of Loran, Decca, etc, should be quoted. However, when there is a series of fixes along a ship course, only the method of fixing and the objects used need be indicated. Latitude and longitude should only be used specifically to position the details when they have been fixed by the astronomical observations and full description of the latter should be given.

4. A cutting from the largest scale chart is the best medium for forwarding details, the alterations and additions being shown thereon in red. When requested, a new copy will be sent in replacement of chart that has been used to forward information, or when extensive observations have involved defacement of the observer's chart. If it is preferred to show the amendments on a tracing of the largest scale chart (rather than on the chart itself) these should be in red as above, but adequate details from the chart must be traced in black ink to enable the amendments to be fitted correctly.

5. When **soundings** are obtained The Mariner's Handbook (NP 100) should be consulted. The echo sounding trace should be marked with times, depths, etc., and forwarded with the report. It is important to state whether the echo sounder is set to register depths below the surface or below the keel; in the latter case the vessel's draught should be given. Time and date should be given in order that corrections for the height of the tide may be made where necessary. The make, name and type of set, together with stylus speed/sound velocity, should also be given.

6. Modern echo sounders frequently register greater depths than the advertised maximum for the set, e.g. with a set whose maximum is 500 metres, a trace appearing at 50 metres may in fact be 550 metres or even 1050 metres. Sounding recorded beyond the set's nominal range usually be recognized by the following:-

- a. the trace being weaker than normal for the depth recorded
- b. the trace passing through the transmission line
- c. the "feathery" nature of trace.

As a check that apparently shoal soundings are not due to echoes beyond the set's nominal range sounding should be continued until reasonable agreement with charted soundings is reached. However, soundings received after one or more rotations of the stylus can still be useful and should be submitted if they show significant differences from charted depth.

7. Reports, which cannot be confirmed or are lacking in certain details should be withheld. Shortcomings should be stressed and any firm expectation of being able to check the information on a succeeding voyage should be mentioned.

8. Reports of **shoal soundings**, uncharted dangers and navigational aids out of order should, at the mariner's discretion, also be made by radio to the nearest coast radio station. The draught of modern tankers is such that any uncharted depth under 30 metres or 15 fathoms may be sufficient importance to justify a radio message.

9. **Port Information** should be forwarded on Form MH 501a together with Form MH 501. Form MH 501a lists the information required for Admiralty Sailing Directions and should be used as an *aide memoire*. Where there is insufficient space on the form an additional sheet should be used.

Note: An acknowledgement of receipt will be sent and the information then used to the best advantage, which may mean immediate action or inclusion in revision in due course. When the Notice to Mariners is issued, the sender's vessel or name is quoted as sometimes happens the information is also received in foreign Notice to Mariners. Further communication should be expected only if the information is of outstanding value or has unusual features.

HYDROGRAPHIC NOTE FOR PORT INFORMATION

(To accompany Form MH 501)

Name of ship or address of sender

Ref

No

Date

1. **NAME OF PORT**

2. **GENERAL REMARKS**

Principal activities and trade
Latest population figures and date
Number of ships or tonnage
handled per year
Maximum size of vessel handled.
Copy of Port Handbook if available

3. **ANCHORAGES**

Designation, depths
holding ground, shelter afforded

4. **PILOTAGE**

Authority for requests.
Embarkation position.
Regulations.

5. **DIRECTIONS**

Entry and berthing information
Tidal Streams.
Navigational aids

6. **TUGS**

Number available and max. hp.

7. **WHARVES**

Names, number or positions.
Lengths.
Depth alongside.
Height above Chart Datum
Facilities available

8. **CARGO HANDLING**

Container, lighters,
Ro-Ro etc.

9. **CRANES**

Brief details and max. capacity

10.	REPAIRS
	Hull, Machinery and underwater. Ship and boat yards. Docking or shipping facilities. Gives sizes of vessels handled or dimensions. Hard and ramps. Divers.
11.	RESCUE AND DISTRESS
	Salvage, lifeboat Coastguard, etc.
12.	SUPPLIES
	Fuel with type and quantities available Fresh water with rate of supply. Provisions.
13.	SERVICES
	Medical De-ratting Consuls. Ship chandlery, compass adjustment, Tank cleaning, hull painting.
14.	COMMUNICATIONS
	Road, rail and air services available. Nearest airport or airfield. Port radio and information service with Frequencies and hours of operating.
15.	PORT AUTHORITY
	Designation, address and telephone number.
16.	SMALL CRAFT FACILITIES
	Information and facilities for small craft (E.g. yachts) visiting the port. Yacht Clubs berth, etc.
17.	VIEWS
	Photographs (where permitted) of the approaches, leading marks, The entrance to the harbor, etc. Picture postcards may also be useful

Signature of observer/reporter.....



Bandar Armada Putra, Pulau Indah
42009 Pelabuhan Klang
Selangor, MALAYSIA
Tel : +603-40160816